

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	47
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE													
STATION	LOCATION	SIGN NUMBER	SIZE	MESSAGE	NUMBER OF POSTS	72000100	72000200	72000300	72400310	72400320	72400330	72800100	73100100
		(MUTCD)	(IN)			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
					(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(EACH)
20+75 (TR320)	LT	R1-1	36 x 36	STOP	1	9.00						19	1
20+75 (TR320)	LT	R6-3	24 x 18	DIVIDED HIGHWAY		3.00							
25+00 (TR 320)	LT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1
1238+18.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1238+18.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1238+50.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1238+50.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1240+50.00	RT	M1-4	30 x 24	136	1	5.00						16	1
1240+50.00	RT	M1-1100	24 x 24	336	1	4.00						16	1
1240+50.00	RT	M3-2	24 x 12	EAST		2.00							
1240+50.00	RT	M3-1	24 x 12	NORTH		2.00							
1240+50.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1240+50.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1242+02.00	LT	W2-2L	30 x 30	SIDE ROAD (SYMBOL)					6.25				
1242+02.00	LT		22 x 30	OAK GROVE CHRISTIAN CHURCH					4.58				
1243+73.00	LT	R3-1100R	24 x 24	RIGHT TURN LANE	1	4.00						16	1
1243+73.00	LT	M6-2R	21 x 15	ARROW		2.19							
1244+50.00	RT	R2-1	36 x 48	SPEED LIMIT 65	1		12.00					17	1
1245+60.00	MEDIAN	R3-1100L	24 x 24	RIGHT TURN LANE	1	4.00						16	1
1245+60.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1247+88.00	LT	W1-2R	30 x 30	CURVE (SYMBOL)					6.25				
1248+50.00	RT	R2-1104	48 x 96	SPEED LIMIT OVER 4 TONS	1			32.00				20	1
1248+60.00	MEDIAN	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						16	
1248+60.00	LT	W2-1	36 x 36	CROSS ROAD (SYMBOL)	1	9.00						16	1
1251+36.00	LT	W14-3	30 x 40	NO PASSING ZONE						8.33			
1253+22.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1253+35.00	MEDIAN	W1-2R	30 x 30	CURVE (SYMBOL)					6.25				
1254+00.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1268+75.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1277+95.00	MEDIAN	W14-3	30 x 40	NO PASSING ZONE						8.33			
1279+06.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1279+06.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1279+65.00	LT	W1-2L	30 x 30	CURVE (SYMBOL)					6.25				
1281+06.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1281+06.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1281+39.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1281+39.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1281+64.00	LT	R6-1L	36 x 12	ONE WAY	1	3.00						14	1
1282+10.00	RT	R6-1L	36 x 12	ONE WAY	1	3.00						14	1
1282+36.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1282+36.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1

DGN: SPEC
 DATE: TIME
 *REF: 01

D6 PROJECT: FILE:

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: DRAWN BY: RG
 DATE: MARCH 10, 2006 CHECKED BY: JAC