SCHEDULE OF QUANTITIES

SIGN SCHEDULE

STATION	LOCATION	SIGN NUMBER	SIZE	MESSAGE	NUMBER OF POSTS	72000100 SIGN PANEL - TYPE 1	72000200 SIGN PANEL - TYPE 2	72000300 SIGN PANEL - TYPE 3	72400310 REMOVE SIGN PANEL - TYPE 1	72400320 REMOVE SIGN PANEL - TYPE 2	72400330 REMOVE SIGN PANEL - TYPE 3	72800100 TELESCOPING STEEL SIGN SUPPORT	73100100 BASE FOR TELESCOPING STEEL SIGN SUPPORT
		(MUTCD)	(IN)		(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(EACH)
1282+67.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1282+67.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1284+67.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1284+67.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1287+43.00	MEDIAN	W1-2R	30 x 30	CURVE (SYMBOL)					6.25				
1290+13.00	LT	W14-3	30 x 40	NO PASSING ZONE						8.33			
1291+65.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1301+09.00	LT	W1-2L	30 x 30	CURVE (SYMBOL)					6.25				
1303+00.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1307+70.00	MEDIAN	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1307+70.00	RT	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1310+70.00	MEDIAN	R3-1100L	24 x 24	LEFT TURN LANE	1	4.00						16	1
1310+70.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1313+85.00	MEDIAN	W2-2L	30 x 30	SIDE ROAD (SYMBOL)					6.25				
1313+94.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1313+94.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1315+94.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1315+94.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1316+27.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1316+27.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
30+87 (TR 358)	LT		30 x 9	288OE					1.88				
30+87 (TR 358)	LT		30 x 9	150ON					1.88				
30+86 (TR 358)	LT	R1-1	30 x 30	STOP					6.25				
31+04 (TR 358)	LT	R6-1L	36 x 12	ONE WAY		3.00							
31+04 (TR 358)	LT	R6-1R	36 x 12	ONE WAY		3.00							
31+04 (TR 358)	LT	R1-1	36 x 36	STOP	1	9.00						19	1
31+04 (TR 358)	LT	R6-3a	24 x 18	DIVIDED HIGHWAY		3.00							
33+61 (TR 358)	LT	W3-1a	30 x 30	STOP AHEAD (SYMBOL)					6.25				
36+04 (TR 358)	LT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1
1316+98.00	RT	R6-1L	36 x 12	ONE WAY	1	3.00						14	1
1317+23.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1317+23.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1317+55.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1317+55.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1319+55.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1319+55.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1320+64.00	LT	W2-2R	30 x 30	SIDE ROAD (SYMBOL)					6.25				
1321+28.00	LT	R3-1100R	24 x 24	RIGHT TURN LANE	1	4.00						16	1
1321+28.00	LT	M6-2R	21 x 15	ARROW		2.19							
1323+22.00	MEDIAN	W11-10	30 x 30	TRUCK CROSSING (SYMBOL)					6.25				
1325+28.00	MEDIAN	W2-2R	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1325+28.00	LT	W2-2R	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC