SCHEDULE OF QUANTITIES

SIGN SCHEDULE

STATION	LOCATION	SIGN NUMBER	SIZE	MESSAGE	NUMBER OF POSTS	72000100 SIGN PANEL - TYPE 1	72000200 SIGN PANEL - TYPE 2	72000300 SIGN PANEL - TYPE 3	72400310 REMOVE SIGN PANEL - TYPE 1	72400320 REMOVE SIGN PANEL - TYPE 2	72400330 REMOVE SIGN PANEL - TYPE 3	72800100 TELESCOPING STEEL SIGN SUPPORT	73100100 BASE FOR TELESCOPING STEEL SIGN SUPPORT
		(MUTCD)	(IN)		(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(EACH)
1372+09.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1374+00.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1379+10.00	MEDIAN	W2-2R	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1379+10.00	RT	W2-2R	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1382+10.00	RT	R3-1100R	24 x 24	RIGHT TURN LANE	1	4.00						16	1
1382+10.00	RT	M6-2R	21 x 15	ARROW		2.19							
1382+32.00	RT	W14-3	30 x 40	NO PASSING ZONE						8.33			
1385+30.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1385+30.00	RT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1387+30.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1387+30.00	RT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1387+63.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1387+63.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1387+93.00	LT	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
1388+17.00	MEDIAN		30 x 9	3000E					1.88				
1388+17.00	MEDIAN		30 x 9	1460N					1.88				
1388+38.00	RT	R1-1	30 x 30	STOP					6.25				
44+00 (TR 221)	RT	W3-1a	36 x 36	STOP AHEAD (SYMBOL)	1	9.00						16	1
49+20 (TR 221)	RT	R6-1L	36 x 12	ONE WAY		3.00							
49+20 (TR 221)	RT	R6-1R	36 x 12	ONE WAY		3.00							
49+20 (TR 221)	RT	R1-1	36 x 36	STOP	1	9.00						19	1
49+20 (TR 221)	RT	R6-3	24 x 18	DIVIDED HIGHWAY		3.00							
1388+62.00	MEDIAN	R6-1L	36 x 12	ONE WAY		3.00							
1388+62.00	MEDIAN	W1-2	36 x 36	YIELD	1	9.00						17	1
1388+90.00	LT	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1388+90.00	MEDIAN	R5-1	36 x 36	DO NOT ENTER	1	9.00						16	1
1390+33.00	RT	W1-2L	30 x 30	CURVE (SYMBOL)					6.25				
1390+90.00	LT	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1390+90.00	MEDIAN	R5-1a	36 x 24	WRONG WAY	1	6.00						15	1
1395+15.00	MEDIAN	R3-1100L	24 x 24	LEFT TURN LANE	1	4.00						16	1
1395+15.00	MEDIAN	M6-2L	21 x 15	ARROW		2.19							
1396+50.00	LT	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1396+50.00	MEDIAN	W2-2L	36 x 36	SIDE ROAD (SYMBOL)	1	9.00						17	1
1397+05.00	MEDIAN	R6-1R	36 x 12	ONE WAY	1	3.00						14	1
					TOTALS	1,254.94	96.00	146.38	217.17	70.00	50.38	2,740.00	165.00
					USE	1,255	96	147	218	70	51	2,740	165

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC