

| | | | | |
|---|---------|-----------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 714 | | CHRISTIAN | 14 | 3 |
| STA. 64+00 TO STA. 206+40 | | | | |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |
| D-6 IL. 48 IMPROVEMENT 2006 | | | | |

SUMMARY OF QUANTITIES

| CODE NO. | SUMMARY OF QUANTITIES PAY ITEM | UNIT | TOTAL QUANTITY | S.N. 011-2507 | | S.N. 011-2512 | | S.N. 011-7055 | | ROADWAY RESURFACING | |
|----------|---|---------|----------------|---|--|---|--|---|--|---|--|
| | | | | ROADWAY F.A.P. 714 80% FEDERAL 20% STATE | STRUCTURE S.N. 011-2507 80% FEDERAL 20% STATE | ROADWAY F.A.P. 714 80% FEDERAL 20% STATE | STRUCTURE S.N. 011-2512 80% FEDERAL 20% STATE | ROADWAY F.A.P. 714 80% FEDERAL 20% STATE | STRUCTURE S.N. 011-7055 80% FEDERAL 20% STATE | ROADWAY F.A.P. 714 80% FEDERAL 20% STATE | PARKING LANES 50% STATE 50% VILLAGE |
| | | | | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | CONSTRUCTION TYPE CODE | |
| | | | | X020-2A | X028-2A | X020-2A | X028-2A | X020-2A | X028-2A | 1000-2A | Y025 |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 29 | 29 | | | | | | | |
| 20200100 | EARTH EXCAVATION | CU. YD. | 1963 | 240 | 272 | | | 292 | | 1159 | |
| 20200500 | EARTH EXCAVATION (WIDENING) | CU. YD. | 119 | 37 | 40 | | | 42 | | | |
| 20400800 | FURNISHED EXCAVATION | CU. YD. | 437 | | 288 | | | 149 | | | |
| 25000200 | SEEDING, CLASS 2 | ACRE | 4.6 | 0.6 | 0.6 | | | 0.5 | | 2.9 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 414 | 54 | 54 | | | 45 | | 261 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 414 | 54 | 54 | | | 45 | | 261 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 414 | 54 | 54 | | | 45 | | 261 | |
| 25000700 | AGRICULTURAL GROUND LIMESTONE | TON | 9.2 | 1.2 | 1.2 | | | 1.0 | | 5.8 | |
| 25100115 | MULCH, METHOD 2 | ACRE | 4.6 | 0.6 | 0.6 | | | 0.5 | | 2.9 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 750 | 60 | 60 | | | 50 | | 580 | |
| 28000300 | TEMPORARY DITCH CHECKS | EACH | 26 | | | | | | | 26 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 5700 | | | | | | | 5700 | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ. YD. | 412 | | | 236 | | | 176 | | |
| 28200200 | FILTER FABRIC | SQ. YD. | 412 | | | 236 | | | 176 | | |
| 31100300 | SUBBASE GRANULAR MATERIAL, TYPE A 4" | SQ. YD. | 651 | 213 | 270 | | | 168 | | | |
| 35100100 | AGGREGATE BASE COURSE, TYPE A | TON | 78 | 78 | | | | | | | |
| 35800100 | PREPARATION OF BASE | SQ. YD. | 84 | | | | | | | 84 | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 71.55 | 0.68 | 0.88 | | | 0.87 | | 67.85 | 1.27 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 286.65 | 1.81 | 2.93 | | | 2.91 | | 279 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | | | | | | | 2 | |
| 40600980 | BITUMINOUS SURFACE REMOVAL - BUTT JOINT | SQ. YD. | 2452 | 54 | | | | | | 2398 | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ. YD. | 193 | | | | | | | 193 | |
| 40600990 | TEMPORARY RAMP | SQ. YD. | 1464 | 62 | | | | | | 1402 | |
| 40800040 | INCIDENTAL BITUMINOUS SURFACING | TON | 260 | | | | | | | 260 | |
| 44000006 | BITUMINOUS SURFACE REMOVAL 1 1/2" | SQ. YD. | 100 | 100 | | | | | | | |
| 44000030 | BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH) | SQ. YD. | 182664 | 717 | 1223 | | | 1321 | | 176056 | 3347 |
| 44000100 | PAVEMENT REMOVAL | SQ. YD. | 561 | 174 | 250 | | | 137 | | | |
| 44001430 | BITUMINOUS SHOULDER REMOVAL | SQ. YD. | 1159 | 314 | 437 | | | 408 | | | |
| 44200104 | PAVEMENT PATCHING, TYPE I, 9 INCH | SQ. YD. | 50 | | | | | | | 50 | |
| 44200108 | PAVEMENT PATCHING, TYPE II, 9 INCH | SQ. YD. | 700 | | | | | | | 700 | |
| 44200112 | PAVEMENT PATCHING, TYPE III, 9 INCH | SQ. YD. | 400 | | | | | | | 400 | |
| 44200114 | PAVEMENT PATCHING, TYPE IV, 9 INCH | SQ. YD. | 400 | | | | | | | 400 | |
| 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | FOOT | 56769 | | 500 | | | 441 | | 55828 | |
| 48101200 | AGGREGATE SHOULDERS TYPE B | TON | 5804 | | 85 | | | 89 | | 5630 | |
| 48202000 | BITUMINOUS SHOULDERS SUPERPAVE | TON | 4959 | 92 | 119 | | | 115 | | 4633 | |

SUMMARY OF QUANTITIES
 F.A.P. ROUTE 714 - IL ROUTE 48
 SECTION D-6 IL. 48 IMPROVEMENT 2006
 CHRISTIAN COUNTY

FILE NAME: COMBIN.D SC. REV. 3/28/05