

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	*	CHRISTIAN	54	4
STA. 64+00 TO STA. 206+40				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* D-6 IL. 48 IMPROVEMENT 2006				

SUMMARY OF QUANTITIES

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	S.N. 011-2507		S.N. 011-2512		S.N. 011-7055		ROADWAY RESURFACING	
				ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-2507 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-2512 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-7055 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	PARKING LANES 50% STATE 50% VILLAGE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	
				X028-2A	X028-2A	X028-2A	X028-2A	X028-2A	X028-2A	1000-2A	Y025
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1				
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1						1		
50300225	CONCRETE STRUCTURES	CU. YD.	93.8		93.8						
50800105	REINFORCEMENT BARS	POUND	51495		7060		30930		13505		
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	310		310						
50901001	STEEL BRIDGE RAIL	FOOT	299.86		114.68		104.32		80.86		
51201400	FURNISHING STEEL PILES HP 10 X 42	FOOT	1284		1284						
51202700	DRIVING STEEL PILES	FOOT	1284		1284						
51203400	TEST PILE STEEL HP 10 X 42	EACH	2		2						
51205200	TEMPORARY SHEET PILING	SQ. FT.	1907				1345		562		
51500100	NAME PLATES	EACH	3		1		1		1		
54003000	CONCRETE BOX CULVERTS	CU. YD.	208.1				127.9		80.2		
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	32							32	
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	52							52	
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	104	104							
54215559	METAL END SECTIONS 24"	EACH	2	2							
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	12	12							
550A0080	STORM SEWERS, CLASS A, TYPE 1 16"	FOOT	30	30							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	70	70							
55100400	STORM SEWER REMOVAL 10"	FOOT	34	34							
55100500	STORM SEWER REMOVAL 12"	FOOT	67	67							
55100800	STORM SEWER REMOVAL 16"	FOOT	56	56							
60209700	CATCH BASINS, TYPE C, SPECIAL, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60220400	MANHOLES, TYPE A, SPECIAL, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
X0325375	MANHOLES, TYPE A, SPECIAL, 9' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	2							2	
*63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1887.5	87.5		575		575		650	
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2							
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	10	2		4		4			
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	18	2		4		4		8	
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	1045			477		468		100	
63300900	VERTICAL ADJUSTMENT OF GUARDRAIL	FOOT	840							840	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	2	2							
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL. MO.	16	4		4		4		4	
67100100	MOBILIZATION	L. SUM	1	0.25		0.25		0.25		0.25	

\* SPECIALTY ITEMS

Rev.

SUMMARY OF QUANTITIES  
F.A.P. ROUTE 714 - IL ROUTE 48  
SECTION D-6 IL. 48 IMPROVEMENT 2006  
CHRISTIAN COUNTY