

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714		CHRISTIAN	94	5
STA. 64+00 TO STA. 206+40				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
D-6 IL. 48 IMPROVEMENT 2006				

SUMMARY OF QUANTITIES

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	S.N. 011-2507		S.N. 011-2512		S.N. 011-7055		ROADWAY RESURFACING	
				ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-2507 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-2512 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	STRUCTURE S.N. 011-7055 80% FEDERAL 20% STATE	ROADWAY F.A.P. 714 80% FEDERAL 20% STATE	PARKING LANES 50% STATE 50% VILLAGE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	
				X02B-2A	X02B-2A	X02B-2A	X02B-2A	X02B-2A	X02B-2A	1000-2A	4025
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1							1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1	0.25		0.25		0.25		0.25	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1	0.34		0.33		0.33			
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L. SUM	1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0.25		0.25		0.25		0.25	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321, SPECIAL	EACH	3	1		1		1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DAY	12	3		3		3		3	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	3	1		1		1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11854	130		160		154		11410	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	137561	898		1342		1318		134003	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	72	24		24		24			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO. FT.	3237	397		479		469		1892	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1400	525		450		425			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1200	325		450		425			
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	137561	898		1342		1318		134003	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	723	5		7		7		704	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	62	10		18		18		16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	18	2		4		4		8	
* 78202000	TERMINAL MARKER - POST MOUNTED	EACH	2	2							
78300100	PAVEMENT MARKING REMOVAL	SO. FT.	216	64		76		76			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	722	5		7		7		703	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO. FT.	478		478						
X0324118	GRANULAR CULVERT BACKFILL	CU. YD.	439		214		118		107		
X0325283	BITUMINOUS SHOULDER REMOVAL AND REPLACEMENT 8"	SO. YD.	500							500	
X3550700	BITUMINOUS BASE COURSE SUPERPAVE 10"	SO. YD.	2717	783		990		944			
X3550810	BITUMINOUS BASE COURSE SUPERPAVE 1 1/2"	SO. YD.	580	190		240		150			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIXTURE C, N50	TON	12464	90		120		117		11715	422
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	6043	67		60		58		5858	
X7200201	WIDTH RESTRICTION SIGNING	L. SUM	1	0.34		0.33		0.33			
XX005496	TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)	EACH	2	2							
Z0002600	BAR SPLICERS	EACH	191		24		92		75		
⊙ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	4		2		2			
⊙ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	2		2		2			
Z0073100	TEMPORARY SHORING	EACH	2			1		1			
X0325376	THREE SIDED PRECAST CONCRETE STRUCTURES, 25' x 6'-2"	FOOT	43		43						

⊙ SFTY-3H
* SPECIALTY ITEMS

Rev.

SUMMARY OF QUANTITIES
F.A.P. ROUTE 714 - IL ROUTE 48
SECTION D-6 IL. 48 IMPROVEMENT 2006
CHRISTIAN COUNTY