

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	*	CHRISTIAN	94	11
STA. 64+00 TO STA. 206+40				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* D-6 IL. 48 IMPROVEMENT 2006				

PAVEMENT SCHEDULE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	BITUMINOUS BINDER THICKNESS (INCH)	BITUMINOUS SURFACE THICKNESS (INCH)	BITUMINOUS SURFACE REMOVAL (VAR. DEPTH) (SQ. YD.)	LEVELING BINDER SUPER N50 (TON)	BITUMINOUS CONCRETE SURFACE CSE. SUPERPAVE (TON)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	BITUMINOUS SURFACE REMOVAL BUTT JOINT (SQ. YD.)
STA. 64+00 TO STA. 392+00	32,800	22	0.75	1.5	80,177.78	3,367.47	6,734.93	30.47	160.36	74
STA. 392+00 TO STA. 399+53	753	22	0.75	1.5	1,840.67	77.31	154.62	0.70	3.68	
CULVERT OMISSION (S.N. 011-2507)										
STA. 399+53 TO STA. 403+17										
STA. 403+17 TO STA. 407+00	383	22	0.75	1.5	936.22	39.32	78.64	0.36	1.87	
STA. 407+00 TO STA. 411+42	442	22	0.75	1.5	1,080.44	45.38	90.76	0.41	2.16	
STA. 411+42 TO STA. 413+00	158	22	0.75	1.5	386.22	16.22	32.44	0.15	0.77	
STA. 413+00 TO STA. 418+11	511	22	0.75	1.5	1,249.11	52.46	104.92	0.47	2.50	
STA. 418+11 TO STA. 429+82	1171	22	0.75	1.5	2,862.44	120.22	240.44	1.09	5.72	
STA. 429+82 TO STA. 431+92	210	22	0.75	1.5	513.33	21.56	43.12	0.20	1.03	
CULVERT (S.N. 011-2505)										
STA. 431+92 TO STA. 432+72	80	24	0.75	1.5	213.33	896	17.92	0.08	0.43	
STA. 432+72 TO STA. 443+57.80	1,085.80	22	0.75	1.5	2,654.18	111.48	222.96	1.01	5.31	
STATION EQUATION - STA. 443+57.80 BACK = STA. 0+04.32 AHEAD										
STA. 0+04.32 TO STA. 0+06	1.68	22	0.75	1.5	4.11	0.17	0.34	0.00	0.01	
CULVERT OMISSION (S.N. 011-2512)										
STA. 0+06 TO STA. 5+96										
STA. 5+96 TO STA. 108+00.40	10,204.40	22	0.75	1.5	24,944.09	1,047.65	2,095.30	9.48	49.89	
CULVERT OMISSION (S.N. 011-7055)										
STA. 108+00.40 TO STA. 113+96.60										
STA. 113+96.60 TO STA. 206+40	9,243.40	22	0.75	1.5	22,594.98	948.99	1,897.98	8.59	45.19	74
TOTAL					139,456.90	5,857.19	11,714.37	53.01	278.92	148
PAY ITEM TOTAL					139,457	5858	11,715	53.01	279	148

SHOULDER SCHEDULE

LOCATION	LENGTH (FOOT)	AGGREGATE SHOULDERS, WIDTH (FOOT)	BITUMINOUS SHOULDERS, WIDTH (FOOT)	AGGREGATE SHOULDERS, TYPE B (TON)	BITUMINOUS SURFACE REMOVAL (VAR. DEPTH) (SQ. YD.)	BITUMINOUS SHOULDERS, SUPERPAVE (TON)	BITUMINOUS MATERIALS PRIME COAT (TON)	BITUMINOUS CONCRETE SURFACE CSE. SUPERPAVE (TON)
SHOULDER ITEMS								
STA. 64+00 TO STA. 392+00	32,800	4' LT. & RT.	3' LT. & RT.	3,320.49	21,866.67	2,755.20	8.31	
STA. 392+00 TO STA. 399+53	753	4' LT. & RT.	3' LT. & RT.	76.23	502.00	63.25	0.19	
CULVERT OMISSION (S.N. 011-2507)								
STA. 399+53 TO STA. 403+17								
STA. 403+17 TO STA. 407+00	383	4' LT. & RT.	3' LT. & RT.	38.77	255.33	32.17	0.10	
STA. 407+00 TO STA. 411+42	442	4' LT. & RT.	3' LT. & RT.	44.75	294.67	37.13	0.11	
STA. 411+42 TO STA. 413+00	158	6' LT., 4' RT.	3' RT.	19.99	52.67	6.64	0.02	
STA. 413+00 TO STA. 418+11	511	6' LT.		38.80				
STA. 429+82 TO STA. 430+00	18	4' LT. & RT.	3' LT. & RT.	1.82	12.00	1.51	0.00	
STA. 430+00 TO STA. 430+85	85	4' LT. & RT.	3' LT. & 5' RT.	8.60	75.56	9.52	0.03	
STA. 430+85 TO STA. 431+92	107	4' RT.	6' LT. & 5' RT.	5.42	130.78	16.48	0.05	
CULVERT (S.N. 011-2505)								
STA. 431+92 TO STA. 432+72	80	---	8' LT. & RT.	---	142.22	17.92	0.05	
STA. 432+72 TO STA. 434+17	145	4' RT.	6' LT. & 5' RT.	7.34	177.22	22.33	0.07	
STA. 434+17 TO STA. 443+57.80	940.80	4' LT. & RT.	3' LT. & RT.	95.42	677.20	87.81	0.24	
STATION EQUATION - STA. 443+57.80 BACK = STA. 0+04.32 AHEAD								
STA. 0+04.32 TO STA. 0+06	1.68	4' LT. & RT.	3' LT. & RT.	0.17	1.12	0.14	0.00	
CULVERT OMISSION (S.N. 011-2512)								
STA. 0+06 TO STA. 5+96								
STA. 5+96 TO STA. 108+00.40	10,204.40	4' LT. & RT.	3' LT. & RT.	1,033.04	6,802.93	857.17	2.59	
CULVERT OMISSION (S.N. 011-7055)								
STA. 108+00.40 TO STA. 113+96.60								
STA. 113+96.60 TO STA. 206+40	9,243.40	4' LT. & RT.	3' LT. & RT.	935.75	6,162.27	776.45	2.34	
TOTAL				5626.42	37,102.63	4,674.93	14.10	
SIDEROAD QUANTITIES TO BE SUBTRACTED								
TOTAL ADJUSTED QUANTITY					504	42.34	0.19	
PAY ITEM TOTAL					5627	36,599	4,633	13.91
STONINGTON PARKING LANE ITEMS								
STA. 413+00 TO STA. 418+11	511		10' TO 10'-6" RT.		581.97		0.22	73.33
STA. 418+11 TO STA. 429+82	1171	-	11' LT., 10' TO 10'-6" RT.	-	2,764.86		1.05	348.37
TOTAL					3,346.83		1.27	421.70
PAY ITEM TOTAL					3,347		1.27	422

SCHEDULE OF QUANTITIES
 F.A.P. ROUTE 714 - IL. ROUTE 48
 SECTION D-6 IL. 48 IMPROVEMENT 2006
 CHRISTIAN COUNTY