

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714		CHRISTIAN	94	26
STA. 401+00 TO STA. 401+71				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
D-6 IL. 48 IMPROVEMENT 2006				

GUARDRAIL SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 2 (EACH)	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL) (EACH)	TRAFFIC BARRIER TERMINAL TYPE 6A (EACH)	STEEL BRIDGE RAIL (FOOT)
STAGE I						
STA. 400+60.5, 52' RT. TO STA. 400+70, 41.5' RT. (S. WEST STREET)			1			
STA. 400+70, 41.5' RT. TO STA. 400+21.5 33' RT. (S. WEST STREET)		12.5		1		
STA. 400+70, 41.5' RT. TO STA. 401+06.83 RT.						
STA. 401+06.83 TO STA. 401+64.17 RT.					1	57.34
STA. 401+64.17 TO STA. 401+95.57 RT.						
STA. 401+95.57 TO STA. 402+33.07 RT.		37.5				
STA. 402+33.07 TO STA. 402+83.07 RT.	1					
STAGE II						
STA. 399+87.93 TO STA. 400+37.93 LT.	1					
STA. 400+37.93 TO STA. 400+75.43 LT.		37.5				
STA. 400+75.43 TO STA. 401+06.83 LT.					1	
STA. 401+06.83 TO STA. 401+64.17 LT.						57.34
STA. 401+64.17 TO STA. 401+87, 38.5' LT.				1		
STA. 401+87, 38.5' LT. TO STA. 401+92, 53' LT. (WEST STREET)			1			
TOTAL	2	87.5	2	2	2	114.68

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FT.)	PAVEMENT MK. REMOVAL		TEMP. PVMT. MK. LINE - 5"		SHORT TERM PVMT. MARKING LINE - 5"		WORK ZONE PVMT. MARKING REMOVAL		PAINT PVMT. MK. LINE - 5"		TEMPORARY PAINT PAVEMENT MARKING LINE-24"
		WHITE (SQ. FT.)	YELLOW (SQ. FT.)	WHITE (FT.)	YELLOW (FT.)	WHITE (FT.)	YELLOW (FT.)	WHITE (SQ. FT.)	YELLOW (SQ. FT.)	WHITE (SQ. FT.)	YELLOW (SQ. FT.)	WHITE (FOOT)
STA. 397+95.8 TO STA. 401+00 (C)	304.2		34									
STA. 401+71 TO STA. 404+44.5 (C)	273.5		30									
STA. 399+53 TO STA. 403+17 LT. (EDGE)	364			364				153		364		
STA. 397+95.8 TO STA. 404+44.5 C	648.7				170						170	
STA. 399+53 TO STA. 403+17 RT. (EDGE)	364			364				153		364		
STA. 397+95.8 TO STA. 404+44.5 C	648.7					*130		43				
STA. 397+95.8 (STOP BAR) RT.	12							24				12
STA. 404+44.5 (STOP BAR) LT.	12							24				12
TOTAL		64	898	130	397	898	24					

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS.
 * 10% OF TOTAL LENGTH FOR SHORT-TERM PAVEMENT MARKING

SCHEDULE GUARDRAIL & TERMINAL MARKERS

LOCATION	GUARDRAIL MARKERS TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)	TERMINAL MARKER POST MOUNTED (EACH)
STA. 400+00 LT.	1		
STA. 400+50 LT.	1		
STA. 400+65 RT. (S. WEST ST.)	1		
STA. 401+00 LT.	1		
STA. 401+00 RT. (S. WEST ST.)	1		
STA. 401+75 LT. (WEST ST.)	1		
STA. 401+75 RT.	1		
STA. 401+95 (WEST ST.)	1		
STA. 402+25 RT.	1		
STA. 402+75 RT.	1		
STA. 399+87.93 LT.		1	
STA. 402+45.57 RT.		1	
STA. 400+60, 53' RT.			1
STA. 401+93, 53' LT.			1
TOTAL	10	2	2

SCHEDULE GRANULAR CULVERT BACKFILL

LOCATION	QUANTITY (CU. YD.)
STA. 401+00 TO STA. 401+21.83 & STA. 401+49.17 TO STA. 401+71	202
STA. 401+21.83 TO STA. 401+49.17	12
TOTAL	214

SCHEDULE SUB-BASE GRANULAR MATERIAL TYPE A 4"

LOCATION	QUANTITY (SQ. YD.)
STA. 401+00 TO STA. 401+71	213
TOTAL	213

SCHEDULE BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION	QUANTITY (SQ. YD.)
S. WEST STREET	54
TOTAL	54

SCHEDULE BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)

LOCATION	QUANTITY (SQ. YD.)
STA. 399+53 TO STA. 401+00	360
STA. 401+71 TO STA. 403+17	357
TOTAL	717

SCHEDULE AGGREGATE PRIME COAT

LOCATION	QUANTITY (TON)
STA. 399+53 TO STA. 401+00	0.72
STA. 401+00 TO STA. 401+71	0.38
STA. 401+71 TO STA. 403+17	0.71
TOTAL	1.81

SCHEDULE RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)
STA. 399+53 TO STA. 403+17 LT.	5
TOTAL	5

SCHEDULE BITUMINOUS SURFACE REMOVAL

LOCATION	QUANTITY (SQ. YD.)
WEST STREET	100
TOTAL	100

SCHEDULE PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STA. 401+00 TO STA. 401+71	221
TOTAL	221

SCHEDULE BITUMINOUS SHOULDER REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STA. 399+53 TO STA. 403+17 LT. & RT.	243
STA. 401+00 TO STA. 401+71 9' SHLDR. LT. ST. I	71
TOTAL	314

SCHEDULE AGGREGATE BASE COURSE TYPE A

LOCATION	QUANTITY (TON)
WEST STREET	78
TOTAL	78

SCHEDULE PIPE CULVERTS, CLASS D, TYPE 1 24"

LOCATION	QUANTITY (FOOT)
STA. 401+41 TO STA. 402+45 LT.	104
TOTAL	104

SCHEDULE STORM SEWER REMOVAL 10"

LOCATION	QUANTITY (FOOT)
STA. 401+22, 48' RT. TO STA. 401+27, 31' RT.	17
STA. 401+27, 31' RT. TO STA. 401+32, 47' RT.	17
TOTAL	34

SCHEDULE MANHOLES, TYPE A SPECIAL, 9' DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION	QUANTITY (EACH)
STA. 401+27, 40.5' RT.	1
TOTAL	1

SCHEDULE MANHOLES, TYPE A SPECIAL, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION	QUANTITY (EACH)
STA. 401+47, 31' LT.	1
TOTAL	1

SCHEDULE STORM SEWER REMOVAL 12"

LOCATION	QUANTITY (FOOT)
STA. 401+27, 31' RT. TO STA. 401+47, 33' LT.	67
TOTAL	67

SCHEDULE STORM SEWER REMOVAL 16"

LOCATION	QUANTITY (FOOT)
STA. 400+93, 42' RT. TO STA. 401+35, 7' RT.	56
TOTAL	56

SCHEDULE STORM SEWERS, CLASS A, TYPE 1, 10"

LOCATION	QUANTITY (FOOT)
STA. 401+22, 48' RT. TO STA. 401+24, 43' RT.	6
STA. 401+30, 42' RT. TO STA. 401+32, 47' RT.	6
TOTAL	12

SCHEDULE STORM SEWERS, CLASS A, TYPE 1, 16"

LOCATION	QUANTITY (FOOT)
STA. 400+94, 41' RT. TO STA. 401+24, 39' RT.	30
TOTAL	30

SCHEDULE RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	QUANTITY (EACH)
STA. 399+75 (C)	1
STA. 400+55 (C)	1
STA. 401+35 (C)	1
STA. 402+15 (C)	1
STA. 402+95 (C)	1
TOTAL	5

SCHEDULE STORM SEWERS, CLASS A, TYPE 1, 24"

LOCATION	QUANTITY (FOOT)
STA. 401+28, 37' RT. TO STA. 401+47, 30' LT.	70
TOTAL	70

SCHEDULE CATCH BASINS, TYPE C, SPECIAL, TYPE 1 FRAME, CLOSED LID

LOCATION	QUANTITY (EACH)
STA. 400+93, 41' RT.	1
TOTAL	1

SCHEDULE FURNISHING & ERECTING R.O.W. MARKERS

LOCATION	QUANTITY (EACH)
STA. 400+74.60, 74.72' RT.	1
STA. 401+59.60, 36.48' RT.	1
TOTAL	2

SCHEDULE TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	QUANTITY (UNITS)
STA. 401+01.5, 51' RT.	11
STA. 401+22.5, 45' RT.	12
STA. 401+43, 37' RT.	6
TOTAL	29

FILE NAME: 05 REV. 3/27/06

QUANTITY SCHEDULES
 IL. ROUTE 48 OVER BUCKHART CREEK
 F.A.P. ROUTE 714 - SECTION
 D-6 IL. 48 IMPROVEMENT 2006
 CHRISTIAN COUNTY
 STA. 401+35.50
 S.N. 011-2507