

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SHEET 2 OF 6  
CONTRACT 72A40

INDEX OF SHEETS

1	COVER SHEET	STANDARDS	630001-06
2	GENERAL NOTES, SIGNATURES, & SUMMARY OF QUANTITIES		631032-02
3	GUARDRAIL SCHEDULE		630301-03
4	EXISTING BRIDGE PLAN		701006-02
5	EXISTING BRIDGE RAIL PLAN		701011-01
6	TYPE T-1 STEEL RAILING		701201-02
			701301-02
			701311-02
			702001-06

GENERAL NOTES

THE PRICE OF TRAFFIC CONTROL ITEMS SHALL BE INCLUDED IN THE BID PRICE FOR STEEL PLATE BEAM GUARDRAIL AS PER ARTICLE 701.05 IN THE STANDARD SPECIFICATIONS

STEEL BRIDGE RAIL POSTS SHALL REMAIN IN PLACE, ONLY THE BRIDGE RAIL SHALL BE REPLACED. ANY NECESSARY MODIFICATIONS TO THE NEW BRIDGE RAIL SHALL BE INCLUDED IN THE BID PRICE FOR REMOVE AND REPLACE STEEL BRIDGE RAIL, TYPE T-1 (SPECIAL).

SUMMARY OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY	SFTY-3J 100% STATE HANCOCK
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1887.5	1887.5
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	6
63200310	GUARDRAIL REMOVAL	FOOT	2267	2267
67100100	MOBILIZATION	L SUM	1	1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	28	28
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6
X0325363	REMOVE AND REPLACE STEEL BRIDGE RAIL, TYPE T-1 (SPECIAL)	FOOT	179.4	179.4

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>March 10</u> 20 <u>06</u>	<u>Sam J. Hunt</u> ENGINEER OF OPERATIONS
EXAMINED <u>March 15</u> 20 <u>06</u>	<u>W. R. J.</u> ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED <u>MARCH 20</u> 20 <u>06</u>	<u>William E. Masten</u> ENGINEER OF PROGRAM DEVELOPMENT

INDEX OF SHEETS, GENERAL  
NOTES, SIGNATURES, &  
SUMMARY OF QUANTITIES

DATE	
BY	
NO.	
PLAT	
NOTEBOOK	