



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2006

SUBJECT: Route FAP 95/FAU 8379 (ILL 33/US 45)  
Project HS-000S(487)  
Section D7 Signal Modernization 2006-1  
Effingham County  
Contract No. 74087  
Item No. 20, June 16, 2006 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 2 of the Schedule of Prices.
2. Revised sheets 2 and 3 of the Plans.
3. Added sheet 12 to the Plans.
4. Revised page 2 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine  
Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Christine Reed, Region 4, District 7; Roger Driskell;  
Estimates; Design & Environment File

DB/cab

Special attention is called to Articles 107.09, 107.14 and 107.15 of the Standard Specifications for Road and Bridge Construction, the following Highway Standards and Special Details relating to traffic control, and these Special Provisions.

Highway Standards:

702001 701006 701606 701701 701801

The existing streets shall be kept open to traffic at all times except when the actual construction operations require closing a portion of the roadway. At no time shall more than one-half of the existing pavement width be closed. Two-way traffic shall be provided during non-working hours.

Traffic Control shall be in accordance with the traffic control standards and special drawings in the plans except as follows:

1. Standard 701006 shall be used when at any time any vehicle, equipment, workers or their activities will encroach in an area closer than 4.6m (15 ft.), but not closer than 0.6m (2 ft.) to the edge of a traffic lane. Examples of this type of construction include concrete foundations and sidewalk construction. This traffic control and protection shall be considered incidental to the contract.
2. Standard 701606 shall be used for any lane closures required with two-way multi-lane traffic. Examples of the types of construction for this project include Traffic Signal Head removal and installation and Mast Arm installation. This traffic control and protection will be paid for the contract lump sum price for TRAFFIC CONTROL AND PROTECTION, STANDARD 701606.
3. Standard 701701 shall be used for any lane closures at a multi-lane intersection. Examples of the types of construction for this project include Traffic Signal Head removal and installation. This traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION, STANDARD 701701.
4. Standard 701801 shall be used for any sidewalk closures required. This traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION, STANDARD 701801.

The Engineer will determine the required traffic control for any operation not covered above.

Revised 6/5/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 74087

State Job # - C-97-046-05  
 PPS NBR - 7-82870-0000  
 County Name - EFFINGHAM- -  
 Code - 49 - -  
 District - 7 - -  
 Section Number - D7 SIGNAL MODERNIZATION 2006-1

Project Number  
 HS-000S/487/

Route  
 FAP 95  
 FAU 8379

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
42000500	PCC PVT 10	SQ YD	18.000					
42001200	PAVEMENT FABRIC	SQ YD	18.000					
42400100	PC CONC SIDEWALK 4	SQ FT	60.000					
44000600	SIDEWALK REM	SQ FT	60.000					
44003100	MEDIAN REMOVAL	SQ FT	189.000					
60622400	CONC MED TSM6.06	SQ FT	27.000					
67100100	MOBILIZATION	L SUM	1.000					
* DELETED								
70102625	TR CONT & PROT 701606	L SUM	1.000					
70102635	TR CONT & PROT 701701	L SUM	1.000					
70102640	TR CONT & PROT 701801	L SUM	1.000					
78005100	EPOXY PVT MK LTR-SYM	SQ FT	427.000					
78005110	EPOXY PVT MK LINE 4	FOOT	1,212.000					
78005130	EPOXY PVT MK LINE 6	FOOT	2,050.000					
78005150	EPOXY PVT MK LINE 12	FOOT	101.000					
			* REVISED : MAY 31, 2006					