

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	EFFINGHAM	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED. 7.5% STATE 2.5% CITY Y031-IF BANKER ST. & FAYETTE AVE.	90% FED. 5% STATE 5% CITY Y031-IF MAPLE ST. & FAYETTE AVE.	Y031-IF RICKLEMAN AVE. & U.S. RTE. 45
* 42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	18	18		
* 42001200	PAVEMENT FABRIC	SQ YD	18	18		
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	60		60	
* 44000600	SIDEWALK REMOVAL	SQ FT	60		60	
* 44003100	MEDIAN REMOVAL	SQ FT	189	189		
* 60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	27	27		
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	427	427		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1212	1212		
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	2050	2050		
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	101	101		
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	191	191		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	693	693		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	25		25	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	25		25	
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	54	54		
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1			1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	318		318	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	317		317	
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	1		1	
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	2		2	
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1	
87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1	1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	13.5		13.5	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15	15		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED. 7.5% STATE 2.5% CITY Y031-IF BANKER ST. & FAYETTE AVE.	90% FED. 5% STATE 5% CITY Y031-IF MAPLE ST. & FAYETTE AVE.	Y031-IF RICKLEMAN AVE. & U.S. RTE. 45
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	31	17	14	
88600100	DETECTOR LOOP, TYPE I	FOOT	166	166		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	12	6	6	
89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	2		2	
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2	1	1	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	437		437	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	1	1	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1		1	
X0323336	LED SIGNAL FACE RETROFIT, RED BALL	EACH	12	12		
X0323337	LED SIGNAL FACE RETROFIT, GREEN BALL	EACH	12	12		
X0323418	LED SIGNAL FACE RETROFIT, YELLOW BALL	EACH	12	12		
X0323419	LED SIGNAL FACE RETROFIT, YELLOW ARROW	EACH	7	7		
X0323420	LED SIGNAL FACE RETROFIT, GREEN ARROW	EACH	7	7		
X0323421	LED SIGNAL FACE RETROFIT, WALK SIGNAL	EACH	6	6		
X0323422	LED SIGNAL FACE RETROFIT, DONT WALK SIGNAL	EACH	6	6		
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6		6	
X8801345	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2	2		
X8801350	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	3	3		
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2		2	
X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2		2	
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	4		4	
* Z0075300	TIE BARS	EACH	38	38		

* SPECIALTY ITEMS

PLOT DATE = 3/24/2006
FILE NAME = PFILE1
SCALE = INCHES
USER NAME = gawpax

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY