

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	(107, 107Z) 1-2	EFFINGHAM	12	2
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 74129

GENERAL NOTES

- THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2002; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.
- THE WORK INCLUDED IN THIS SECTION CONSISTS OF THE FINAL PAVEMENT MARKINGS ON APPROXIMATELY 1.98 MILES OF F.A.P. ROUTE 774 (IL RTE 32/33).
- THE PROPOSED PROJECT BEGINS 0.23 MILES WEST OF THE INTERSECTION OF IL ROUTE 32/33 AND NAZARENE RD AT STA. 942+50.00 AND EXTENDS IN AN EASTERLY DIRECTION TO A STATION EQUATION AT STA. 1039+00.00(BK) = STA. 39+00.00(AH), THEN CONTINUES TO STA. 46+80.05 EAST OF FORD AVE IN EFFINGHAM, IL, A TOTAL DISTANCE OF 1.98 MILES.
- RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS, THE PLANS, AND AS DETERMINED BY THE ENGINEER. THE FINAL PAVEMENT MARKINGS SHALL BE PLACED PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS. ESTIMATED QUANTITIES:

CRYSTAL (MONODIRECTIONAL)	467 EACH
CRYSTAL (BIDIRECTIONAL)	0 EACH
AMBER (MONODIRECTIONAL)	449 EACH
AMBER (BIDIRECTIONAL)	36 EACH
TOTAL	952 EACH
- THIS PROJECT SHALL BE COORDINATED WITH CONSTRUCTION OF THE ROADWAY PROJECT IN THE SAME AREA. THE CONTRACTOR SHALL NOT START THIS PROJECT WITHOUT THE APPROVAL OF THE DISTRICT 7 PROJECT IMPLEMENTATION ENGINEER.

HIGHWAY STANDARDS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NUMBER: 12

STANDARD NO.	DESCRIPTION
000001-04	STANDARD SYMBOLS, ABBREVIATION, AND PATTERNS
701426-02	LANE CLOSURE MULTILANE INTERMITTENT OR MOVING OPERATIONS FOR SPEEDS \geq 45 MPH
702001-00	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

REVISIONS	
NAME	DATE
DRM	3/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES AND
HIGHWAY STANDARDS

DRAWN BY MLO
CHECKED BY SJK
DATE 5/05