

CONTRACT NO. 74130

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	801.FED./201.STATE	
				1000-2A	Y030-IE
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	33	33	
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	52	52	
20200100	EARTH EXCAVATION	CU YD	25,165	25,165	
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	68	68	
20800150	TRENCH BACKFILL	CU YD	237	237	
25000210	SEEDING, CLASS 2A	ACRE	7.0	7.0	
25000312	SEEDING, CLASS 4A	ACRE	3.0	3.0	
25000320	SEEDING, CLASS 5	ACRE	3.0	3.0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	900	900	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	900	900	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	900	900	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	20.0	20.0	
25100120	MULCH, METHOD 2	TON	20.0	20.0	
25100630	EROSION CONTROL BLANKET	SQ YD	162	162	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,000	1,000	
28000300	TEMPORARY DITCH CHECKS	EACH	50	50	
28000400	PERIMETER EROSION BARRIER	FOOT	75	75	
28000500	INLET AND PIPE PROTECTION	EACH	15	15	
28100107	STONE RIPRAP, CLASS A4	SQ YD	602	602	
28200200	FILTER FABRIC	SQ YD	602	602	
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	33,589	33,589	
30201500	LIME	TON	846.5	846.5	
3100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1,989	1,989	
3101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1,916	1,916	
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	1,368	1,368	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	119	119	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	165	165	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21,958	21,958	
40600300	AGGREGATE (PRIME COAT)	TON	134.4	134.4	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	617	617	
40600990	TEMPORARY RAMP	SQ YD	707	707	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	91	91	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	652	652	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	23,099	23,099	
44000100	PAVEMENT REMOVAL	SQ YD	4,002	4,002	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	308	308	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	2,288	2,288	
44002805	ISLAND REMOVAL	SQ FT	86	86	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	8,546	8,546	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	8,151	8,151	
50105200	REMOVE EXISTING CULVERTS	EACH	22	22	
50300225	CONCRETE STRUCTURES	CU YD	54.6	54.6	
50800105	REINFORCEMENT BARS	POUND	8,964	8,964	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	52	52	
54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	52	52	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	183	183	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	128	128	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	218	218	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	801.FED./201.STATE	
				1000-2A	Y030-IE
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	403	403	
542D0226	PIPE CULVERTS, CLASS D, TYPE 1 21"	FOOT	77	77	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	103	103	
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	47	47	
542D5473	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 18"	FOOT	30	30	
542JA024	PIPE CULVERTS, CLASS A 24" (JACKED)	FOOT	154	154	
54207162	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL EQUIVALENT ROUND-SIZE 27"	FOOT	105	105	
54213450	END SECTIONS 15"	EACH	12	12	
54213453	END SECTIONS 18"	EACH	16	16	
54213456	END SECTIONS 21"	EACH	4	4	
54213459	END SECTIONS 24"	EACH	6	6	
54213465	END SECTIONS 30"	EACH	2	2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2	
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2	
54214722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, ELLIPTICAL EQUIVALENT ROUND-SIZE 27"	EACH	2	2	
55101200	STORM SEWER REMOVAL 24"	FOOT	116	116	
55101600	STORM SEWER REMOVAL 36"	FOOT	195	195	
55101900	STORM SEWER REMOVAL 48"	FOOT	309	309	
60218300	MANHOLES, TYPE A, 4"-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1	
60500040	REMOVING MANHOLES	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	192	192	
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	1,246	1,246	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	35	35	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	8	8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	7	7	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	39	39	
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	1	1	
70104495	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 2	EACH	1	1	
70104500	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 3	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,632	5,632	
70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	530.4	530.4	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48,535	48,535	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,979	3,979	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,951	3,951	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	43	43	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	36	36	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	49,444	49,444	
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1,770	1,770	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24,527	24,527	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	530.4	530.4	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	48,535	48,535	
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	3,979	3,979	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	3,951	3,951	
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	43	43	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	753	753	

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 SHEET 1 OF 2  
 DATE 8/02  
 DRAWN BY ASB  
 CHECKED BY SJK