F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	107 WRS-2, L	EFFINGHAM	127	12
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 74130

REMOVE EXISTING CULVERTS

LOCATION	STATION	OFFSET	EACH
MAINLINE	552+40.00	LT	1
MAINLINE	891+00.00	RT	1
MAINLINE	891+22.08	LT	1
MAINLINE	894+70.00	RT	1
MAINLINE	896+54.55	LT	1
MAINLINE	904+00.00	LT	1
MAINLINE	904+30.49	RT	1
MAINLINE	910+06.27	RT	1
MAINLINE	913+90.65	LT	1
MAINLINE	913+87.84	RT	1
MAINLINE	918+51.20	RT	1
MAINLINE	940+31.82	LT	1
MAINLINE	940+56.13	RT	2
MAINLINE	940+77.10	LT	1
1700TH AVE.	217+92.98	-	1
1700TH AVE.	218+36.44	-	1
1700TH AVE.	230+48.00	-	1
1700TH AVE.	230+90.56	RT	1
LAKE SARA RD.	60+98.00	LT	1
LAKE SARA RD.	62+50.00	LT	1
LAKE SARA RD.	65+60.00	RT	1
		TOTAL	22

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
539+45.17	263.10' RT	1
539+50.53	272.42' RT	1
540+39.16	219.96' RT	1
541+86.60	182.34' RT	1
542+50.00	40.00' LT	1
542+50.00	50.00' LT	1
544+14.54	106.00' RT	1
544+14.81	50.00' LT	1
556+64.94	70.00' LT	1
894+56.43	235.99' LT	1
895+00.00	70.00' LT	1
895+49.05	85.00' LT	1
896+20.43	155.02' LT	1
896+54.48	176.01' LT	1
897+15.96	75.00' LT	1
897+77.00	100.00' RT	1
898+57.19	336.04' RT	1
898+62.07	333.16' RT	1
899+00.00	75.00' LT	1
900+00.00	95.00' LT	1
900+25.00	100.00' RT	1
902+00.00	95.00' LT	1
902+50.00	75.00' RT	1
903+50.00	75.00' LT	1
906+73.50	75.00' LT	1
906+73.50	75.00' RT	1
911+43.50	75.00' LT	1
911+43.50	75.00' RT	1
913+60.59	75.00' LT	1
914+20.59	75.00' LT	1
916+00.00	75.00' LT	1
924+00.00	60.00' LT	1
933+00.00	75.00' LT	1
937+00.00	75.00' LT	1
940+01.41	85.00' LT	1
	TOTAL	35

RELOCATE EXISTING MAILBOX

LOCATION	STATION	OFFSET	EACH
MAINLINE	910+33.72	RT	1
MAINLINE	914+06.23	RT	1
IL RTE 32	50+18.59	LT	1
LAKE SARA	62+26.08	LT	1
		TOTAL	4

REMOVE RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
542+49.38	RT	1
895+69.01	LT	1
895+94.36	LT	1
895+98.63	LT	1
896+23.85	RT	1
897+18.46	RT	1
904+14.65	RT	1
904+64.71	LT	1
905+14.67	LT	1
	TOTAL	9

BITUMINOUS BASE COURSE, SUPERPAVE, 8"

LOCATION	STATION TO STATION		OFFSET	SQ. YD.
LAKE SARA	60+00.00	61+92.49	RT	182
LAKE SARA	61+92.49	62+66.06	RT	143
LAKE SARA	62+66.06	63+80.70	RT	370
LAKE SARA	62+73.13	63+61.14	LT	30
			TOTAL	725

(SEE RURAL ENTRANCE SCHEDULE FOR REMAINING QUANTITIES)

BITUMINOUS BASE COURSE, SUPERPAVE, 9½"

LOCATION	STATION TO STATION		OFFSET	SQ. YD.
IL. RTE. 32	53+01.78	55+83.37	LT&RT	1866
	51+67.70	53+01.78	RT	60
ISLAND	551+60.76	551+70.27	LT	3
			TOTAL	1929

BITUMINOUS BASE COURSE, SUPERPAVE, 11¾"

STATION TO STATION		OFFSET	SQ. YD.
541+93.85	545+54.95	LT&RT	200
545+54.95	550+00.00	LT&RT	594
550+00.00	551+74.79	LT&RT	156
551+74.79	559+19.18	LT	1166
551+74.79	559+19.18	RT	331
884+96.78	886+00.00	LT&RT	230
886+00.00	896+43.01	LT&RT	2437
896+43.01	906+73.50	LT	1680
896+43.01	906+73.50	RT	1544
906+73.50	911+43.50	LT&RT	1880
911+43.50	942+50.00	LT&RT	12426
		TOTAL	22644

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70

LOCATION	STATION TO STATION		OFFSET	TONS
MAINLINE	541+93.85	942+50.00	LT&RT	5123
LAKE SARA	60+00.00	63+80.70	LT&RT	193
1700TH AVE.	217+00.00	222+39.79	LT&RT	121
1700TH AVE.	224+88.76	228+98.27	LT&RT	71
1000TH ST.	66+16.05	67+60.00	LT&RT	32
			TOTAL	5540

(SEE RURAL ENTRANCE SCHEDULE FOR REMAINING QUANTITIES)

POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90

LOCATION	STATION TO STATION		OFFSET	TONS
IL. RTE. 32	49+90.00	55+83.37	LT&RT	325

LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70

LOCATION	STATION TO STATION		OFFSET	TONS
MAINLINE	541+93.85	942+50.00	LT&RT	980
1700TH AVE.	217+00.00	228+98.27	LT&RT	127
1000TH ST.	66+16.05	67+60.00	LT&RT	24
			TOTAL	1131

LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N90

LOCATION	STATION TO STATION		OFFSET	TONS
IL. RTE. 32	49+90.00	53+01.78	LT&RT	179

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 2 OF 2

DRAWN BY ASB
DATE 03/03 CHECKED BY SJK