

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	107 WRS-2, L	EFFINGHAM	127	13
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 74130

EARTHWORK STAGE I

OFFSET	LOCATION	STATION TO	STATION	EARTH EXCAVATION (CUT) CU YD	*EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT (FILL) CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD
RT	MAIN LINE	541+93.85	942+50.00	9,380	7,035	4,506	2,529
LT & RT	1700th AVE	216+50.00	231+30.00	775	581	1,282	-701
LT & RT	IL RTE 32	49+65.00	55+00.00	995	746	437	309
LT & RT	LAKE SARA RD	59+75.00	63+80.00	485	364	886	-522
STAGE I TOTAL				11,635	8,726	7,111	1,615
EARTHWORK STAGE II							
				CU YD	CU YD	CU YD	CU YD
LT	MAIN LINE	541+93.85	942+50.00	13,260	9,945	4,712	5,233
LT & RT	1000th ST	65+30.00	67+85.00	175	131	1	130
LT & RT	STONERIDGE DR	76+64.62	71+25.00	40	30	1	29
LT & RT	1075th ST	76+00.00	76+80.00	55	41	3	38
STAGE II TOTAL				13,530	10,147	4,717	5,430
GRAND TOTAL				25,165	18,873	11,828	7,045

*EARTH EXCAVATION MULTIPLIED BY SHRINKAGE FACTOR (1 - 0.25 = 0.75)

SEEDING

STATION TO	STATION	OFFSET	SEEDING CLASS 2A ACRE	SEEDING CLASS 4A ACRE	SEEDING CLASS 5 ACRE	NITROGEN FERTILIZER POUND	PHOSPHOROUS FERTILIZER POUND	POTASSIUM FERTILIZER POUND	AGRICULTURAL GROUND LIMESTONE TON	MULCH METHOD 2 TON	TEMPORARY EROSION CONTROL SEEDING POUND
541+93.82	942+50.00	LT&RT	7.0	3.0	3.0	900	900	900	20.0	20.0	1,000

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		EARTHWORK AND SEEDING SCHEDULE

DATE 8/02
DRAWN BY MLO
CHECKED BY TGC