

CONTRACT NO. 74130

ENTRANCE CULVERT SCHEDULE

PROPOSED MATERIAL	TYPE	SIDE/STATION	EXISTING CULVERT SIZE	PIPE CULVERT, CLASS A, TYPE I	PIPE CULVERT, CLASS D					END SECTIONS				PRC FLARED END SECTIONS
					TYPE I					15"	18"	21"	24"	
					24"	15"	18"	21"	24"					
FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	
AGG	FE	RT/ 891+01.17	15"Ø			30					2			
AGG	CE	LT/ 891+22.08	15"Ø					41				2		
CONC	CE	RT/ 894+30.00	18"Ø			68					2			
AGG	CE	LT/ 904+04.27	15"Ø			56					2			
AGG	FE	RT/ 904+30.49	15"Ø					36				2		
EARTH	FE	LT/ 907+25.00	N/A			30					2			
AGG	CE	RT/ 910+06.27	15"Ø			51					2			
AGG	CE	RT/ 913+87.84	15"Ø			57					2			
EARTH	FE	RT/ 918+51.20	15"Ø			39					2			
EARTH	FE	RT/ 926+50.00	N/A							30		2		
EARTH	FE	LT/ 932+90.00	N/A			37					2			
EARTH	FE	RT/ 934+20.00	N/A							33		2		
EARTH	FE	RT/ 941+00.00	N/A							40		2		
CONC	PE	LT/ 50+35.00 IL RTE 32	N/A			50					2			
AGG	PE	RT/ 230+90.56 1700TH AVE	12"Ø			30					2			
AGG	FE	RT/ 66+35.00 1000TH ST	N/A			30					2			
AGG	CE	LT/ 60+98.00 LAKE SARA RD	24"Ø	95										1
TOTAL				95	140	338	77	103	8	14	4	6		1

PUBLIC ROAD CULVERT SCHEDULE

PUBLIC ROAD/SIDE/STATION	EXISTING CULVERT SIZE	PIPE CULVERT, CLASS A, TYPE I	TY 1, RC ELLIPT EQ RND	PIPE CULVERT, CLASS D, TYPE I				PRC FLARED END SECTIONS		END SECTIONS				
				15"	18"	18" EQUIV ROUND	30"	27" ELLIPT EQ RND	36"	15"	18"	18" EQUIV ROUND	30"	
														FT
1700TH AVE RT/217+92.98	15"Ø			30							2			
1700TH AVE RT/218+36.44	18"Ø					30							2	
1700TH AVE LT/230+48.06	12"Ø			48							2			
1000TH ST LT/896+43.01	20"X32" ELLIPT.		105						2					
LAKE SARA RD RT/896+48.57	30"X45" ELLIPT.	128							2					
STONERIDGE DR LT/913+90.65	24"Ø						47							2
1075TH ST LT/940+77.10	15"Ø					65							2	
TOTAL		128	105	78	65	30	47	2	2	4	2	2	2	2

\*DGN-SPEC\*  
\*DATE\*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ENTRANCE PIPE CULVERT SCHEDULES

DATE 8/02  
DRAWN BY MLO  
CHECKED BY SJK