

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|--------------|-----------|------------------|-----------|
| 774 | 107 WRS-2, L | EFFINGHAM | 127 | 60 |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

CONTRACT NO. 74130

SCHEDULE OF QUANTITIES

ELECTRIC SERVICE INSTALLATION (80400100)

| STATION | EACH |
|-----------------------|------|
| 56' LT STA. 955+53.55 | 1 |

LIGHT POLE, FIBERGLASS, 45 FT. M.H., TENON MOUNT (X8300640)

| STATION | EACH |
|-----------------------|------|
| 45' LT STA. 955+25.08 | 1 |

CONDUIT IN TRENCH, 2" DIA., PVC (81012600)

| STATION | STATION | FEET |
|-----------------------|-----------------------|------|
| 45' LT STA. 955+25.08 | 51' LT STA. 955+60.40 | 33 |
| 56' LT STA. 955+53.55 | 51' LT STA. 955+60.40 | 4 |
| | | 37 |

LIGHT POLE FOUNDATION, 24" DIAMETER (83600200)

| STATION | FEET |
|-----------------------|------|
| 45' LT STA. 955+25.08 | 8 |

TRENCH AND BACKFILL FOR ELECTRICAL WORK (81500200)

| STATION | STATION | FEET |
|-----------------------|-----------------------|------|
| 45' LT STA. 955+25.08 | 51' LT STA. 955+60.40 | 33 |
| 56' LT STA. 955+53.55 | 51' LT STA. 955+60.40 | 4 |
| | | 37 |

BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT (83800505)

| STATION | EACH |
|-----------------------|------|
| 45' LT STA. 955+25.08 | 4 |

ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #10 (81702110)

| STATION | STATION | FEET | SLACK | NO. | FEET |
|-----------------------|-----------------------|------|-------|-----|------|
| 45' LT STA. 955+25.08 | 51' LT STA. 955+60.40 | 33 | 5 | 3 | 114 |

ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #6 (81702130)

| STATION | STATION | FEET | SLACK | NO. | FEET |
|-----------------------|-----------------------|------|-------|-----|------|
| 56' LT STA. 955+53.55 | 51' LT STA. 955+60.40 | 29 | 6 | 3 | 105 |

LUMINAIRE, SODIUM VAPOR, MULTI MOUNT, 250 WATT (82103900)

| STATION | EACH |
|-----------------------|------|
| 45' LT STA. 955+25.08 | 1 |

LIGHTING CONTROLLER TYPE CB-RCS 60 AMP - 240 VOLT (82500510)

| STATION | EACH |
|-----------------------|------|
| 51' LT STA. 955+60.40 | 1 |

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---|
| NAME | DATE | |
| | | NAZARENE ROAD LIGHTING PLANS SHEET 6 OF 6 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

DATE 8/02

DRAWN BY ASB
CHECKED BY BWD

4/19/06