

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-BRS-1	ST. CLAIR	39	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		URBAN - 90% FEDERAL / 10% STATE						
				I-64 MAINLINE I000	SILVER CREEK SN 082-0186 SFTY-2A	SILVER CREEK SN 082-0187 SFTY-2A	SILVER CREEK SN 082-0188 SFTY-2A	SILVER CREEK SN 082-0189 SFTY-2A	TR 222 SN 082-0185 SFTY-2A	
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	62							
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	91		44	47				
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	82				41	41		
X4066570	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	8856	8856						
X4066660	<del>POLYMERIZED</del> BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	9963	9963						
<del>40800040</del>	INCIDENTAL BITUMINOUS SURFACING	TON	53	53						
X4420046	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	17	17						
X4420051	CLASS A PATCHES, TYPE II, 11 1/4 INCH	SQ YD	72	72						
X4420052	CLASS A PATCHES, TYPE III, 11 1/4 INCH	SQ YD	21	21						
X4420054	CLASS A PATCHES, TYPE IV, 11 1/4 INCH	SQ YD	159	159						
X4421000	PARTIAL DEPTH PATCHING	TON	355	355						
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	3164	3164						
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12	12						
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	3				3			
Z0075310	TIE BARS, 3/4"	EACH	109	109						
<del>Z0016000</del>	<del>DECK SLAB REPAIR (FD)</del>	<del>SQ YD</del>	<del>3</del>							
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HR</del>	<del>1,500</del>	<del>1,500</del>		3				

PLOT DATE = 3/30/2006  
 FILE NAME = c:\p\o\p\eta\eta\0405\plan\0405.p  
 PLOT SCALE = 48:9999 / IN.  
 REFERENCE = #REF#