F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	*	MADISON	452	57
STA. 33+950.000		TO STA. 34+300.000		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* SECTION 60-14
SECTION 60-14-18
CONTRACT NO. 76321

WILLIAM B. NAGY, ETAL.

MATCH LINE STATION 33+950.000

MATCH LINE STATION 34+300.000

PROPOSED ROW & A.C. LINE

PROPOSED PIPE CULVERT, 900mm

CONSTRUCTION LIMITS

CURVE P ALNMNT-5

STA. 34+245.000
PROPOSED PIPE CULVERT
CLASS A, TYPE 2, 900mm
MEDIAN INLET, STD. 604106
PIPE TEE, 900mm W/ 900mm RISER
STD. 542606 ONE END CAPPED
END SECTIONS, 900mm
USFL 168.393
DSFL 167.954

℄ RAMP *1

℄ RAMP *2

STA. 34+100.000
PROPOSED PIPE CULVERT
CLASS A, TYPE 1, 600mm
INLET BOX, TYPE C, STD. 542511
END SECTIONS, 600mm
USFL 166.801
DSFL 166.757

SECTION LINE

10 m 0 20 m
1 : 500

PROPOSED PROFILE GRADE LINE

EXISTING GROUND LINE

+1.77%

USFL=163.216
DSFL=161.905
PROPOSED PIPE CULVERT, 600mm

USFL=166.801
DSFL=166.757
PROPOSED PIPE CULVERT, 600mm

USFL=168.393
DSFL=167.954
PROPOSED PIPE CULVERT, 900mm

+275.000
170.569

SPECIAL DITCH RT.
-0.92%

+275.000
170.134

SPECIAL DITCH LT.
-4.22%

+300.000
170.339

	33+950	33+975	34+000	34+025	34+050	34+075	34+100	34+125	34+150	34+175	34+200	34+225	34+250	34+275	34+300
	162.887	163.877	164.569	165.035	165.504	167.420	166.693	167.491	167.802	168.269	168.744	169.347	169.389	169.109	169.119
	165.413	165.855	166.298	166.741	167.183	167.626	168.068	168.511	168.953	169.396	169.839	170.281	170.724	171.166	171.609

175.0 / 170.0 / 165.0 / 160.0

DRAINAGE PLAN & PROFILE, FAP ROUTE 310, STA. 33+950.000 TO STA. 34+300.000

FINAL SURVEY NOTE BOOK	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		

ORIGINAL SURVEY NOTE BOOK	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		