

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
304	GRS-2	JERSEY	12	2
STA. _____		TO STA. _____		
CONTRACT NUMBER: 76942				

GENERAL NOTES

THE STANDARDS AND REVISIONS NUMBERS LISTED APPLY TO THIS PROJECT.

IF ANY SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR RESURFACED OVER. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.

THE THICKNESS OF BITUMINOUS MIXTURES SHOWN IN THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT.

MIXTURE USE:	SURFACE	LEVEL BINDER	BINDER/FULL DEPTH PATCH	INCIDENTAL SURF	PARTIAL DEPTH PATCH	SHOULDERS	TOP LIFT SHOULDERS
AC/PG:	PG 64-22	Pg 64-22	PG 64-22	PG 64-22	PG 64-22	PG 58-22	PG 58-22
RAP % (MAX):	10%	10%	15%	10%	10%	30%	30%
DESIGN AIR VOIDS:	4.0% @ Ndes=70	4.0% @ Ndes=70	4.0% @ Ndes=70	4.0% @ Ndes=70	4.0% @ Ndes=70	2.0% @ Ndes=30	**2.0% @ Ndes=30
MIX COMPOSITION:							
FRICITION AGG:	MIXTURE "C"	MIXTURE "C"	MIXTURE "B"	MIXTURE "C"	MIXTURE "C"	BAM	BAM

**TOP LIFT SHOULDERS - DESIGN THIS MIX AT 2.0% VOIDS AND ADD ASPHALT TO REDUCE VOIDS TO 1.5%.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.

ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS.

UTILITY	ABOVE GROUND	BELOW GROUND
* FRONTIER COMMUNICATIONS COMPANY		X

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY *. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

"ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT ENTRANCES AND SIDE STREETS WHERE WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLORASCENT ORANGE. THIS WORK SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION.

SHORT-TERM PAVEMENT MARKINGS SHALL BE APPLIED TO THE BINDER, PRIMED, AND FINAL BITUMINOUS SURFACE. A QUANTITY FOR TEMPORARY PAVEMENT MARKING EQUAL TO THE AMOUNT OF PERMANENT PAVEMENT MARKING HAS BEEN ADDED TO THE PLANS.

ALL TEMPORARY PAVEMENT MARKING WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING AND TOPO SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS MADE BY DESIGN PERSONNEL. BOTH SHALL BE ASSUMED TO BE APPROXIMATE.

FLAGMEN SHALL BE PRESENT DURING ALL CLOSURE HOURS, INCLUDING LUNCH HOUR, AND NO ADDITIONAL COMPENSATION SHALL BE APPLIED.

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, HIGHWAY STANDARDS, MIXTURE REQUIREMENTS, GENERAL NOTES, AND COMMITMENTS
3. SUMMARY OF QUANTITIES
4. EXISTING TYPICAL SECTION
5. PROPOSED TYPICAL SECTION
- 6.-7. SCHEDULES OF QUANTITIES
8. LOCATION MAP
- 9.-10. INTERSECTION DETAILS
11. BUTT JOINT DETAILS
12. PAVEMENT MARKING DETAILS

LIST OF STANDARDS

000001-04	701011-01
001006	701301-02
001001	701306-01
353001-02	701311-02
442201-01	701326-02
606001-02	701336-04
606301-02	702001-06
701001-01	780001-01
701006-02	781001-02

COMMITMENT

NONE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**GENERAL NOTES, STANDARDS
INDEX OF SHEETS, COMMITMENT**
FAP ROUTE 304 (IL 16/IL 100)
SECTION GRS-2
JERSEY COUNTY

DRAWN BY:

PLOT DATE: 3/29/2006

DATE	BY	REVISIONS

REVISIONS
DATE
BY
REVISIONS