F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 83757

	CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE I000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X071-2A	PAVEMENT MARKING SFTY-1D	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	192	192						
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	468	468						
*	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	144	144						
*	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	144	144						
*	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	144	144						
	20200100	EARTH EXCAVATION	CU YD	13,915	13,915						
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,393	2,393						
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	2,797	1,329		1,468				
	20800150	TRENCH BACKFILL	CU YD	1,495	1,495						
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,887	3,887						
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,255	6,255						
	21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	10,864	10,864						
*	25000100	SEEDING, CLASS 1	ACRE	1.4	1.4						
*	25000110	SEEDING, CLASS 1A	ACRE	0.2	0.2						
*	25000312	SEEDING, CLASS 4A	ACRE	1	1						
*	25000314	SEEDING, CLASS 4B	ACRE	1	1						
*	25000324	SEEDING, CLASS 5B	ACRE	1	1						
*	25100115	MULCH, METHOD 2	ACRE	2.7	2.7						
	25100630	EROSION CONTROL BLANKET	SQ YD	11,115	11,115						
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	73	73						
	28000300	TEMPORARY DITCH CHECKS	EACH	3	3						
	28000400	PERIMETER EROSION BARRIER	FOOT	1,746	1,746						
	28000510	INLET FILTERS	EACH	2	2						
	28100105	STONE RIPRAP, CLASS A3	SQ YD	235	235						
	28100107	STONE RIPRAP, CLASS A4	SQ YD	145			145				
	28200200	FILTER FABRIC	SQ YD	380	235		145				
	28300100	FIBER MAT	SQ YD	300	300						
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	6,868	6,321	547					
	35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	708	708						
	42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	514		514					
	42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	506			506				
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	73		73					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8209	8134					75	
	44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	2,637	2637						
	44000100	PAVEMENT REMOVAL	SQ YD	5,192	5,192						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,075	1,075						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,256	3,256						

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

SUMMARY OF QUANTITIES I

SCALE: NTS
DRAWN BY: PFR
DATE: 07/01/05
CHECKED BY: KPS

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0600

..\TEGONE.DGN,..\SUQQNRB.DGN,..\SUQQNRB.DGN
9-08-2005,11:27:37 S:\DOCUMENT\023280\CIVIL\DGN\SUQQNL5.DGN
ROSSPF