F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 83757

CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE I000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X071-2A	PAVEMENT MARKING SFTY-10	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	
44000600	SIDEWALK REMOVAL	SQ FT	5,672	5,597					75	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	63	63						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1				
50200100	STRUCTURE EXCAVATION	CU YD	1,019			1,019				
50200300	COFFERDAM EXCAVATION	CU YD	28			28				
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	201			201				
50200500	COFFERDAMS	EACH	6			6				
50300225	CONCRETE STRUCTURES	CU YD	568.8			568.8				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	361			361				
50300260	BRIDGE DECK GROOVING	SQ YD	802			802				
50300265	SEAL COAT CONCRETE	CU YD	35			35				
50300300	PROTECTIVE COAT	SQ YD	1,124			1,124				
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24			24				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1				
50500505	STUD SHEAR CONNECTORS	EACH	4,752			4,752				
50800105	REINFORCEMENT BARS	POUND	19,850			19,850				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	112,440			112,440				
50900105	ALUMINUM RAILING, TYPE L	FOOT	111			111				
51205200	TEMPORARY SHEET PILING	SQ FT	1,240	1,240						
51500100	NAME PLATES	EACH	1			1				
54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	203	203						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1						
54215547	METAL END SECTIONS 12"	EACH	9	9						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	14	14						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	161	161						
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	586	586						
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	39	39						
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	214	214						
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	10	10						
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	40	40						
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	28	28						
550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	98	98						
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	103	103						
550A0820	STORM SEWERS, CLASS A, TYPE 3 72"	FOOT	282	282						
55100500	STORM SEWER REMOVAL 12"	FOOT	218	218						
55100700	STORM SEWER REMOVAL 15"	FOOT	62	62						
55101100	STORM SEWER REMOVAL 21"	FOOT	70	70						

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

SUMMARY OF QUANTITIES II

SCALE: NTS
DATE: 07/01/05

DRAWN BY: PFR
CHECKED BY: KPS

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE 312/616-0600

..\TTBQ0NZ.DGN,..\S0000NRB.DGN,..\S0000NRB.DGN
S:\DOCUMENT\023280\CIVIL\DGN\S0000NL6.DGN
9-08-2005, 8:27:36
ROSSPF