

F.A.U. R/F	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 83757

CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE I000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X091-2A	PAVEMENT MARKING SFTY-10	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
55101200	STORM SEWER REMOVAL 24"	FOOT	33	33					
55101600	STORM SEWER REMOVAL 36"	FOOT	65	65					
55101800	STORM SEWER REMOVAL 42"	FOOT	181	181					
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	53	53					
56103100	DUCTILE IRON WATER MAIN 8"	FOOT	458	458					
56108900	TAPPING VALVES AND SLEEVES 8"	EACH	1	1					
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	446			446			
60107700	PIPE UNDERDRAINS 6"	FOOT	26	26					
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	2	2					
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2					
60201505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE B-24 FRAME AND GRATE	EACH	16	16					
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4					
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	6	6					
60249000	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 5 FRAME, CLOSED LID	EACH	1	1					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4					
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3					
60500040	REMOVING MANHOLES	EACH	1	1					
60500050	REMOVING CATCH BASINS	EACH	18	18					
60600105	CONCRETE CURB	FOOT	131		131				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	42.5		42.5				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3263.5		3263.5				
60618760	CONCRETE MEDIAN, TYPE M-4.12	SO FT	636		636				
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	648		648				
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SO FT	877		877				
60624600	CORRUGATED MEDIAN	SO FT	22		22				
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1					
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1					
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1					
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1					
63100201	TRAFFIC BARRIER TERMINAL, TYPE 5 (SPECIAL)	EACH	2	2					
63200310	GUARDRAIL REMOVAL	FOOT	270	270					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					

\*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX  
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK  
WILL COUNTY

**SUMMARY OF QUANTITIES III**

SCALE: NTS  
DATE: 07/01/05

DRAWN BY: PFR  
CHECKED BY: KPS

**TENG**

TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
255 N. MICHIGAN AVE., CHICAGO, IL 60601  
TELEPHONE: 312.587.0000

ROSSPF

ATTENTION: BORN, \SUD000R6.DGN, \SUD000R6.DGN  
9-08-2005, 12:27:36  
S:\DOCUMENT\022800\CIVIL\UD00\CIVIL\UD00\SUD000R6.DGN