

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 83757				

SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING - LINE 24'							TOTAL	213
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	COLOR/TYPE	FEET	
6+03.47	37.12	LT	6+21.57	33.80	LT		18	
9+25.00	10.25	LT	9+25.00	17.64	RT		28	
10+75.00	46.66	LT	10+75.00	0.25	LT		46	
10+79.17	10.25	RT	10+79.17	22.25	RT		12	
11+29.03	10.25	RT	11+29.03	22.25	RT		12	
11+62.80	10.25	RT	11+62.80	22.25	RT		12	
18+23.12	61.74	RT	18+32.54	58.72	RT		10	
21+44.50	36.61	RT	21+54.00	36.65	RT		10	
299+23.95	2.50	LT	299+23.95	28.14	RT		31	
300+51.66	5.00	RT	300+51.66	28.89	LT		34	

SCHEDULE OF THERMOPLASTIC PAVEMENT MARKINGS, LETTERS & SYMBOLS				TOTAL	352.4
APPX. STATION	SIDE	MARKING TYPE		SQ FT	
6+89.00	LT	ONLY		20.8	
7+13.00	LT	ARROW		15.6	
8+87.00	LT	ONLY		20.8	
9+11.00	LT	ARROW		15.6	
10+89.00	LT	ARROW		15.6	
11+13.00	LT	ONLY		20.8	
10+89.00	LT	ARROW		15.6	
11+13.00	LT	ONLY		20.8	
11+04.00	RT	RR XING		61.2	
16+02.00	CTR	ARROW		15.6	
16+27.00	CTR	ONLY		20.8	
19+07.00	CTR	ARROW		15.6	
19+30.00	CTR	ONLY		20.8	
297+22.00	CTR	ONLY		20.8	
297+48.00	CTR	ARROW		15.6	
301+43.00	CTR	ARROW		15.6	
301+67.00	CTR	ONLY		20.8	

SCHEDULE OF PREFORMED PLASTIC PAVEMENT MARKINGS - LINE 4"							TOTAL	297
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	COLOR/TYPE	FEET	
11+99.00	22.25	RT	13+21.00	22.25	RT	WHITE	122	
13+21.00	22.25	RT	14+35.00	21.07	RT	WHITE	114	
14+11.42	22.02	LT	14+35.00	21.30	LT	DOT WHT	6	
12+91.72	11.25	LT	13+21.00	11.25	LT	DOT WHT	7	
13+21.00	11.25	LT	14+23.72	9.66	LT	DOT WHT	26	
14+23.72	9.66	LT	14+35.00	9.37	LT	DBL YEL	23	

SCHEDULE OF PREFORMED PLASTIC PAVEMENT MARKINGS - LINE 6"							TOTAL	795
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	COLOR/TYPE	FEET	
STRIPING ACROSS RR -- SB LANES								
12+09.00	23.25	LT	13+21.00	23.25	LT	WHITE	510	
13+21.00	23.25	LT	14+11.42	22.02	LT	WHITE	112	
12+09.00	11.25	LT	12+91.72	11.25	LT	WHITE	90	

SCHEDULE OF PREFORMED PLASTIC PAVEMENT MARKINGS - LINE 12"							TOTAL	59	
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	COLOR/TYPE	FEET		
11+99.00	36.25	RT	12+13.00	22.25	RT	WHITE	20		
13+03.07	38.25	RT	13+19.07	22.25	RT	WHITE	23		
14+16.85	28.22	RT	14+22.08	21.32	RT	WHITE	9		
PAINTED MEDIAN, STA. 14+23 TO 14+35							YELLOW	8	

SCHEDULE OF PREFORMED PLASTIC PAVEMENT MARKINGS - LINE 24"							TOTAL	91
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	COLOR/TYPE	FEET	
12+09.00	0.25	LT	12+09.00	36.25	LT	WHITE	36	
13+61.30	5.21	LT	13+62.98	34.78	LT	WHITE	30	
14+10.71	8.73	LT	14+10.27	33.81	LT	WHITE	25	

SCHEDULE OF PREFORMED PLASTIC PAVEMENT MARKINGS, LETTERS & SYMBOLS				TOTAL	195.2
APPX. STATION	SIDE	MARKING TYPE		SQ FT	
12+66.00	LT	ARROW		15.6	
12+91.00	LT	ONLY		20.8	
13+27.00	LT	ARROW		15.6	
13+50.00	LT	ONLY		20.8	
13+86.00	LT	RR XING		61.2	
13+86.00	LT	RR XING		61.2	

SCHEDULE OF TREES				
TREE TYPE	STATION	OFFSET	SIDE	GENERAL LOCATION
SK	13+75.00	60.00	RT	PARKWAY
WA	14+25.00	80.00	RT	PARKWAY
MG	15+64.55	56.00	RT	PARKWAY
GL	15+94.00	56.00	RT	PARKWAY
SK	16+00.00	45.00	LT	PARKWAY
SH	16+23.50	56.00	RT	PARKWAY
WA	16+30.00	45.00	LT	PARKWAY
MG	16+60.00	45.00	LT	PARKWAY
NM	16+78.50	56.00	RT	PARKWAY
GL	16+90.00	45.00	LT	PARKWAY
SG	17+11.50	56.00	RT	PARKWAY
RL	17+66.00	55.00	RT	PARKWAY
NM	16+27.11	766.03	LT	COMP STORAGE
SG	16+57.69	760.50	LT	COMP STORAGE
RL	16+73.14	782.24	LT	COMP STORAGE
SK	17+03.39	775.43	LT	COMP STORAGE
WA	17+22.20	795.22	LT	COMP STORAGE
MG	17+47.53	805.91	LT	COMP STORAGE
RL	18+49.18	341.68	LT	COMP STORAGE
SG	19+20.07	347.22	LT	COMP STORAGE
NM	19+81.33	359.23	LT	COMP STORAGE
SH	20+13.42	350.91	LT	COMP STORAGE
MG	20+29.61	376.82	LT	COMP STORAGE
GL	20+39.17	350.88	LT	COMP STORAGE
GL	20+51.79	802.48	LT	COMP STORAGE
WA	20+60.42	369.58	LT	COMP STORAGE
SK	20+60.45	399.58	LT	COMP STORAGE
RL	20+60.49	429.58	LT	COMP STORAGE
SG	20+60.53	459.58	LT	COMP STORAGE
NM	20+60.56	489.58	LT	COMP STORAGE
SH	20+60.60	519.58	LT	COMP STORAGE
GL	20+60.64	549.58	LT	COMP STORAGE
MG	20+60.67	579.58	LT	COMP STORAGE
WA	20+60.71	609.58	LT	COMP STORAGE
SK	20+60.75	639.58	LT	COMP STORAGE
RL	20+60.78	669.58	LT	COMP STORAGE
SG	20+60.82	699.58	LT	COMP STORAGE
NM	20+60.86	729.58	LT	COMP STORAGE
SH	20+60.90	759.58	LT	COMP STORAGE

LEGEND & TOTALS		
GL	GREENSPIRE LITTLE LEAF LINDEN	5 TOTAL
MG	MARSHALL'S SEEDLESS GREEN ASH	5 TOTAL
NM	NORWAY MAPLE	5 TOTAL
RL	REDMOND AMERICAN LINDEN	5 TOTAL
SG	SUMMIT GREEN ASH	5 TOTAL
SH	SHADEMASTER THORNLESS COMMON HONEYLOCUST	4 TOTAL
SK	SKYLINE THORNLESS COMMON HONEYLOCUST	5 TOTAL
WA	AUTUMN PURPLE WHITE ASH	5 TOTAL


REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

SCHEDULE OF QUANTITIES V

SCALE: NTS
DATE: 07/01/05

DRAWN BY: PFR
CHECKED BY: KPS



TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
200 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-611-0000

R05SPF

A:\TBDONZ\DEN...S\0000\0000\0000\CIVIL\0369\0369\FPC.DGN SA:\0369\0369\FPC.DGN