

SCHEDULE OF REMOVED EXISTING STRUCTURES					
NO.	DESCRIPTION	STATION	OFFSET		SHEET
R1	CATCH BASIN	5+96.37	24.89	LT	46
R2	CATCH BASIN	6+35.30	12.48	RT	46
R3	CATCH BASIN	13+86.08	28.22	RT	46
R4	CATCH BASIN	14+30.40	76.07	RT	46
R5	CATCH BASIN	14+37.06	48.81	RT	46
R6	CATCH BASIN	14+64.31	84.52	RT	46
R7	CATCH BASIN	15+47.43	44.53	RT	46
R8	CATCH BASIN	15+99.79	37.80	RT	46
R9	CATCH BASIN	16+03.48	65.36	RT	48
R10	CATCH BASIN	16+75.07	26.11	RT	48
R11	MANHOLE	16+98.60	10.67	RT	48
R12	CATCH BASIN	18+16.84	76.79	RT	48
R13	CATCH BASIN	18+44.22	37.85	RT	48
R14	CATCH BASIN	18+46.05	7.58	LT	48
R15	CATCH BASIN	20+31.30	16.51	LT	48
R16	CATCH BASIN	21+06.49	11.64	RT	48
R17	CATCH BASIN	21+16.48	19.18	RT	48
R18	CATCH BASIN	21+81.28	11.98	RT	48
R19	CATCH BASIN	21+80.66	15.82	LT	48

SCHEDULE OF ADJUSTED STRUCTURES																	
NO.	DESCRIPTION	STATION	OFFSET	EX. RIM	PR. RIM	NORTH INVERT		SOUTH INVERT		EAST INVERT		WEST INVERT		SHEET			
						PIPE	INVERT	SIDE	PIPE	INVERT	SIDE	PIPE	INVERT		SIDE	PIPE	INVERT
70	CATCH BASIN	9+75.61	38.22	LT	638.21	637.79								46			
71	CATCH BASIN	10+44.12	22.40	LT	638.78	638.13								46			
72	CATCH BASIN	10+46.72	39.74	LT	638.62	637.78								46			
73	MANHOLE (UTILITY)	11+12.51	54.85	RT	634.19	635.98								46			
74	MANHOLE	17+19.04	54.25	RT	627.70	627.32	EX	620.39	N	EX	619.95	S		48			
75	SANITARY MANHOLE	17+24.36	72.53	RT	627.70	627.42								48			
76	SANITARY MANHOLE	18+44.22	37.85	RT	629.78	629.51								48			
77	MANHOLE	18+74.42	25.53	RT	631.55	632.14	EX	624.00	N	EX	620.70	S		48			
78	MANHOLE	20+03.66	20.27	RT	634.08	634.05								48			
79	MANHOLE	21+38.71	30.77	RT	634.82	634.97	EX	15	628.92	NE	SEE RECON BELOW			48			
80	MANHOLE	21+59.30	40.62	RT	635.15	636.37			EX	15	628.80	SW	EX	15	629.03	E	48
81	CATCH BASIN	22+32.37	20.13	RT	634.55	634.95			EX	12	632.32	SW	EX	6	632.33	E	48

SCHEDULE OF RECONSTRUCTED EXISTING STRUCTURES																	
NO.	DESCRIPTION	STATION	OFFSET		ADD OPENING		DELETE OPENING		ADD OPENING		DELETE OPENING		SHEET				
					PIPE	INVERT	SIDE	PIPE	INVERT	SIDE	PIPE	INVERT		SIDE	PIPE	INVERT	SIDE
79	MAN RECON NEW TIF CL	21+38.71	30.77	RT	131	628.30	SW	R114	627.70	SW				48			
91	MAN RECON NEW TIF CL	21+76.26	19.31	RT	133	631.75	S	R118	631.48	W				48			
92	MAN RECON NEW TIF CL	21+67.73	27.26	LT	132	630.30	NE	R116	TBD*	NE	130	629.75	SE	R115	TBD*	SE	48

\* DELETED OPENING INVERT TO BE DETERMINED BY CONTRACTOR

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX  
 F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK  
 WILL COUNTY

### DRAINAGE & UTILITIES STRUCTURE SCHEDULE I

SCALE: NTS  
 DATE: 07/01/05

DRAWN BY: PFR  
 CHECKED BY: CJH

**TENG**  
TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 312 N. MICHIGAN AVE. CHICAGO, IL 60611  
 TELEPHONE: 312.642.4000

RO55PF

S:\DOCUMENT\023280\CIVIL\DRY\DRAGON\_2.DGN

T:\TENG\2005\7-19-2005\_162037