

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	52
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO: 83757				

SCHEDULE OF NEW PIPES								
NO.	DESCRIPTION	DIAMETER (IN)	LENGTH (FT)	SLOPE	FROM STRUCT.	TO STRUCT.	TRENCH BACKFILL (CU YD)	SHEET
101	STORM SEW CL A 2 12	12	70.22	3.02%	3	4	32.80	46
102	STORM SEW CL A 2 15	15	21.39	2.95%	4	9	11.86	46
103	STORM SEW CL A 2 12	12	63.21	0.90%	5	6	173.42	46
104	STORM SEW CL A 3 30	30	98.29	0.22%	9	11	173.42	46
105	STORM SEW CL A 2 15	15	36.00	0.64%	6	7	20.62	46
106	STORM SEW CL A 2 18	18	10.50	0.86%	7	8	8.06	46
107	STORM SEW CL A 2 18	18	12.80	0.94%	8	9	10.63	46
108	STORM SEW CL A 1 12	12	14.00	0.93%	10	11	4.59	46
109	STORM SEW CL A 2 12	12	27.62	0.51%	12	11	12.04	46
110	STORM SEW CL A 2 30	30	10.00	3.00%	11	SA	16.13	46
111	STORM SEW CL A 3 24	24	28.43	1.76%	15	14	0.00	46
112	STORM SEW CL A 3 15	15	40.41	0.62%	13	15	52.56	46
113	STORM SEW CL A 3 36	36	35.09	0.71%	16	13	76.99	46
114	STORM SEW CL A 3 36	36	67.67	0.15%	17	16	5.56	46
115	STORM SEW CL A 2 21	21	58.69	1.04%	18	16	76.06	46
116	STORM SEW CL A 3 72	72	282.48	0.11%	21	15	0.00	46
117	STORM SEW CL A 2 15	15	67.73	0.50%	19	23	51.70	46
118	STORM SEW CL A 2 15	15	15.03	0.53%	20	22	11.50	48
119	STORM SEW CL A 2 15	15	40.00	0.45%	23	22	31.16	48
120	STORM SEW CL A 2 15	15	7.38	0.68%	22	21	3.51	48
121	STORM SEW CL A 2 15	15	157.28	1.98%	28	21	0.00	48
122	STORM SEW CL A 2 15	15	54.63	0.51%	26	24	6.16	48
123	(NOT USED)							
124	STORM SEW CL A 2 15	15	21.86	0.50%	27	26	16.64	48
125	STORM SEW CL A 2 15	15	37.04	0.46%	30	29	27.63	48
126	STORM SEW CL A 2 21	21	87.72	1.42%	31	29	87.86	48
127	STORM SEW CL A 2 15	15	35.66	1.82%	32	35	14.88	48
128	STORM SEW CL A 2 15	15	29.06	0.52%	33	35	12.84	48
129	STORM SEW CL A 2 15	15	30.37	0.49%	34	33	12.62	48
130	STORM SEW CL A 2 21	21	67.35	1.56%	92	31	41.88	48
131	STORM SEW CL A 2 15	15	23.69	1.27%	79	31	18.56	48
132	STORM SEW CL A 2 18	18	16.01	2.19%	35	92	2.84	48
133	STORM SEW CL A 2 15	15	8.58	1.17%	91	32	3.41	48
134	P CUL 1 CS/A CP 12	12	18.00	0.50%	RW	36	0.00	46
135	P CUL 1 CS/A CP 12	12	48.00	0.50%	38	37	0.00	46
136	P CUL 1 CS/A CP 12	12	54.00	0.50%	40	39	0.00	46
137	P CUL 1 CS/A CP 12	12	39.00	1.00%	42	41	0.00	48
138	P CUL 1 CS/A CP 12	12	44.00	1.00%	44	43	0.00	48

SCHEDULE OF PIPE REMOVAL					
NO.	DESCRIPTION	DIAMETER (IN)	LENGTH (FT)	TRENCH BACKFILL (CU YD)	SHEET
R101	STORM SEWER REM 24	24	33.00	36.58	45
R102	STORM SEWER REM 42	42	181.00	301.71	45
R103	STORM SEWER REM 12	12	12.00	4.68	45
R104	STORM SEWER REM 12	12	14.00	6.84	45
R105	STORM SEWER REM 12	12	34.00	14.44	45
R106	STORM SEWER REM 12	12	26.00	9.82	45
R107	STORM SEWER REM 12	12	4.00	1.78	45
R108	STORM SEWER REM 12	12	24.00	4.74	45
R109	STORM SEWER REM 12	12	34.00	12.76	45
R110	STORM SEWER REM 12	12	32.00	14.22	45
R111	STORM SEWER REM 12	12	32.00	20.75	45
R112	STORM SEWER REM 21	21	70.00	76.50	45
R113	STORM SEWER REM 12	12	6.00	2.67	45
R114	STORM SEWER REM 15	15	20.00	17.75	45
R115	STORM SEWER REM 36	36	65.00	73.15	45
R116	STORM SEWER REM 15	15	11.00	5.41	45
R117	STORM SEWER REM 15	15	26.00	11.13	45
R118	STORM SEWER REM 15	15	5.00	2.14	45

ROSSFF

SAJDDJMENT\023280\00\CIVIL\UDON\DRAGON_4.DWG

ATTORNEY IN CHARGE
7-19-2005, 16:20:35

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

DRAINAGE & UTILITIES PIPE SCHEDULE

SCALE: NTS DRAWN BY: PFR
DATE: 07/01/05 CHECKED BY: CJH

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
802 N. MICHIGAN AVE. CHICAGO, IL 60611
TELEPHONE: 312-644-0000