

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN CONSTRUCTION TYPE CODE
			ROADWAY 80% FEDERAL 20% LOCAL 1000
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,176
40600300	AGGREGATE (PRIME COAT)	TON	83
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,186
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	863
42400800	DETECTABLE WARNINGS	SQ FT	143
44000600	SIDEWALK REMOVAL	SQ FT	993
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	826
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	442
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	575
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	610
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	433
48101200	AGGREGATE SHOULDERS, TYPE B	TON	945
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, SPECIAL	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,160
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	556
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35,610
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,820
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	328
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	460
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	180
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4,946
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70	TON	1,595
Z0017400	DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	EACH	5
Xx006553	BITUMINOUS SURFACE REMOVAL - 0 TO 1 3/4"	SQ YD	5,756
Xx006554	BITUMINOUS SURFACE REMOVAL - BUTT JOINT DRIVEWAY	SQ YD	353

* SPECIALTY ITEM

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00010-00-RS	MCHENRY	25	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS HIGHWAY PROJECT		

CONTRACT # 83854

SMITH ENGINEERING CONSULTANTS, INC.
 CIVIL/STRUCTURAL ENGINEERS AND SURVEYORS
 4500 PRIME PARKWAY, SUITE 801
 MCHENRY, ILLINOIS 60050
 PH: 815-385-1778 FAX: 815-385-1781
 www.smithengineering.com E-MAIL: sec@smithengineering.com
 * MCHENRY * HUNTLEY * YORKVILLE
 ILLINOIS PROFESSIONAL DESIGN FIRM # 184-000108

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF JOHNSBURG
 JOHNSBURG ROAD
 SUMMARY OF QUANTITIES

SCALE:
 DATE 01-10-06

DRAWN BY TK
 CHECKED BY TEH

REVISIONS	
NO.	DATE
7.	
6.	
5.	
4.	
3.	
2.	
1.	

PLOT FILE: STANDARD
 C:\P\05-00010-00-RS\05-00010-00-RS-03.DWG
 DATE: 01/10/06 11:00 AM