SCHEDULE OF QUANTITIES

60610400 COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24		FT.
S.W. ISLAND FOREST VIEW		68.2
S.E. ISLAND FOREST VIEW		54.2
S.W. ISLAND STOWMARKET		28.5
S.E. ISLAND STOWMARKET		33.1
N.W. ISLAND STOWMARKET		31.3
N.E. ISLAND STOWMARKET		46.9
S.W. ISLAND MULFORD		51.2
S.E. ISLAND MULFORD		81.5
N.W. ISLAND MULFORD		79.1
N.E. ISLAND MULFORD		51.8
	TOTAL	525.8
60618300 CONCRETE MEDIAN SURFACE, 4 INCH Revised 6.9.06		S.F.
LT. & CL. STA. 127+06-127+16		51.0
CL. & RT. STA. 129+79-129+95		40.0
CL. & RT. STA. 130+49-130+56		28.0
LT. & CL. STA. 134+46-134+56		38.0
CL. & RT. STA. 135+38-135+52		32.0
CL. & RT. STA. 140+86-150+00		38.0
STA. 287+34.45-289+61.17		3,794.8
MULFORD STA. 9+91.19-12+14.30		1,606.2
MULFORD STA. 20+18.38-22+23.00		2,496.1
S.W. ISLAND RT. STA. 226+10		527.4
S.E. ISLAND RT. STA. 226+90		342.7
S.W. ISLAND RT. STA. 261+95		101.2
N.W. ISLAND LT. STA. 262+05		125.4
S.E. ISLAND RT. STA. 262.60		140.0
N.E. ISLAND LT. STA. 262+70		266.0
N.W. ISLAND LT. STA. 279+40		712.8
S.W. ISLAND RT. STA. 279+60		331.1
N.E. ISLAND LT. STA. 280+45		330.0
S.E. ISLAND RT. STA. 280+55		784.3
	TOTAL	11,785.0
60619100 CONCRETE MEDIAN, TYPE SB (SPECIAL)		S.F.
STA. 201+17.31-206+09.66		2,964.4
STA. 207+06.70-210+01.20		1,899.6
STA. 216+66.44-219+48.31		1,817.7
STA. 223+10.86-226+06.93		1,885.1
STA. 227+00.39-229+96.50		1,888.2
STA. 234+89.92-237+76.20		1,852.9
STA. 238+25.28-244+12.86		2,434.4
STA. 244+88.87-247+97.19		1,988.6
STA. 252+65.02-255+69.48		1,953.2
STA. 256+60.90-261+88.44		3,107.8
STA. 262+81.00-269+16.48		3,772.3
STA. 270+04.14-271+65.92		1,383.9
STA. 275+73.02-279+27.30		2,327.2
STA. 280+70.51-282+33.31		1,423.2
MULFORD STA. 9+32.60-9+91.19		474.3
MULFORD STA. 12+14.30-15+24.43		2,052.6
MULFORD STA. 16+99.09-20+18.38		2,173.0
EASTROCK STA. 601+24.61-602+32.50		560.0
EASTROCK STA. 602+73.78-604+04.60		621.0
	TOTAL	36,579.4

70103700 TRAFFIC CONTROL COMPLETE		L.SUM
ENTIRE PROJECT		1
	TOTAL	1
78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		S.F.
WHITE		
LT TURN	LT. STA.108+91	12.7
RT & THRU	LT. STA. 109+35	25.3
LT TURN	LT. STA. 109+49	12.7
LT TURN	LT. STA. 110+04	12.7
LT TURN	LT. STA. 111+06	12.7
LT TURN	LT. STA. 112+09	12.7
LT TURN	RT. STA. 118+66	12.7
LT TURN	RT. STA. 119+22	12.7
LT TURN	RT. STA. 119+79	12.7
LT TURN	CL. STA. 123+40	12.7
LT TURN	CL. STA. 123+81	12.7
LT TURN	CL. STA. 124+21	12.7
LT TURN	RT. STA. 127+50	12.7
LT TURN	RT. STA. 128+00	12.7
LT TURN	RT. STA. 128+48	12.7
LT TURN	CL. STA. 130+04	12.7
LT TURN	CL. STA. 130+64	12.7
LT TURN	CL. STA. 131+23	12.7
LT TURN	RT. STA. 133+54	12.7
LT TURN	RT. STA. 134+00	12.7
LT TURN	CL. STA. 135+64	12.7
LT TURN	CL. STA. 136+18	12.7
LT TURN	CL. STA. 136+72	12.7
LT TURN	LT. STA. 141+13	12.7
LT TURN	LT. STA. 141+71	12.7
LT TURN	LT. STA. 142+31	12.7
LT TURN	RT. STA. 143+72	12.7
LT TURN	RT. STA. 144+06	12.7
LT TURN	LT. STA. 145+33	12.7
LT TURN	LT. STA. 145+87	12.7
LT TURN	LT. STA. 146+41	12.7
LT TURN	RT. STA. 148+58	12.7
LT TURN	RT. STA. 149+47	12.7
RT TURN	RT. STA. 149+67	12.7
RT TURN	RT. STA. 150+23	12.7
LT TURN	RT. STA. 150+34	12.7
LT & THRU	RT. STA. 151+05	25.3
RT TURN	RT. STA. 151+20	12.7
LT TURN	LT. STA. 151+61	12.7
LT TURN	LT. STA. 151+91	12.7
LT TURN	CL. STA. 153+82	12.7
LT TURN	CL. STA. 154+72	12.7
LT TURN	CL. STA. 155+62	12.7
LT TURN	CL. STA. 156+56	12.7
	TOTAL	584.0
78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"		FT.
SKIP-DASHED WHITE (10'DASH-30' SKIP)		
RT. STA. 109+78-128+73		474
LT. STA. 109+78-128+77		475
LT. STA. 129+79-140+26		262
RT. STA. 129+79-140+26		262
LT. STA. 140+38-150+59		225
RT. STA. 140+38-150+80		260
LT. STA. 151+31-156+26		124
	SUB-TOTAL	2,082

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" (CONT)		FT.
YELLOW - DOUBLE SOLID		
RT. & LT. STA. 145+08-148+38		660
RT. & CL STA. 145+08-148+38		660
	SUB-TOTAL	1,320
	TOTAL	3,402
78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"		FT.
WHITE - CROSSWALK		
LT. & RT. STA. 109+27		93
LT. STA. 109+27-109+72		90
LT. & RT. STA. 128+77		64
LT. & RT. STA. 128+89		78
LT. & RT. STA. 140+26		56
LT. & RT. STA. 140+38		78
	TOTAL	459
78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"		FT.
WHITE - SOLID		
LT. STA. 109+43		5
LT. STA. 109+55		5
LT. STA. 109+78-112+29		251
RT. STA. 118+44-120+05		161
LT. STA. 123+14-124+41		127
RT. STA. 127+29-128+73		144
LT. STA. 129+79-131+43		164
RT. STA. 133+34-134+43		109
LT. STA. 135+39-146+92		153
LT. STA. 140+87-142+51		164
RT. STA. 143+52-144+32		80
LT. STA. 145+07-146+61		154
RT. STA. 148+38-150+30		192
RT. STA. 148+56		134
RT. STA. 150+29-150+50		24
RT. STA. 151+00		6
RT. STA. 151+12		6
LT. STA. 151+32-152+11		79
LT. STA. 152+11-153+52		35
	SUB-TOTAL	1,993
WHITE - SKIP DASH (2' DASH-6' SKIP)		
LT. STA. 112+29-113+63		34
RT. STA. 117+05-118+44		35
LT. STA. 124+41-125+88		37
LT. STA. 131+43-132+80		34
LT. STA. 131+62-133+34		43
LT. STA. 136+92-138+29		34
LT. STA. 142+51-143+92		35
RT. STA. 142+63-143+52		22
LT. STA. 146+61-148+35		44
RT. STA. 146+89-148+38		37
RT. STA. 148+86-149+54		17
LT. STA. 152+11-153+52		35
	SUB-TOTAL	407
	TOTAL	2,400
78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"		FT.
YELLOW - DIAGONAL		
RT. & LT. STA. 145+08-148+38		50
	TOTAL	50