If you plan to submit a bid directly to the Department of Transportation

PREQUALIFICATION

Any contractor who desires to become pre-qualified to bid on work advertised by IDOT must submit the properly completed pre-qualification forms to the Bureau of Construction no later that 4:30 p.m. prevailing time twenty-one days prior to the letting of interest. This pre-qualification requirement applies to first time contractors, contractors renewing expired ratings, contractors maintaining continuous pre-qualification or contractors requesting revised ratings. To be eligible to bid, existing pre-qualification ratings must be effective through the date of letting.

REQUESTS FOR AUTHORIZATION TO BID

Contractors downloading and/or ordering CD-ROM's and are wanting to bid on items included in a particular letting must submit the properly completed "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) and the ORIGINAL, signed and notarized, "Affidavit of Availability" (BC 57) to the proper office no later than 4:30 p.m. prevailing time, three (3) days prior to the letting date.

WHO CAN BID?

Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction.

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID? When a prospective prime bidder submits a "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial.

ABOUT AUTHORIZATION TO BID: Firms that have not received an authorization form within a reasonable time of complete and correct original document submittal should contact the department as to status. This is critical in the week before the letting. These documents must be received three days before the letting date. Firms unsure as to authorization status should call the Prequalification Section of the Bureau of Construction at the number listed at the end of these instructions.

ADDENDA AND REVISIONS: It is the contractor's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum will be placed with the contract number. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription server e-mails are an added courtesy the Department provides. It is suggested that bidder check IDOT's website http://www.dot.il.gov/desenv/delett.html before submitting final bid information.

IDOT is not responsible for any e-mail related failures.

Addenda Questions may be directed to the Contracts Office at (217)782-7806 or D&Econtracts@dot.il.gov

Technical Questions about downloading these files may be directed to Tim Garman (217)524-1642 or garmantr@dot.il.gov.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

ABOUT SUBMITTING BIDS: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding	Call
Prequalification and/or Authorization to Bid	(217)782-3413
Preparation and submittal of bids	(217)782-7806
Mailing of plans and proposals	(217)782-7806
Electronic plans and proposals	(217)524-1642

ADDENDUMS AND REVISIONS TO THE PROPOSAL FORMS

Planholders should verify that they have received and incorporated the addendum and/or revision prior to submitting their bid. Failure by the bidder to include an addendum could result in a bid being rejected as irregular.

185

BIDDERS NEED NOT RETURN THE ENTIRE PROPOSA

See instructions inside front cover)

1.2.01.11.11.12.12	
Proposal Submitted By	
Name	
Address	
City	

Letting June 16, 2006

NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction. (SEE INSTRUCTIONS ON THE INSIDE OF COVER)

Notice To Bidders, Specifications, Proposal, Contract and Contract Bond



Springfield, Illinois 62764

Contract No. 85390
WINNEBAGO County
Section 03-00520-00-WR (Rockford)
Route FAP 525 (Harrison Avenue)
Project ACF-525(107)
District 2 Construction Funds

PLEASE MARK THE APPROPRIATE BOX BELOW:
☐ A <u>Bid</u> <u>Bond</u> is included.
A Cashier's Check or a Certified Check is included

Prepared by

F

Checked by

Printed by authority of the State of Illinois

INSTRUCTIONS

ABOUT IDOT PROPOSALS: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction.

WHO CAN BID?: Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction. To request authorization, a potential bidder <u>must complete and submit Part B of the Request for Authorization to Bid/or Not For Bid Status form (BDE 124 INT) and submit an original Affidavit of Availability (BC 57).</u>

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Request for Proposal Forms and Plans" he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial. If a contractor has requested to bid but has not received a Proposal Denial and/or Authorization Form, they should contact the Central Bureau of Construction in advance of the letting date.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

ABOUT SUBMITTING BIDS: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

Call

WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding

Prequalification and/or Authorization to Bid	217/782-3413
Preparation and submittal of bids	217/782-7806
Mailing of CD-ROMS	217/782-7806



PROPOSAL

TO THE DEPARTMENT OF TRANSPORTATION

Project ACF-525(107)

the City of Rockford.

Route FAP 525 (Harrison Avenue)

1.	Proposal of
Та	repayer Identification Number (Mandatory) for the improvement identified and advertised for bids in the Invitation for Bids as:
	Contract No. 85390 WINNEBAGO County Section 03-00520-00-WR (Rockford)

District 2 Construction Funds

Project consists of the resurfacing of Harrison Avenue from 26th Street east to Alpine Road and the reconstruction of Harrison Avenue from Alpine Road east to approximately 800' east of Mulford Road, five signalized intersections are to be modernized and lighting improvements all located in

2. The undersigned bidder will furnish all labor, material and equipment to complete the above described project in a good and workmanlike manner as provided in the contract documents provided by the Department of Transportation. This proposal will become part of the contract and the terms and conditions contained in the contract documents shall govern performance and payments.

- 3. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, form of contract and contract bond, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 4. **EXECUTION OF CONTRACT AND CONTRACT BOND.** The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- 5. PROPOSAL GUARANTY. Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

<u> </u>	Amount o	of Bid	Proposal <u>Guaranty</u>	<u>Am</u>	ount c	Proposal <u>of Bid</u> <u>Guaranty</u>
Up to		\$5,000	\$150	\$2,000,000	to	\$3,000,000\$100,000
\$5,000	to	\$10,000	\$300	\$3,000,000	to	\$5,000,000 \$150,000
\$10,000	to	\$50,000	\$1,000	\$5,000,000	to	\$7,500,000 \$250,000
\$50,000	to	\$100,000	\$3,000	\$7,500,000	to	\$10,000,000 \$400,000
\$100,000	to	\$150,000	\$5,000	\$10,000,000	to	\$15,000,000 \$500,000
\$150,000	to	\$250,000	\$7,500	\$15,000,000	to	\$20,000,000 \$600,000
\$250,000	to	\$500,000	\$12,500	\$20,000,000	to	\$25,000,000\$700,000
\$500,000	to	\$1,000,000	\$25,000	\$25,000,000	to	\$30,000,000\$800,000
\$1,000,000	to	\$1,500,000	\$50,000	\$30,000,000	to	\$35,000,000 \$900,000
\$1,500,000	to	\$2,000,000	\$75,000	over		\$35,000,000 \$1,000,000

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

If a combination bid is submitted, the proposal guaranties which accompany the individual proposals making up the combination will be considered as also covering the combination bid.

The amount of the proposal guaranty check is	\$(). If this proposal is accepted
and the undersigned shall fail to execute a contract bond as required herein, it is	s hereby agreed that the amount	of the proposal guaranty shall become
the property of the State of Illinois, and shall be considered as payment of dama	ges due to delay and other cause	s suffered by the State because of the
failure to execute said contract and contract bond; otherwise, the bid bond sha	Il become void or the proposal g	uaranty check shall be returned to the
undersigned.	-	

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

BD 354 (Rev. 11/2001)

6. **COMBINATION BIDS.** The undersigned further agrees that if awarded the contract for the sections contained in the following combination, he/she will perform the work in accordance with the requirements of each individual proposal comprising the combination bid specified in the schedule below, and that the combination bid shall be prorated against each section in proportion to the bid submitted for the same. If an error is found to exist in the gross sum bid for one or more of the individual sections included in a combination, the combination bid shall be corrected as provided in the specifications.

When a combination bid is submitted, the schedule below must be completed in each proposal comprising the combination.

If alternate bids are submitted for one or more of the sections comprising the combination, a combination bid must be submitted for each alternate.

Schedule of Combination Bids

Combination		Combination Bid	
No.	Sections Included in Combination	Dollars 0	Cents

- 7. SCHEDULE OF PRICES. The undersigned bidder submits herewith, in accordance with the rules and instructions, a schedule of prices for the items of work for which bids are sought. The unit prices bid are in U.S. dollars and cents, and all extensions and summations have been made. The bidder understands that the quantities appearing in the bid schedule are approximate and are provided for the purpose of obtaining a gross sum for the comparison of bids. If there is an error in the extension of the unit prices, the unit prices shall govern. Payment to the contractor awarded the contract will be made only for actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as provided elsewhere in the contract.
- 8. **CERTIFICATE OF AUTHORITY.** The undersigned bidder, if a business organized under the laws of another State, assures the Department that it will furnish a copy of its certificate of authority to do business in the State of Illinois with the return of the executed contract and bond. Failure to furnish the certificate within the time provided for execution of an awarded contract may be cause for cancellation of the award and forfeiture of the proposal guaranty to the State.

STATE JOB #- C-92-082-05 PPS NBR - 2-10203-0000

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

1.

	1	EACH	EMOVE EX LIGHT POLE	325151
- II - II - I - I - I - I - I - I - I -	3,353.000 X	FOOT	EM VEH P S LSC 20 3C	0324085
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2,000	EACH	VIDEO SURV SYS COMP	322283
 	77.000	FOOT	TORM SEW WM REQ 30	322127
- tt - 1	200,000	FOOT	TORM SEW WM REQ 24	322125
11 -11 -1	12.000	FOOT	STORM SEW WM REQ 15	22034
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	3.000	EACH	VIDEO VEH DETECTOR	320873
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	3.000	EACH	VIDEO VEH DET SYS	20872
	32.000	EACH	PS MH 150W	06578
	32,000	EACH	LUM PS MH 400W	06577
1	1.000	EACH	BLE INLETS TYP 700	06576
1	8,410.000	FOOT	O CBL CON 48SM 24MM	6575
	28,000.000	F00T	EC C 1/C 6 THHN/THWN	04270
- 11	8,410.00	F00T	BARE CU WIRE 1C 8	2191
- 11	27.000	EACH	LETS T700	XX000968
UNIT PRICE TOTAL PRICE DOLLARS CENTS DOLLARS CTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER
PROJECT NUMBER ROUTE FAP 525	ACF-C	ION NUMBER (ROCKFORD)	NAME CODE DIST SECT GO 201 02 03-00520-00-WR	WINNEBAG

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ORTATION ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 0 RUN TIME - 134423

	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	100.000 X	00	LOT DR 12" W/2.5" S	00657
- 11		1,058.000	EACH	OWEL BARS 1 1/2	001720
- 11	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2.000	EAC	ED SH LED 3F BM	881063
	1	7.000	ACH	D SH P LED 2F BM	81049
- II	 	12.000	EACH	SH P LED 1F BM	881039
- II	1	4.000 X	H H	SH P LED 2F 5S BM	X8801447
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	14,000	EACH	SH P LED 1F 5S MAM	X8801400
- II	1 1 1 1 1 1 1 1 1 1 1 1	27.00	EACH	SH P LED 1F 5S BM	X8801395
- II	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	30.000	EACH	SH P LED 1F 3S MAM	X8801310
- II	 	2,241.000	FOOT	ELCBL C GROUND 6 1C	X8730027
- II	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2,455.000	TOŅ	BCBC SUP IL-19.0 N70	99
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2,455.000	TON	BC SC SUPER "E" N70	6643
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1,131.000	TON	BC SC SUPER "C" N30	406641
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	597.000	FOOT	RM SEW WATER MN 18	930
- II —		54.000		TORM SEW WATER MN 1	X0930400
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	ITEM NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ORTATION ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06

RUN TIME - 134423

		68,978.200 X	T0	UB GRAN MAT A	110010
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		.000	EACH	INLET & PIPE PROTECT	8000500
	1 1 1 1 1	7,179.000	FOO	RIMETER EROS BAR	8000400
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	48.000	EACH	MP DITCH CHECKS	800030
l t		,250.000	DND	MP EROS CONTR SEED	00025
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	 	2,016.000	TINU	UPPLE WATERING	5200200
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0,324.000	SQ YD	SODDING	200100
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	25.000	A	MULCH METHOD 2	5100115
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1	40,324.000	SQ YD	TOPSOIL F & P 6	1101625
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1,924.620	CU YD	TRENCH BACKFILL	0800150
		2,759.00	CU YD	EARTH EXCAVATION	0200100
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0.480 X	ACRE	TREE REMOV ACRES	0100500
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	216.000	INO	TREE REMOV OVER 15	010021
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1	! ! !	IND	EMOV 6-15	01001
800.00	0.80	1,000.000	HOUR	TRAINEES	Z0076600
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	ITEM NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

Matt		기		3	-	7
NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS CEN	TS DOLLARS	CIS
0	TAB SUB-BASE	SQ YD	600		- п —	
35101400	BASE CSE B	TON	5,475.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	1
020080	GG SURF CSE B	_ ;	20.000	1	1	1 1
060020	T MATLS PR CT		23.500		- II - I	1 1
060030	GG PR CT	TON	0.400	;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	- 11 - II	1
200040	CC PVT 9 JOI	SQ YD	5,262.100	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- II - I	1 1 1
00130	OTECTIVE COAT	SQ YD	101,210.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		1
23003	PCC DRIVEWAY PAVT 7	SQ YD	723.200	1 1 1 1 1 1 1 1 1 1		. i
400200	PC CONC SIDEWALK 5	QFT	2,578.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
400000	IT SURF REM 3	Q YD	9,208.000	 1 1 1 1 1	- II	1
0010	AVEMENT REM	Q YD	7,703.000		- II <u>-</u>	1
400020	RIVE PAVEMENT REM	اِ ھ	154.000	I I I I I I I I I I I I I I I I I I I		1
400050	OMB CURB GUTTER REM	FOOT	7,188.000	 		1
400060	IDEWALK REM	! <u> </u>	,818.000] 1 1 1 1 1 1	- II	1
400170	OMB C C&G REM & REPL	FOOT	. 00	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		

4

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

RANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE CES RUN DATE - 05/30/06 85390 RUN TIME - 134423

	11 1	2.000 X	EACH	PRC FLAR END SEC 15	54213660
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	 	000	AC	PRC FLAR END SEC 12	54213657
	1 1 1	6.000	EA	END SECTIONS 12	54213447
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1	18.000	FOOT	P CUL 1 RC-E EQRS 30	54207165
I I I I I I I I I I I I I I I I I I I	; 1 1 1 1 1 1	23.000	001	P CUL CL A 1 30	542A0235
 1 1 3 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1	00		PIPE CULVERT REMOV	50105220
	1 1 1 1 1 1	1.000	EAC	CONC HDWL REM	50104400
1	 	253.900	SQ YD	BIT SHLD SUPER 6	48202400
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		5.300	TON	AGGREGATE SHLDS A	48100100
I I	1 1 1 1 1	724.000	F00T	TRIP REF CR CON TR	430020
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	11 1	2,050.000		W CUTS	421320
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		113,000	SQ	L B PATCH T4 9	0096
	t t	175.000	SQ YD	CL B PATCH T3 9	420096
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		9,537.000	SQ YD	AVED SHLD REMOVAL	400425
		,324.000	SQ FT	CONC MEDIAN SURF REM	44002020
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	ITEM NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

DRTATION ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06

RUN TIME - 134423

	- II -		7.000		STORM SEWER REM 12	510050
ı	- 11			FOOT	STORM SEW CL A 2 3	Ö
·	; ; (1	210.000	FOOT	TORM SEW CL A 2 24	50A041
	: ; ; ; ; ; ;		626.000	FOOT	STORM SEW CL A 2 18	50A038
1	! ! ! ! !		949.000	, , ,	STORM SEW CL A 2 1	50A036
1	- 11 —		1,176.000	OT:	STORM SEW CL A 2 12	50A034
1 1 2 2 1 1 1 1 1	- 11 —		2.000	001	STORM SEW CL A 1 36	50A016
t	- II —	 	514.000	FOOT	STORM SEW CL A 1 24	50A012
1 1 1 1 1 1 1 1 1	- 11 —	1 1 1 1 1 1	226,000	FOOT	STORM SEW CL A 1 18	50A009
1	1 1 1 1	1	391.000	F00T	STORM SEW CL A 1 15	50A007
	 	- X - I	35.000	F00T	STORM SEW CL A 1 12	50A005
1 1 1 1 1 1	 	 	0.450	· ≺ ·	CONCRETE COLLAR	424851
[) []	1 1 1 1 1	2.000	EAC	PRCF END S EL EQRS 3	421472
	1 1 1 1	,	2.000	EACH	PRC FLAR END SEC 30	421367
	11		1,000	ACH	RC FLAR END SE	42136
TOTAL PRICE DOLLARS CTS	ICE	UNIT PR	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	ITEM NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

7

- 11	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1.000 X	EACH	NLETS TA T12F&G	02369
- 11 11 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	6.000 X	ו קַבֹּו	NLETS TA T11F&G	23680
11 - 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 -	1 1 1 1 1 1 1	5.000	AC I	NLETS TA T8G	023620
- 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	1 1 1 1 1 1 1	1,000	EAC	MAN TA 6 DIA T1F CL	0223800
- 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	! ! ! ! ! !	1.000	EAC	MAN TA 5 DIA T3F&G	02212
	 	10.000	ြင်	AN TA 5 DIA T1F CL	022
11 11	 	11.000	ACH	MAN TA 4 DIA T1F CL	0218400
- 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	; ; ; ; ; ;	1,025.000	FOOT	PIPE UNDERDRAINS 4	010
- II —		1.000	EACH	FIRE HYDNTS RELOCATED	6400400
- 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -		5.000	ACH	FIRE HYDNTS TO BE A	6400300
	 	9.000	007	WATER MAIN 16	01000
- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	1 1 1 1 1 3 1 1	6.000	00T	STORM SEWER REM 30	510140
- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	 1 1 1 1	50.000	FOOT	ORM SEWER REM 24	510120
	 		F00T	TORM SEWER REM	510090
- u —		000		TORM SEWER REM	510070
TOTAL PRICE OOLLARS CTS	UNIT PRICE	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

ECMS002 DTGECM03 ECMR003 PAGE 8 RUN DATE - 05/30/06 RUN TIME - 134423

FAP 525 03-00520-00-WR (ROCKFORD) WINNEBAGO

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

[60605000 60603500 60262700 60500060 60255500 60608600 60600095 60500040 60260100 60257900 60255800 60242801 60242700 60240301 ITEM NUMBER COMB CC&G TB6.24 COMB CC&G TB6.18 CLASS SI CONC OUTLE COMB CC&G TB6.06 REMOV INLETS REMOV MANHOLES MAN RECONST COMB CC&G TM6.06 INLETS ADJUST MAN ADJ NEW T1F C MAN ADJUST INLETS RECONST INLETS SPL N5 INLETS SPL N3 INLETS PAY ITEM DESCRIPTION TB T8G MEASURE EACH EACH EACH F001 F001 F001 F001 EACH EACH EACH **EACH** EACH EACH EACH QUANTITY 20,569.400 3,420.000 2,398.600 358.200 47.000 14.140 46.000 51.000 33.000 11.000 2.000 4.000 1.000 1.000 1.000 DOLLARS UNIT PRICE CENTS DOLLARS PRICE CTS

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

F TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE PRICES RUN DATE - 05/30/06 RUN TIME - 134423

1	 	— X —	4,988.700	F00T	PAINT PVT MK LINE 4	800111
1	 		71.200		PT PVT MK LTRS & SY	80011
	1 1 3 8		285,000	FOOT	THPL PVT MK LINE 24	9006
]]]]]]]]			50.000	FOOT	THPL PVT MK LINE 12	800060
			,400.0	FOOT	THPL PVT MK LINE 8	00050
11 11 11 11 11 11 11 11 11 11 11 11 11	 	-X	459.000	0	THPL PVT MK LINE 6	8000400
I I		- X -	3,402.000	FOOT	THPL PVT MK LINE 4	000200
I	ı	-X	584.000	SQ FT	THPL PVT MK LTR & SY	800010
1 1 3 1 1 1 1	1 1 1	- X - I	27.0	SQ FT	NSTALL EX SIGN PANEL	72300100
			1.000	L SUM	TRAF CONT COMPL	010370
1	- II -	- X - I	1.000	SUM	MOBILIZATION	00100
	1 1 1 1	-X-	18.000	L MO	ENGR FIELD OFFICE A	700040
[[] [] [] [] [] [] [] [] [] [1 1 1 1	- X	36,579.400	SQ F	ONC MED TSB SPL	0619
1 1 1 1 1 1 1 1 1 1	I I]] [42,448.300	. SQ FT	NC MEDIAN SURF 4	0618
		-×-	525.800		OMB CC&G TM6.24	60610400
TOTAL PRICE DOLLARS CTS	PRICE S CENTS	UNIT P DOLLARS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

-0

NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS	CENTS _	TOTAL PRICE	CTS
78001140	AINT PVT MK LINE	F00	2.300		- tı —		
800115	INT PVT MK LINE 12	F00	39.300	1 1 1 1 1 1	- II - I	 	1
00118	AINT PVT MK LINE 24	FOOT	1,074.000	; ; ; ; ; ;	t t 1	1 1 1 1 1 1	ľ
81001	RAISED REFL PAVT MKR	EAC	245.000	1 1 1 1 1	 - - - -	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1
400100	ELECT SERV INSTALL	EAC	Ō	 		1 1 1 1 1 1 1	
050020	SERV INSTALL TY B	EAC	3.000	, , , , , , , , , , , , , , , , , , ,	- II I	; ; ; ; ;	! 1
50	T 1 1/2 PVC	00	11.000	1 1 1 1 1 1 1	: : : : [[
101260	ON T 2 PVC	100	,881.000	, I	1 1 1	1 1 1 1 1 1	- 1
1270	CON T 2 1/2 PVC	FOOT	452.000	 	1 1 1 — 11 –	 	- 1
1012800	CON T 3 PVC	F00	3.000		1 1 1 1 1 1 1	1 1 1 1 1 1 1	- 1
101300	ON T 4 PVC	007	51.000	1 1 1 1 1 1 1 1	- 11	 1 1 1 1 1	1
101310	T 5 PV	00	31.000	1	1 1 1 1 - 11 –	 	1
101320	ON T 6 PVC	F00	0.000	! ! ! ! !	! ! ! ! ! - !! —	 	
4001	ANDHOLE	EAC	35.000 X	 	- II —	! !	1
81400300	DBL HANDHOLE	EACH	3.000 X	 	- 11 -	 	, ,

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

N ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

I TEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE
150020	R & BKFIL F ELECT	F00	13,560.000 X		
70211	C XLP USE 1C 10	F00	442.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
210325	LUM SV HOR MT PC 250W	EACH			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
301640	LT P A TB 40MH 10DA	EACH	32.00	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
36003	LP F M 15BC 8" X 6'	EACH	32.000		
5700305	FAC T5 CAB SPL	EACH	3.000	1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
570050	AC IN EXIST CAB	EACH	2.000		
7301215	ELCBL C SIGNAL 14 2C	00T	971.000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
730122	LCBL C SIGNAL 14 3C	FOOT	4,860.000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
730124	LCBL C SIGNAL 14 5C	F00T	6,421.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
7301255	ELCBL C SIGNAL 14 7C	007	8 :		
7301805	LCBL C SERV 6 2	00	000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
750246	TS POST GALVS	AC .	3.000	 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
7502	S POST GALVS 1	i O i	000	1 1 1 1 1 1 1 1	
02	L COMB MAA&P	EACH	1.000 X		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 85390

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 05/30/06 RUN TIME - 134423

		830.000 X	F00	EM ELCBL FR CON	950230
	; ; ; ; ; ;	000	LS	EMP TR SIG INSTALL	900020
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1	29.000	EAC	PED PUSH-BUTTON	8800100
 	1 1 1 1 1 1 1	3.000	EAC	LIGHT DETECTOR AMP	8700300
3 1 1 1 1 1 1 1 1		15.000	EACH	LIGHT DETECTOR	8700200
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 	72.000	ACH	TS BACKPLATE LOU PLAS	8200310
	 	4.000	EACH	DRILL EX HANDHOLE	790020
 		211.000	F00T	CONC FDN TY E 36D	0041
I I I I	1 1 1 1 1	10,500	F00	CONC FDN TY D	780020
1 1 1 1 1 1 1 1 1		42.000	FOOT	FDN TY A	780010
1		8.000	EACH	OMB MAA&P 55	770300
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	: : : : : : :	1.000	EACH	COMB MAA&P 50	770298
	[1 1 1 1 1	1.000	EACH	L COMB MAA&P 48	770297
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1	3.000	AC	TL COMB MAA&P 46	96
		1.000	EAC	STL COMB MAA&P 44	77029
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

12

		 11 —		5.000 X	EACH	QUIP	REMOV EX TS EQUIP	89502375
CIS	TOTAL PRICE DOLLARS C	CENTS	UNIT PRI DOLLARS	QUANTITY -	UNIT OF MEASURE	PAY ITEM DESCRIPTION	PAY ITEN	I TEM NUMBER
13	ECMS002 DTGECM03 ECMR003 PAGE 13 RUN DATE - 05/30/06 RUN TIME - 134423)TGECM03 EC - 05/30/06 - 134423		TRANSPORTATION RICES - 85390	ILLINOIS DEPARTMENT OF TRANSPO SCHEDULE OF PRICES CONTRACT NUMBER - 85390	ILLINOI	FAP 525 03-00520-00-WR (ROCKFORD) WINNEBAGO	FAP 525 03-00520-0 WINNEBAGO

TOTAL

NOTE:

- 1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
- 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
- ω IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
- 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. By execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances has been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for termination of the contract and the suspension or debarment of the bidder.

II. ASSURANCES

A. The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous assurance, and the surety providing the performance bond shall be responsible for the completion of the contract.

B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any state agency from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-10.

C. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$150,700.00. Sixty percent of the salary is \$90,420.00.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

D. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

E. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

F. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, associate procurement officers, State purchasing officers, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

G. Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offerors, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

H. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

I. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

III. CERTIFICATIONS

A. The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous certification, and the surety providing the performance bond shall be responsible for completion of the contract.

B. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
 - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
 - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
 - (1) the business has been finally adjudicated not guilty; or
 - (2) the business demonstrates to the governmental entity with which it seeks to contract, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State shall contain a certification by the contractor that the contractor is not barred from being awarded a contract or subcontract under this Section. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The bidder certifies that it is not barred from being awarded a contract under Section 50.5.

C. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

D. Bid-Rigging/Bid Rotating

- 1. Section 33E-11 of the Criminal Code of 1961 provides:
- § 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.

(b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

E. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

F. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

G. Debt Delinquency

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder certifies that it, or any affiliate, is not barred from being awarded a contract under 30 ILCS 500. Section 50-11 prohibits a person from entering into a contract with a State agency if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The contractor further acknowledges that the contracting State agency may declare the contract void if this certification is false or if the contractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

H. Sarbanes-Oxley Act of 2002

1. The Illinois Procurement Code provides:

Section 50-60(c).

The contractor certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 for a period of five years prior to the date of the bid or contract. The contractor acknowledges that the contracting agency shall declare the contract void if this certification is false.

I. ADDENDA

The contractor or bidder certifies that all relevant addenda have been incorporated in to this contract. Failure to do so may cause the bid to be declared unacceptable.

J. Section 42 of the Environmental Protection Act

The contractor certifies in accordance with 30 ILCS 500/50-12 that the bidder or contractor is not barred from being awarded a contract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The contractor acknowledges that the contracting agency may declare the contract void if this certification is false.

K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

NA - FEDERAL	

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

TO BE RETURNED WITH BID

IV. DISCLOSURES

A. The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous disclosure, and the surety providing the performance bond shall be responsible for completion of the contract.

B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all bids of more than \$10,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid or incorporated by reference.**

C. <u>Disclosure Form Instructions</u>

Form A: For bidders that have previously submitted the information requested in Form A

The Department has retained the Form A disclosures submitted by all bidders responding to these requirements for the April 24, 1998 or any subsequent letting conducted by the Department. The bidder has the option of submitting the information again or the bidder may sign the following certification statement indicating that the information previously submitted by the bidder is, as of the date of signature, current and accurate. The Certification must be signed and dated by a person who is authorized to execute contracts for the bidding company. Before signing this certification, the bidder should carefully review its prior submissions to ensure the Certification is correct. If the Bidder signs the Certification, the Bidder should proceed to Form B instructions.

CERTIFICATION STATEMENT

I have determined that the Form A disclosure informaccurate, and all forms are hereby incorporated by forms or amendments to previously submitted for	y reference in this bid. Any necessary additional
(Bidding C	Company)
Name of Authorized Representative (type or print)	Title of Authorized Representative (type or print)
Signature of Autho	prized Representative Date

Form A: For bidders who have NOT previously submitted the information requested in Form A

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than \$90,420.00? YES NO
3.	Does anyone in your organization receive more than \$90,420.00 of the bidding entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YES NO
4.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than \$90,420.00? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.)
bidding e authorize	answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the ntity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is do to execute contracts for your organization. Photocopied or stamped signatures are not acceptable . The person signing can be, but have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.
	ower to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by that is authorized to execute contracts for your company.
bidding e	Identifying Other Contracts & Procurement Related Information Disclosure Form B must be completed for each bid submitted by the nitity. It must be signed by an individual who is authorized to execute contracts for the bidding entity. Note: Signing the NOT ABLE STATEMENT on Form A does not allow the bidder to ignore Form B. Form B must be completed, signed and dated or the bidder considered nonresponsive and the bid will not be accepted.
ongoing	er shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following:
agency pattached	If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois ending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development ust be included. Bidders who submit Affidavits of Availability are suggested to use Option II.
"See Affi agency p	If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type davit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois ending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.
Bidders	Submitting More Than One Bid
Bidders s Please ir by refere	submitting multiple bids may submit one set of forms consisting of all required Form A disclosures and one Form B for use with all bids. Idicate in the space provided below the bid item that contains the original disclosure forms and the bid items which incorporate the forms nce.
	te bid submitted for letting item contains the Form A disclosures or Certification Statement and the Form B sclosures. The following letting items incorporate the said forms by reference:

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form A Financial Information & Potential Conflicts of Interest Disclosure

Contractor Name		
Legal Address		
City, State, Zip		
Telephone Number	Email Address	Fax Number (if available)
Disclosure of the information contained in the LCS 500). Vendors desiring to enter into a potential conflict of interest information as solublicly available contract file. This Form a contracts. A publicly traded company matche requirements set forth in Form A. See 1990	a contract with the State of Illinois specified in this Disclosure Form. A must be completed for bids in e y submit a 10K disclosure (or ee Disclosure Form Instructions.	must disclose the financial information and This information shall become part of the excess of \$10,000, and for all open-ended quivalent if applicable) in satisfaction of
DISCLO	OSURE OF FINANCIAL INFORM	IATION
	nare in excess of 5%, or an interest . (Make copies of this form as ned e requirements)	interest in the BIDDER (or its parent) in which has a value of more than \$90,420.00 cessary and attach a separate Disclosure
NAME:		
ADDRESS		
Type of ownership/distributable incom	ne share:	
stock sole proprietorship % or \$ value of ownership/distributable in		other: (explain on separate sheet):
2. Disclosure of Potential Conflicts of In potential conflict of interest relationships ap describe.		
(a) State employment, currently or in t	he previous 3 years, including cont	ractual employment of services. YesNo
If your answer is yes, please answ	er each of the following questions.	
 Are you currently an office Highway Authority? 	r or employee of either the Capitol	Development Board or the Illinois Toll YesNo
currently appointed to or e exceeds \$90,420.00, (60°	ed to or employed by any agency mployed by any agency of the State % of the Governor's salary as of 7/ employed and your annual salary.	e of Illinois, and your annual salary

3.	If you are currently appointed to or employed by any ager salary exceeds \$90,420.00, (60% of the Governor's salar (i) more than 7 1/2% of the total distributable income corporation, or (ii) an amount in excess of the salary of the	ry as of 7/1/01) are you entitled to receive of your firm, partnership, association or
4.	If you are currently appointed to or employed by any ager salary exceeds \$90,420.00, (60% of the Governor's salar or minor children entitled to receive (i) more than 15% in a of your firm, partnership, association or corporation, or (ii salary of the Governor?	ry as of 7/1/01) are you and your spouse aggregate of the total distributable income
` '	employment of spouse, father, mother, son, or daughter, inc previous 2 years.	cluding contractual employment for services
	answer is yes, please answer each of the following questio	YesNo ns.
1.	Is your spouse or any minor children currently an officer or Board or the Illinois Toll Highway Authority?	employee of the Capitol Development YesNo
2.	Is your spouse or any minor children currently appointed to of Illinois? If your spouse or minor children is/are currently agency of the State of Illinois, and his/her annual salary of Governor's salary as of 7/1/01) provide the name of the spof the State agency for which he/she is employed and his/h	y appointed to or employed by any exceeds \$90,420.00, (60% of the pouse and/or minor children, the name
3.	If your spouse or any minor children is/are currently appoir State of Illinois, and his/her annual salary exceeds \$90,42 as of 7/1/01) are you entitled to receive (i) more than 71/29 firm, partnership, association or corporation, or (ii) an a Governor?	0.00, (60% of the salary of the Governor 60% of the total distributable income of your
4.	If your spouse or any minor children are currently appointed State of Illinois, and his/her annual salary exceeds \$90,420 7/1/01) are you and your spouse or any minor children entiaggregate of the total distributable income from your firm, p (ii) an amount in excess of 2 times the salary of the Govern	0.00, (60% of the Governor's salary as of itled to receive (i) more than 15% in the partnership, association or corporation, or or?
		Yes No
unit of I	e status; the holding of elective office of the State of Illinois, local government authorized by the Constitution of the State currently or in the previous 3 years.	
` '	nship to anyone holding elective office currently or in the production daughter.	evious 2 years; spouse, father, mother, YesNo
Americ of the S	tive office; the holding of any appointive government office of a, or any unit of local government authorized by the Constitute of Illinois, which office entitles the holder to compensate charge of that office currently or in the previous 3 years.	ution of the State of Illinois or the statues
` '	nship to anyone holding appointive office currently or in the laughter.	previous 2 years; spouse, father, mother, YesNo
(g) Employ	yment, currently or in the previous 3 years, as or by any reg	istered lobbyist of the State government. YesNo

(h) Relationship to a son, or daughter.	nyone who is or was a registered lobbyist in the previous 2 years; s Yes _	spouse, father, mother, No
committee registe	nployment, currently or in the previous 3 years, by any registered red with the Secretary of State or any county clerk of the State of I registered with either the Secretary of State or the Federal Board o	llinois, or any political
last 2 years by any county clerk of the	nyone; spouse, father, mother, son, or daughter; who was a compey registered election or re-election committee registered with the See State of Illinois, or any political action committee registered with real Board of Elections. Yes _	ecretary of State or any
	APPLICABLE STATEMENT	
This Disclosure Fo	rm A is submitted on behalf of the INDIVIDUAL named on prev	ious page.
Completed by:		
	Name of Authorized Representative (type or print)	
Completed by:		
•	Title of Authorized Representative (type or print)	
Completed by:		
•	Signature of Individual or Authorized Representative	Date
	NOT APPLICABLE STATEMENT	
	hat no individuals associated with this organization meet the tion of this Form A.	criteria that would
This Disclosure Fo	rm A is submitted on behalf of the CONTRACTOR listed on the	e previous page.
	Name of Authorized Representative (type or print)	
	Title of Authorized Representative (type or print)	
	Signature of Authorized Representative	Date

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form B Other Contracts & Procurement Related Information Disclosure

		Disclosure	
Contractor Name			
Legal Address			
City, State, Zip		_	
Telephone Number	Email Address	Fax Number (if available)	
,		, , ,	
	tion contained in this Form is required by the		
·	information shall become part of the publicly		
be completed for bids in ϵ	excess of \$10,000, and for all open-ended co	intracts.	
DISCLOS	SURE OF OTHER CONTRACTS AND PRO	CUREMENT RELATED INFORMATION	
has any pending contra- any other State of Illinoi	ontracts & Procurement Related Informaticts (including leases), bids, proposals, or othes agency: Yes No bidder only needs to complete the signature	er ongoing procurement relationship with	
	 Identify each such relationship by showing sor project number (attach additional pages a 		
	THE FOLLOWING STATEMENT	MUST BE SIGNED	
	Name of Authorized Representativ	e (type or print)	
	Title of Authorized Representative	(type or print)	
	Signature of Authorized Repr	esentative Date	_

SPECIAL NOTICE TO CONTRACTORS

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



Contract No. 85390
WINNEBAGO County
Section 03-00520-00-WR (Rockford)
Project ACF-525(107)
Route FAP 525 (Harrison Avenue)
District 2 Construction Funds

PART I. IDENTIFICA	ATION																	
Dept. Human Rights	s #						Du	ıration	of Proje	ect: _						-		
Name of Bidder:																_		
PART II. WORKFO A. The undersigned which this contract wor projection including a p	bidder ha	s analyz perform for mino	ed min ed, and rity and	d for the d fema TAI	ne locati ale empl BLE A	ons fro	om whi	ch the b on in all	idder re	cruits	employe	es, and h	ereb	y subm	its the follo	owir con	ng workfo	
		TOTA	AL Wo	rkforce	Project	tion for	Contr	act							CURRENT		_	S
				MIN	ORITY E	EMPLO	OYEES	3	TO BE ASSIGNED TO CONTRACT									
JOB CATEGORIES	TO [*] EMPLO		BLA	ACK	HISP	ANIC	_	HER NOR.		APPREN- ON THE JOB TICES TRAINEES			TOTAL EMPLOYEES		MINORITY EMPLOYEE			
	М	F	М	F	М	F	М	F	М	F	М	F		М	F	1	М	F
OFFICIALS (MANAGERS)																		
SUPERVISORS																		
FOREMEN																		
CLERICAL																		
EQUIPMENT OPERATORS																		
MECHANICS																		
TRUCK DRIVERS																		
IRONWORKERS																		
CARPENTERS																		
CEMENT MASONS																		
ELECTRICIANS																		
PIPEFITTERS, PLUMBERS																		
PAINTERS																		
LABORERS, SEMI-SKILLED																		
LABORERS, UNSKILLED																		
l		1	1	ı	1	ı	ı	l	1	I	l	1				ı	ı l	

TOTAL Training Projection for Contract									
EMPLOYEES	TO	TAL					*OTHER		
IN	EMPLO	DYEES	BLA	BLACK HISPAI			MINOR.		
TRAINING	М	F	М	F	М	F	М	F	
APPRENTICES									
ON THE JOB TRAINEES									

TABLE C

TOTAL

Please specify race of each employee shown in Other Minorities column.

Note: See instructions on the next page

FOR DEPARTMENT USE ONLY

^{*}Other minorities are defined as Asians (A) or Native Americans (N).

Contract No. 85390 WINNEBAGO County Section 03-00520-00-WR (Rockford) Project ACF-525(107) Route FAP 525 (Harrison Avenue) District 2 Construction Funds

PART II. WORKFORCE PROJECTION - continued

B.		ded in "Total Emp the undersigned l				r of new h	ires that wo	ould be employed in the
		undersigned bidderecruited from or base of operati		new hires				new hires would ed; and/or (number) ch the bidder's principal
C.	Includ	·	oyees" unde	er Table A is a				employed directly by the contractors.
	The ube dir	indersigned bidde ectly employed by oyed by subcontra	r estimates t y the prime octors.	that (number) ₋ contractor and	that (number) _			persons will persons will be
PART	III. AFF	FIRMATIVE ACTION	ON PLAN					
A.	utiliza in any comm (geare utiliza	ition projection inc y job category, an nencement of wor ed to the comple	eluded under nd in the eve rk, develop etion stages d. Such Affir	PART II is detent that the un and submit a of the contra rmative Action	termined to be a dersigned bidde written Affirma ct) whereby de	n underutilizer is awarde tive Action ficiencies ir	zation of mir ed this contr Plan includi n minority a	y and female employee nority persons or women act, he/she will, prior to ing a specific timetable nd/or female employee contracting agency and
B.	subm		he goals and	d timetable inc				ree utilization projection if required, are deemed
Comp	any				Tel	ephone Nur	mber	
Addre	ss							
				NOTICE R	EGARDING SIGN	NATURE		
		Bidder's signature or s to be completed or			et will constitute th	e signing of	this form. The	e following signature block
	Signa	iture:			Title:			Date:
Instruct	ions:	All tables must include	de subcontracto	or personnel in add	dition to prime contra	ctor personnel		
Table A	. -	(Table B) that will be	e allocated to co	ontract work, and	include all apprentic	es and on-the-	-job trainees. T	al number currently employed The "Total Employees" column d on the contract work.
Table B	3 -	Include all employee currently employed.	es currently emp	ployed that will be	allocated to the cont	tract work inclu	iding any appre	entices and on-the-job trainees
Table C	; -	Indicate the racial br	eakdown of the	total apprentices	and on-the-job traine	es shown in T	able A.	BC-1256-Pg. 2 (Rev. 3/98)

ADDITIONAL FEDERAL REQUIREMENTS

In addition to the Required Contract Provisions for Federal-Aid Construction Contracts (FHWA 1273), all bidders make the following certifications.

CERTIFICATION, EQUAL EMPLOYMENT OPPORTUNITY:

YES _____ NO ____

B.

A. By the execution of this proposal, the signing bidder certifies that the bidding entity has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action, in restraint of free competitive bidding in connection with the submitted bid. This statement made by the undersigned bidder is true and correct under penalty of perjury under the laws of the United States.

1.	Have you participated in any previous contracts or subcontracts subject to the equal opportunity clause. YES NO
2.	If answer to #1 is yes, have you filed with the Joint Reporting Committee, the Director of OFCC, any Federal agency, or the former President's Committee on Equal Employment Opportunity, all reports due under the applicable filing requirements of those organizations?

Contract No. 85390 WINNEBAGO County Section 03-00520-00-WR (Rockford) Project ACF-525(107) Route FAP 525 (Harrison Avenue) District 2 Construction Funds

PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 3 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name	
(IF AN INDIVIDUAL)	Signature of Owner	
	Firm Name	
	Ву	
(IF A CO-PARTNERSHIP)		
		Name and Address of All Members of the Firm:
<u> </u>		
	Corporate Name	
	Ву	Signature of Authorized Representative
(IF A CORPORATION)		Signature of Authorized Representative
		Typed or printed name and title of Authorized Representative
	Attest	Signature
(IF A JOINT VENTURE, USE THIS SECTION FOR THE MANAGING PARTY AND THE	Pusinosa Address	
SECOND PARTY SHOULD SIGN BELOW)	Business Address	
	Corporate Name	
(IF A JOINT VENTURE)	, Jy	Signature of Authorized Representative
		Typed or printed name and title of Authorized Representative
	Attest	
		Signature
	Business Address	
If more than two parties are in the joint venture, p	olease attach an addit	ional signature sheet.

RETURN WITH BID



Division of Highways Proposal Bid Bond

(Effective November 1, 1992)

	Item No.
	Letting Date
KNOW ALL MEN BY THESE PRESENTS, That We	
as PRINCIPAL, and	
	as SURETY, are
Article 102.09 of the "Standard Specifications for Road and Bridge	NOIS in the penal sum of 5 percent of the total bid price, or for the amount specified in the Construction" in effect on the date of invitation for bids, whichever is the lesser sum, well tent of which we bind ourselves, our heirs, executors, administrators, successors and assigns.
	S SUCH, That Whereas, the PRINCIPAL has submitted a bid proposal to the STATE OF the improvement designated by the Transportation Bulletin Item Number and Letting Date
the bidding and contract documents, submit a DBE Utilization Plat PRINCIPAL shall enter into a contract in accordance with the term coverages and providing such bond as specified with good and sufflabor and material furnished in the prosecution thereof; or if, in the into such contract and to give the specified bond, the PRINCIPAL	proposal of the PRINCIPAL; and if the PRINCIPAL shall, within the time and as specified in that is accepted and approved by the Department; and if, after award by the Department, the is of the bidding and contract documents including evidence of the required insurance ficient surety for the faithful performance of such contract and for the prompt payment of event of the failure of the PRINCIPAL to make the required DBE submission or to enter pays to the Department the difference not to exceed the penalty hereof between the amount Department may contract with another party to perform the work covered by said bid hall remain in full force and effect.
Surety shall pay the penal sum to the Department within fifteen (15	has failed to comply with any requirement as set forth in the preceding paragraph, then by days of written demand therefor. If Surety does not make full payment within such mount owed. Surety is liable to the Department for all its expenses, including attorney's or in part.
In TESTIMONY WHEREOF, the said PRINCIPAL and	said SURETY have caused this instrument to be signed by their respective officers this A.D.,
PRINCIPAL	SURETY
(Company Name)	(Company Name)
By:	By:
(Signature & Title)	(Signature of Attorney-in-Fact)
Notar	y Certification for Principal and Surety
STATE OF ILLINOIS, COUNTY OF	
I,	, a Notary Public in and for said County, do hereby certify that
and	
(Insert names of individua	als signing on behalf of PRINCIPAL & SURETY)
	se names are subscribed to the foregoing instrument on behalf of PRINCIPAL and and respectively, that they signed and delivered said instrument as their free and voluntary
Given under my hand and notarial seal this day	y of, A.D
My commission expires	
	Notary Public
	the Principal may file an Electronic Bid Bond. By signing below the Principal is ensuring pal and Surety are firmly bound unto the State of Illinois under the conditions of the bid
Electronic Bid Bond ID# Company/Bidder Name	Signature and Title

PROPOSAL ENVELOPE



PROPOSALS

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

Submitted By:

Name:	
Address:	
Phone No.	

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

NOTICE

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

NOTICE

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. 85390
WINNEBAGO County
Section 03-00520-00-WR (Rockford)
Project ACF-525(107)
Route FAP 525 (Harrison Avenue)
District 2 Construction Funds



Illinois Department of Transportation

NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway, in Springfield, Illinois until 10:00 o'clock a.m., June 16, 2006. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- **2. DESCRIPTION OF WORK**. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 85390
WINNEBAGO County
Section 03-00520-00-WR (Rockford)
Project ACF-525(107)
Route FAP 525 (Harrison Avenue)
District 2 Construction Funds

Project consists of the resurfacing of Harrison Avenue from 26th Street east to Alpine Road and the reconstruction of Harrison Avenue from Alpine Road east to approximately 800' east of Mulford Road, five signalized intersections are to be modernized and lighting improvements all located in the City of Rockford.

- 3. INSTRUCTIONS TO BIDDERS. (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
 - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Timothy W. Martin, Secretary

BD 351 (Rev. 01/2003)

INDEX FOR

SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS Adopted March 1, 2005

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 1-1-02) (Revised 3-1-05)

SUPPLEMENTAL SPECIFICATIONS

Std. Sr		ge No.
101	Definition of Terms	1
105	Control of Work	
205	Embankment	3
251	Mulch	4
281	Riprap	5
282	Filter Fabric for Use With Riprap	
285	Concrete Revetment Mats	
311	Granular Subbase	
351	Aggregate Base Course	
440	Removal of Existing Pavement and Appurtenances	
442	Pavement Patching	
449	Removal and Replacement of Preformed Elastomeric Compression Joint Seal	
481	Aggregate Shoulders	19
501	Removal of Existing Structures	
	Concrete Structures	21
503	Steel Structures	
505		
506	Cleaning and Painting Metal Structures	
508	Reinforcement Bars	
512	Piling	
540	Box Culverts	28
589	Elastic Joint Sealer	30
602	Catch Basin, Manhole, Inlet, Drainage Structures and Valve Vault	
	Construction, Adjustment and Reconstruction	31
603	Adjusting Frames and Grates of Drainage and Utility Structures	
610	Shoulder Inlets with Curb	
665	Woven Wire Fence	
669	Removal and Disposal of Regulated Substances	
671	Mobilization	
702	Work Zone Traffic Control Devices	
1003	Fine Aggregates	. 38
1004	Coarse Aggregate	. 39
1005	Stone, Concrete Blocks and Broken Concrete for Erosion Protection,	
	Sediment Control and Rockfill	42
1006	Metals	
1007	Timber and Preservative Treatment	
1012	Hydrated Lime	
1020	Portland Cement Concrete	. 51
1021	Concrete Admixtures	
1022	Concrete Curing Materials	_
1024	Nonshrink Grout	
1041	Brick	
1043	Precast Reinforced Concrete Manhole Sections and Adjusting Rings	
1056	Preformed Flexible Gaskets and Mastic Joint Sealer for Sewer and Culvert Pipe	
	Elastic Joint Sealers	
1059		
1060	Waterproofing Materials	
1069	Pole and Tower	
1070	Foundation and Breakaway Devices	
1077	Post and Foundation	
1080	Fabric Materials	
1081	Materials For Planting	
1083	Elastomeric Bearings	
1094	Overhead Sign Structures	
1103	Portland Cement Concrete Equipment	. 79

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS and RECURRING LOCAL ROADS AND STREETS SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

CHECK		PAGE NO.
1 X	State Required Contract Provisions All Federal-aid Construction Contracts (Eff. 2-1-69) (Rev. 10-1-	83) 80
2 X	Subletting of Contracts (Federal-aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93)	82
3 X	FEO (Fff 7-21-78) (Rev. 11-18-80)	83
4	Specific Equal Employment Opportunity Responsibilities NonFederal-aid Contracts	
•	(Eff 3-20-60) (Pay 1-1-04)	94
5	Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 4-1-93)	100
	Reserved	105
6	Asphalt Quantities and Cost Reviews (Eff. 7-1-88)	106
7	National Pollutant Discharge Elimination System Permit (Eff. 7-1-94) (Rev. 1-1-03)	100
	National Pollutant Discharge Elimination System Permit (Eli. 7-1-94) (Rev. 1-1-93)	107
9	Haul Road Stream Crossings, Other Temporary Stream Crossings and In-Stream Work Pads	400
	(Eff. 1-2-92) (Rev. 1-1-98)	108
10	Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-02)	109
11	Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-02)	112
12	Use of Geoteytile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-97)	115
13	Asphaltic Emulsion Slurry Seal and Fibrated Asphaltic Emulsion Slurry Seal (Eff. 8-1-89) (Rev. 2-1-	97) 117
14	Bituminous Surface Treatments Half-Smart (Eff. 7-1-93) (Rev. 1-1-97)	123
	Quality Control/Quality Assurance of Bituminous Concrete Mixtures (Eff. 1-1-00) (Rev. 3-1-05)	120
15	Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 2-1-95)	1/10
16	Subsealing of Concrete Pavernerits (En. 11-1-64) (Rev. 2-1-93)	140 450
17	Bituminous Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 10-15-97)	102
18	Resurfacing of Milled Surfaces (Eff. 10-1-95)	154
19	PCC Partial Depth Bituminous Patching (Eff. 1-1-98)	155
20	Patching with Bituminous Overlay Removal (Eff. 10-1-95) (Rev. 7-1-99)	157
21	Reserved	159
22	Protective Shield System (Eff. 4-1-95) (Rev. 1-1-03)	160
23	Polymer Concrete (Eff. 8-1-95) (Rev. 3-1-05)	162
24	Controlled Low-Strength Material (CLSM) (Eff. 1-1-90) (Rev. 3-1-05)	164
25 X	Pine Underdrains (Eff. 9-9-87) (Rev. 1-1-98)	169
26	Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97)	170
27	Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-97)	175
	Reserved	177
28	Reserved	178
29	Reserved	
30	Night Time Inspection of Roadway Lighting (Eff. 5-1-96)	180
	Night Time Inspection of Roadway Lighting (Ell. 5-1-90)	100
32	Reserved	400
33	English Substitution of Metric Bolts (Eff. 7-1-96)	
34	English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03)	183
35	Polymer Modified Emulsified Asphalt (Eff. 5-15-89) (Rev. 1-1-04)	185
36	Corrosion Inhibitor (+π. 3-1-80) (Rev. 7-1-99)	107
37	Quality Control of Concrete Mixtures at the Plant-Single A (Eff. 8-1-00) (Rev. 1-1-04)	188
38	Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04)	194
39 X	Quality Control/Quality Assurance of Concrete Mixtures (Eff. 4-1-92) (Rev. 3-1-05)	202
40	Traffic Barrier Terminal Type 1, Special (Eff. 8-1-94) (Rev. 1-1-03)	215
41	Reserved	216
42	Segregation Control of Bituminous Concrete (Eff. 7-15-97)	217
43	Reserved	220
	LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS	
	LOOKE NO INCLETO RECOVERED WITH CO. LOVIET NO.	PAGE NO.
1004	Commenter Math. 1838 of CF 4.4.00 (Per 4.4.00)	222
LRS 1	Cooperation With Utilities (Eff. 1-1-99) (Rev. 1-1-02)	
LRS 2	Furnished Excavation (Eff. 1-1-99) (Rev. 1-1-02)	224
LRS 3	☐ Construction Zone Traffic Control (Eff. 1-1-99	225
LRS 4	☐ Flaggers in Work Zones (Eff. 1-1-99)	226
LRS 5	Reserved	227
LRS 6	Bidding Requirements and Conditions for Contract Proposals (Eff. 1-1-02)	228
LRS 7	Bidding Requirements and Conditions for Material Proposals (Eff. 1-1-03)	234
	☐ Failure to Complete the Work on Time (Eff. 1-1-99)	240
LRS 8		241
LRS 9	Bituminous Surface Treatments (Eff. 1-1-99)	
LRS 10		242
LRS 11		243
LRS 12	Wages of Employees on Public Works (Eff. 1-1-99)	245
LRS 13	Selection of Labor (Eff. 1-1-99)	246

INDEX OF SPECIAL PROVISIONS

Location and Description of Work1
Project Completion Date1
Combination Concrete Curb and Gutter Removal and Replacement1
Saw Cuts2
Bituminous Shoulders Superpave 6"2
Concrete Headwall Removal2
Pipe Culvert Removal2
Fire Hydrant to be Adjusted3
Fire Hydrant to be Relocated3
Water Main 16"3
Inlets, Special4
Combination Concrete Curb and Gutter, Type B-6.064
Concrete Median, Type SB (Special)4
Traffic Control Complete4
Install Existing Sign Panel11
Service Installation, Type B11
Full-Actuated Controller and Type V Cabinet, Special11
Full-Actuated Controller in Existing Cabinet12
Steel Combination Mast Arm Assembly and Pole12
Concrete Foundation, Type E, 36 Inch Diameter12
Light Detector & Light Detector Amplifier12
Temporary Traffic Signal Installation13

Remove Existing Traffic Signal Equipment	13
Inlets, Type 700	13
Bare Copper Wire, 1/C No. 8	13
Removing Existing Light Pole	14
Electric Cable in Conduit, 600B 1/C No. 6 THHN/THWN	14
Video Vehicle Detection System	14
Video Vehicle Detector	15
Storm Sewer (Water Main Requirements)	15
Video Surveillance System, Complete	16
Emergency Vehicle Priority System, Line Sensor Cable, No. 20 3/C	20
Storm Sewer Water Main	20
Electric Cable in Conduit, Grounding N6 1/C	20
Double Inlets, Type 700	21
Fiber Optic Cable in Conduit, 48 Fiber, Single Mode and 24 Fiber Mode	21
Light Pole, Aluminum, Transformer Base, 40 FT. M.H., 10 FT. Davit Arm	34
Luminaire, Pulse Start Metal Halide, 150 Watt	34
Luminaire, Pulse Start Metal Halide, 400 Watt	34
Storm Water Pollution Prevention Plan	35

INDEX LOCAL ROADS AND STREETS SPECIAL PROVISIONS

_R#	TITLE	<u>PAGE</u>
SD 16	"Slab Movement Detection Device" (Eff. 11-1-84)	•
SD 17	"Required Cold Milled Surface Texture" (Eff. 11-1-87)	
105	"Cooperation with Utilities" (Eff 1/1/99) (Rev 1/1/06)	
107-1	"Nationwide Permit No. 14" (Eff. 2-1-04) (Rev. 3-1-05). Developed by the Bureau of Local Roads and Streets to outline the necessary requirements to comply with No. 14 permits.	•
107-2	"Railroad Protective Liability Insurance for Local Lettings" (Eff. 3-1-05). Developed by the Bureau of Local Roads & Streets to require insurance policies to be submitted to the letting agency rather than the department.	
107-3	"Wages of Employees on Public Works" (Eff 8-10-95)	
108	"Combination Bids (Eff. 1-1-94)(Rev. 3-1-05). Developed by the Bureau of Local Roads & Streets to allow the revision of working days and calendar days. Revised to incorporate applicable portions of deleted Sections 102 & 103	
109	"Contract Claims" (Eff. 1-1-02) (Rev. 5-1-02). Developed by the Bureau of Local Roads	
212	"Shaping Roadway" (Eff. 8-1-69) (Rev. 1-1-02)	
302	Rescinded	
355-1	"Asphalt Stabilized Base Course, Road Mix or Traveling Plant Mix" (Eff. 10-1-73)(Rev. 1-1-02)	
355-2	"Asphalt Stabilized Base Course, Plant Mix" (Eff. 2-20-63)(Rev. 1-1-02)	
355-3	"Bituminous Aggregate Mixture Base Course" (6-27-66)(Rev. 1-1-02). Developed by the	
	Bureau of Materials and Physical Research and the Bureau of Local Roads and Streets to construct a stabilized base course with paving grade asphalt.	
400		
400 402	"Penetrating Emulsified Prime" (Eff. 4-1-84)(Rev. 1-1-02)	
403-1	"Penetrating Emulsified Asphalt" (Eff. 1-1-94)(Rev. 1-1-02). Developed for bituminous	
	surface treatments on roads that require flexibility and penetration due to low traffic volume.	
403-2	Bituminous Hot Mix Sand Seal Coat" (Eff. 8-1-69)(Rev. 1-1-02)	
420	"PCC Pavement (Special)" (Eff. 5-12-64)(Rev. 1-1-02). Developed by the Bureau of Local Roads & Streets to allow local agencies to construct quality PCC pavements for low volume roads.	•
430	"Paving Brick and Concrete Paver Pavements and Sidewalks" (Eff 1-1-04) Developed by the Bureau	
	of Local Roads & Streets and the Bureau of Materials & Physical Research to provide statewide requirements for paving brick and concrete paver pavements and sidewalks.	
442	"Bituminous Patching Mixtures for Maintenance Use" (Eff 1-1-04). Developed by the Bureau of Local Roads	
112	& Streets to reference approved bituminous patching mixtures.	,,
451	"Crack Filling Bituminous Pavement with Fiber-Asphalt" (Eff. 10-1-91)(Rev. 1-1-02)	
503-1	"Furnishing Class SI Concrete" (Eff. 10-1-73)(Rev. 1-1-02)	
503-2	"Furnishing Class SI Concrete (Short Load)" (Eff. 1-1-89) (Rev. 1-1-02). Developed by the Bureau of Local Roads and Streets to allow a load charge to be added when short loads are expected during the contract.	
542	"Pipe Culverts, Type (Furnished)" (Eff. 9-1-64) (Rev. 1-1-02)	
663	"Calcium Chloride Applied" (Eff. 6-1-58) (Rev. 1-1-02)	
671	Rescinded	
701	"Flagger Certification" (Eff. 1-1-93) (Rev. 1-1-02)	
701	"Construction and Maintenance Signs" (Eff 1-1-04) Developed by the Bureau of Local Roads & Streets to	
102		
1004	require florescent orange sheeting and a minimum sign size of 48" X 48" on construction and maintenance signs "Coarse Aggregate for Bituminous Surface Treatment" (Eff. 1-1-02). Developed by the Bureau of Materials &	
1004	Physical Research, the Bureau of Local Roads & Streets, and Local Agencies to provide a coarser mix when aggregate producers have adjusted the CA-16 gradation according to the Aggregate Gradation	• • • • • • • • • • • • • • • • • • • •
	Control System (AGCS) to a finer mix for Hot-Mix Asphalt.	
1013	"Rock Salt (Sodium Chloride)" (Eff. 8-1-69) (Rev. 1-1-02)	

BDE SPECIAL PROVISIONS For The April 28, and June 16, 2006 Lettings

The following special provisions indicated by an "x" are applicable to this contract. An * indicates a new or revised special provision for the letting.

<u>File Name</u>	<u>PG</u> #		Special Provision Title		<u>Effective</u>	Revised
80099	<u>11</u>	Accessible Po	edestrian Signals (APS)		April 1, 2003	
80156	43		nipping Tickets		Jan. 1, 2006	
80108			aring Pad Removal		Nov. 1, 2003	
72541			iterproofing Membrane and Asbestos Bituminou face Removal	ıs	June 1, 1989	June 30,1994
80128			Railroad Engineer		July 1, 2004	
80065			ase Course/Widening Superpave		April 1, 2002	Aug. 1, 2005
80050	44		oncrete Surface Course		April 1, 2001	April 1, 2003
80142	45		quipment, Spreading and Finishing Machine		Jan. 1, 2005	
80066		Bridge Deck			April 1, 2002	April 1, 2004
50261		Building Rem	oval-Case I (Non-Friable and Friable Asbestos))	Sept. 1, 1990	Aug. 1, 2001
50481		Building Rem	oval-Case II (Non-Friable Asbestos)		Sept. 1, 1990	Aug. 1, 2001
50491		Building Rem	oval-Case III (Friable Asbestos)		Sept. 1, 1990	Aug. 1, 2001
50531		Building Rem	oval-Case IV (No Asbestos)		Sept. 1, 1990	Aug. 1, 2001
80118	46	X Butt Joints			April 1, 2004	April 1, 2005
80031		Calcium Chlo	oride Accelerator for Portland Cement Concrete	Patching	Jan. 1, 2001	
80077		Chair Suppor			Nov. 1, 2002	Nov. 2, 2002
80051	47		egate for Trench Backfill, Backfill and Bedding		April 1, 2001	Nov. 1, 2003
80094	54	X Concrete Adr	mixtures		Jan. 1, 2003	July 1, 2004
80112		Concrete Bar			Jan. 1, 2004	April 2, 2004
80102			Metal Pipe Culverts		Aug. 1, 2003	July 1, 2004
80114	59		rotection of Concrete Construction		Jan. 1, 2004	Nov. 1, 2005
80146	67	X Detectable W			Aug. 1, 2005	
80029	69		ed Business Enterprise Participation		Sept. 1, 2000	June 22, 2005
80144		Elastomeric I	-		April 1, 2005	
31578	77		ng on Reinforcement		April 1, 1997	Jan. 1, 2003
80041		Epoxy Paven			Jan. 1, 2001	Aug. 1, 2003
80055	78		Sediment Control Deficiency Deduction		Aug. 1, 2001	Nov. 1, 2001
80103	79	X Expansion Jo			Aug. 1, 2003	1 4 0000
80101	80	X Flagger Vest			April 1, 2003	Jan. 1, 2006
80079	81	X Freeze-Thaw			Nov. 1, 2002	N 4 0004
80072		Furnished Ex			Aug. 1, 2002	Nov. 1, 2004
80054	82	X Hand Vibrato			Nov. 1, 2003	
80147		Illuminated S			Aug. 1, 2005	
80109		Impact Attend			Nov. 1, 2003	April 1, 2004
80110			uators, Temporary		Nov. 1, 2003 Aug. 1, 2003	April 1, 2004
80104		Inlet Filters	and Disc Culticate		Nov. 1, 2002	Aug. 1, 2003
80080	02	Insertion Lini	ng of Pipe Culverts g Diode (LED) Pedestrian Signal Head		Nov. 1, 2002	April 1, 2006
* 80150	83		g Diode (LED) Pedestriait Signal Head		April 1, 2002	Nov. 1, 2005
80067	85		g Diode (LED) Signal Head on Requirements		Nov. 1, 2002	1404. 1, 2000
80081 * 80133		and the same and the same of t	ed Soil Mixture		Nov. 1, 2004	April 1, 2006
* 80158		Manholes	Cd Coll Mixture		April 1, 2006	April 1, 2000 ;
80045		Material Tran	sefar Davica	**************************************	June 15, 1999	March 1, 2001
80137			ne Width with Lane Closure		Jan. 1, 2005	
80138	87	X Mulching Sec			Jan. 1, 2005	
80082	88		vement Patching		Nov. 1, 2002	
80129			dge Longitudinal Joint		July 1, 2004	
80069			-Rich Paint System		Nov. 1, 2001	Aug. 1, 2003
			•		•	

<u>File Name</u>	<u>PG</u> #		Special Provision Title	Effective	<u>/e</u>	Revised
80116	<u>#</u>	Х	Partial Payments	Sept. 1,	2003	
80013			Pavement and Shoulder Resurfacing	Feb. 1,		July 1, 2004
53600	90	X	Pavement Thickness Determination for Payment	April 1,	1999	Jan. 1, 2004
* 80022	95	Χ	Payments to Subcontractors	June 1,	2000	Jan. 1, 2006
80155	97	X	Payrolls and Payroll Records	Aug. 10,		
80130	99	Х	Personal Protective Equipment	July 1,		•
80148			Planting Woody Plants	Jan. 1,		
80134			Plastic Blockouts for Guardrail	Nov. 1,		
80073			Polymer Modified Emulsified Asphalt	Nov. 1,		
80119			Polyurea Pavement Marking	April 1,		
80124			Portable Changeable Message Signs	Nov. 1,		April 2, 2004
80139	100	X	Portland Cement	Jan. 1,		Nov. 1, 2005
80083	101	Х	Portland Cement Concrete	Nov. 1,		
80036	102	X	Portland Cement Concrete Patching	Jan. 1,		Jan. 1, 2004
419	106	X	Precast Concrete Products	July 1,		Nov. 1, 2004
80120			Precast, Prestressed Concrete Members	April 1,		
80084	107	X	Preformed Recycled Rubber Joint Filler	Nov. 1,		
80015	108	X	Public Convenience and Safety	Jan. 1,		
80121			PVC Pipeliner	April 1,		April 1, 2005
* 80159			Railroad Flaggers	April 1,		and the second second
80122			Railroad, Full-Actuated Controller and Cabinet	April 1,		
34261			Railroad Protective Liability Insurance	Dec. 1,		Jan. 1, 2006
80157			Railroad Protective Liability Insurance (5 and 10)	Jan. 1,		
80105			Raised Reflective Pavement Markers (Bridge)	Aug. 1,		
80011	109	X	RAP for Use in Bituminous Concrete Mixtures	Jan. 1,		April 1, 2002
* 80160		X	Reflective Crack Control Treatment	April 1,		
80151	117	X	Reinforcement Bars	Nov. 1,		Nov. 2, 2005
80032			Remove and Re-Erect Steel Plate Beam Guardrail and Traffic Barrier Terminals	Jan. 1,		Jan. 1, 2005
80085			Sealing Abandoned Water Wells	Nov. 1,		
80131	119	X	Seeding and Sodding	July 1,		Aug. 1, 2005
80152	122	X	Self-Consolidating Concrete for Cast-In-Place Construction	Nov. 1,		
80132	128	X	Self-Consolidating Concrete for Precast Products	July 1,		Nov. 1, 2005
80096			Shoulder Rumble Strips	Jan. 1,		
80140			Shoulder Stabilization at Guardrail	Jan. 1,	ara e em sanconio	A : 11 4 0000
* 80135	400		Soil Modification			
80070	130	X	Stabilized Subbase and Bituminous Shoulders Superpave	April 1,		Aug. 1, 2005
80127			Steel Cost Adjustment	April 2,		July 1, 2004
80153	400	L	Steel Plate Beam Guardrail	Nov. 1,		
80143	136	X	Subcontractor Mobilization Payments	April 2,		
80086	137	X	Subgrade Preparation	Nov. 1,		
80136	420	L	Superpave Bituminous Concrete Mixture IL-4.75	Nov. 1,		A mil 4 2004
80010	138	X	Superpave Bituminous Concrete Mixtures Superpave Bituminous Concrete Mixtures (Low ESAL)	Jan. 1,		April 1, 2004 April 1, 2004
80039 80075			Surface Testing of Pavements	Jan. 1, April 1,		Nov. 1, 2004
			•	June 11,		NOV. 1, 2005
80145			Suspension of Slipformed Parapets	Oct. 1,		Nov. 1, 2003
80092 80087	145	X	Temporary Concrete Barrier Temporary Erosion Control	Nov. 1,		1100. 1, 2003
	140	 ^-		Jan. 1,		
80008 80106			Temporary Module Glare Screen System Temporary Portable Bridge Traffic Signals	Aug. 1,		
80098			Traffic Barrier Terminals	Jan. 1,		
5729I	147	X	Traffic Control Deficiency Deduction	April 1,		Jan. 1, 2005
* 80161	148	X	Troffic Signal Craumding	April 1,		Juli. 1, 2003
20338	149	X	Training Special Provisions	Oct. 15,		
80107	152	X	Transient Voltage Surge Suppression	Aug. 1,		
00107	102		1 Translate Voltage Carge Suppression	, nug. 1,	2000	

File Name	<u>PG</u> #		Special Provision	<u>Title</u>	<u>Effective</u>	<u>Revised</u>
80123	154	Χ	Truck Bed Release Agent		April 1, 2004	
80154	a management code		Turf Reinforcement Mat	wand historial which the provides the memorian all approximation in the contract of the contra	Nov. 1, 2005)
* 80162			Uninterruptable Power Supply (UPS)		April 1, 2006	
80149	155	Х	Variable Spaced Tining		Aug. 1, 2005	;)
* 80163			Water Blaster with Vacuum Recovery		April 1, 2006	
80048	156	X	Weight Control Deficiency Deduction		April 1, 2001	Aug. 1, 2002
80090			Work Zone Public Information Signs	;	Sept. 1, 2002	? Jan. 1, 2005
80125			Work Zone Speed Limit Signs		April 2, 2004	Jan. 1, 2006
80126			Work Zone Traffic Control		April 2, 2004	Nov. 1, 2005
80097	158	Х	Work Zone Traffic Control Devices		Jan. 1, 2003	Nov. 1, 2004
80071			Working Days		Jan. 1, 2002	<u>)</u>

The following special provisions have been deleted from use:

80141 Additional Award Criteria

This special provision is no longer required.

80113 Curb Ramps for Sidewalk Warnings".

This special provision has been replaced by the BDE Special Provision, "Detectable

The following special provisions require additional information from the designer. The additional information needs to be included in a separate document attached to this check sheet. The Project Development and Implementation section will then include the information in the applicable special provision. The Special Provisions are:

- Building Removal-Case I
- Building Removal-Case II
- Building Removal-Case III
- Building Removal-Case IV
- DBE Participation
- Material Transfer Device
- Railroad Protective Liability Insurance
- Training Special Provisions
- Working Days

STATE OF ILLINOIS SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2002, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures of Materials" in effect on the date of invitation of bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of Harrison Avenue (Section 03-00520-00-WR), City of Rockford, and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION AND DESCRIPTION OF WORK

The proposed project includes resurfacing and reconstruction of the existing four-lane roadway. Roadside ditches are to be replaced with concrete curb and gutter and storm sewer. Five signalized intersections are to be modernized. The resurfacing project is from the intersection of Harrison Avenue and 26th Street east to Alpine Road. The reconstruction project is from the intersection of Harrison Avenue and Alpine Road east until approximately 800' east of the Harrison Avenue and Mulford Road intersection.

PROJECT COMPLETION DATE

The Contractor shall perform his work in such a manner that all major project items such as earth excavation and base course, patching, pavement, storm sewer, multi-use path, sidewalk, traffic signal and light pole placement are completed, on or prior to November 30, 2007. The project shall have all the above noted major pay items completed except for final grading, landscaping and striping, before it is considered complete on the November date. If the Contractor fails to complete the major project items by the November completion date, the Contractor shall be charged liquidated damages by the Department as per Section 108 of the Standard Specifications for each day that major project items are not completed. If in the event additional traffic control and protection is required to open the road after the road is open to traffic, it shall be at the Contractor's expense.

The Contractor will be allowed 60 working days after the November 30, 2007 completion date to complete the remaining items.

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

This work shall conform to Section 606 of the Standard Specifications and shall be constructed in accordance with the details as shown herein. One inch (1") Ceramer expansion joint material, with caulking or equal, shall be installed at 100 foot intervals, at all radii, and 5 feet either side of inlets when not at radii. Each expansion joint shall be finished with an Engineer approved caulking material that fills the void between the Ceramer expansion joint material and the face of the curb.

Curb and Gutter used for this item shall conform to Highway Standard 606001, types B-6.06 and M-6.24.

Excavation to install this item to grade shall not be paid for separately, but shall be incidental.

Method of Measurement. Measurement for this work will be per foot.

Basis of Payment. This item will be paid for at the contract unit price per foot for COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT, of the type specified, which price shall include expansion joints, aggregate under the curb & gutter (2" minimum depth), necessary pavement removal, curb and gutter removal, and pavement replacement to the adjacent surface and gutter flag elevation.

Portland Cement Concrete shall be used to fill in the void area between the new curb and gutter and the existing pavement, unless otherwise directed by the Engineer. Expansion joints, aggregate under the curb & gutter (4" minimum depth), necessary pavement removal, curb and gutter removal, and pavement replacement to the adjacent surface and gutter flag elevation shall be required and shall be incidental to this item.

SAW CUTS

This work shall conform to Section 442 of the Standard Specifications and shall be for the sawing of patches full depth.

This work shall be paid for at the contract unit price per lineal foot of saw cuts.

BITUMINOUS SHOULDERS SUPERPAVE 6"

This work shall conform to Section 482 of the Standard Specifications and BDE Special Provisions 80011 and 80010 depending on the Superpave mixed used.

This work shall be paid for at the contract unit price per square yard (sy) of BITUMINOUS SHOULDERS SUPERPAVE of the thickness specified.

CONCRETE HEADWALL REMOVAL

This item shall be in accordance with Section 501 of the Standard Specification and is to cover the cost of the complete removal of the existing headwall noted on the plans. This item shall consist of excavation, removal and disposal of existing materials.

This work will be paid for at the contract unit price per each for CONCRETE HEADWALL REMOVAL, removed.

PIPE CULVERT REMOVAL

This item shall be in accordance with Section 601 of the Standard Specifications and is to cover the cost of pipe culvert removal in areas were no pipe culverts are to be placed. This item shall consist of excavation, removal and disposal of existing pipe culverts as shown on the plans.

Salvage of pipe will not be required. The contactor shall be responsible for location of any laterals, private or public, entering pipe culverts to be removed. If any such laterals are determined, by the engineer, to be "live" they shall be extended and connected to an existing pipe culvert or a proposed inlet or sewers as directed by the engineer and payment made in accordance with Article 104.03 of the Standard Specifications. Trench backfill shall be incidental to pipe culverts removal and shall be properly compacted pit run sand or equal. Plugging existing lines that are to remain shall be incidental to this item.

This work will be paid for at the contact unit price per lineal foot for PIPE CULVERT REMOVAL of the size specified, removed.

FIRE HYDRANT TO BE ADJUSTED

This item shall be in accordance with Section 564 of the Standard Specifications. This item is to cover all cost associated with adjusting fire hydrant and valve which serves the hydrant.

This work shall be paid for at the contact unit price each for FIRE HYDRANT TO BE A ADJUSTED.

FIRE HYDRANT TO BE RELOCATED

This item shall be in accordance with Section 564 of the Standard Specifications. The item FIRE HYDRANT TO BE RELOCATED is to cover all costs associated with relocating the fire hydrant and valve which serves the hydrant. All water main required to relocate a fire hydrant or fire hydrant assembly shall be incidental to this item and shall be new water main meeting the requirements of the City of Rockford.

This work shall be paid for at the contract unit price each for FIRE HYDRANT TO BE RELOCATED.

WATER MAIN 16"

This work shall be furnished and installed in accordance with the City of Rockford Water Division Specifications and the requirements of the Engineer. <u>Bacteriological sampling shall be done in accordance with the AWWA C651-99 regulations and EPA regulation section 652.203. The City of Rockford shall receive a copy of all bacteriological laboratory reports. All water mains shall be made from ductile iron or an approved equal material. All fittings (bends, tees, crosses, and plugs) required to complete this installation shall be as shown upon the plans or as directed by the Engineer.</u>

Method of Measurement. Measurement for this work will be per foot in place. All fitting required for water main that is 12" diameter in size and smaller will not be measured separately, but shall be included in the cost of the associated water mains.

Basis of Payment. This work will be paid for at the contract unit price per foot for WATER MAIN 16" of the class and type specified; of the diameters specified and of the particular kind of material when specified.

INLETS, SPECIAL

This item shall be constructed in accordance with Section 602 of the Standard Specification and the details shown in the plans.

This item shall include the cost of furnishing the frame, lid, reinforcement bars, floor, walls, top-of-slab, labor, and other necessary items to construct the inlets.

Basis of Payment. This work will be paid for at the contract unit price for INLETS, SPECIAL of the type specified.

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06

This item shall be in accordance with Section 606 of the Standard Specifications. The curb shall match the section of a Type B-6.12 curb and gutter except that the gutter will be only six inches wide.

This item shall be paid for at the contract unit price per lineal foot for COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.06.

CONCRETE MEDIAN, TYPE SB (SPECIAL)

This item shall be in accordance with Section 606 of the Standard Specifications and the detail shown on the plans. Note that the gutter section for this item is not uniform and varies from six (6) to twelve (12) inches.

This item shall be paid for at the contract unit price per square feet for CONCRETE MEDIAN, TYPE SB (SPECIAL).

TRAFFIC CONTROL COMPLETE

This work shall consist of furnishing, installing and maintaining all signs, signals, temporary pavement markings, other required traffic control markings, barricades, warning lights, and other devices which are to be used to regulate, warn or guide traffic during construction of this improvement. This work shall be done in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, Illinois Department of Transportation, adopted January 1, 2002, the Supplemental Specifications and Recurring Special Provisions adopted March 1, 2005 and the Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD), 2003 Edition.

Special attention is called to Articles 107.09, 107.14 and Section 701 of the Standard Specifications for Road and Bridge Construction, and Illinois Department of Transportation Standards 701602, 701606, 701701, 701801, 702001, BLR 21 and BLR 22. Note, cones will not be allowed as a traffic control device.

MAINTENANCE OF TRAFFIC

Maintenance of traffic shall be as per the "Staging Plan Harrison Avenue" included in the plans and as follows:

On Harrison Avenue between Ohio Parkway and Mulford Road two-way traffic shall be maintained at all times. A minimum of one lane, 12 feet in width, shall be maintained in each direction. Traffic shall be maintained on new or existing pavement only (see Standard 701602.

On the west end of the project west of Ohio Parkway when work is being done on the north side of Harrison Avenue merge eastbound traffic to one lane and cross westbound traffic to the westbound lanes in accordance with Standard 701606. Remove and replace combination curb and gutter and median surface and construct temporary pavement as necessary. When work is being done on the south side of Harrison Avenue, reverse the process.

On the east end of the project east of Mulford Road when work is being done on the north side of Harrison Avenue merge westbound traffic to one lane and cross over to eastbound lanes in accordance with Standard 701602. Westbound traffic shall be merged to single lane prior to Columbine Road. When work is being done on the south side of Harrison Avenue, reverse the process.

Access to side streets shall be as per the "Staging Plan Harrison Avenue" included in the plans and as follows:

Maintain access to all local residences along Harrison Avenue at all times. Use temporary granular surface as necessary.

Ohio Parkway north of Harrison Avenue to the end of the return may be closed during construction of the north side of Harrison Avenue. Access to residents is to be provided from the north. Signage at Ohio Parkway and Seward Avenue shall be in accordance with BLR Standard 22. R11-4 signage shall be posted on the type III barricades. At no time shall Ohio Parkway, Wisconsin Road and Colorado Avenue be closed together. Only one of these streets may be closed to traffic at any one time. Reverse process when work is being done on the south side of Harrison Avenue for the closure of Ohio Parkway south of Harrison Avenue. Provide 3-way or 4-way stop controlled intersection. Set signals to flashing red. Provide temporary stop signs with 2 red flags.

Wisconsin Road may be closed to all traffic. Access is to be provided from the north. Signage at Wisconsin Road and Seward Avenue shall be in accordance with BLR Standard 22. RII-4 signage shall be posted on the type III barricades.

City of Rockford Section 03-00520-00-WR Harrison Avenue

Colorado Avenue may be closed to all traffic. Access is to be provided from the north. Signage at Colorado Avenue and Seward Avenue shall be in accordance with BLR standard 22. RII-4 signage shall be posted on the type III barricades.

At Alpine road all north/south lanes shall remain open at all times. Temporary signals are to be provided for eastbound and westbound lanes to locate signal heads above active traffic lanes. See temporary signal plans.

Holmes Road north of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the north half of Harrison Avenue. Access to residents is to be provided from the north. Signage at the intersection of Holmes and Upland shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. The spacing of warning signs may be reduced to 200'. Provide 3-way or 4-way stop controlled intersection at Holmes. Provide post mounted RI-4 stop signs with 2 red flags. Set existing signals to flashing red. Maintain existing signals for as long as possible.

Upland Drive north of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the north half of Harrison Avenue. Access to residents is to be provided from the north. Signage at the intersection of Upland and Skokie shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. The spacing of warning signs may be reduced to 200'.

Eggleston Court north of Harrison Avenue to the end of the new return may be closed to all traffic during the construction of the north half of Harrison Avenue. Access shall be provided from Forest View Road. Signage at the intersection of Eggleston and Forest View shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. If work is ongoing at Forest View Road traffic on Eggleston Court shall remain open to traffic at all times.

One lane of traffic in each direction shall be maintained on Forest View Road both north and south of Harrison Avenue at all times. These lanes shall be a minimum 11 feet in width and shall be on new or existing pavement. Provide 4-way stop controlled intersection at Forest View Road. Provide post mounted RI-1 stop signs with 2 red flags. Set existing signals to flashing red. Maintain existing signals for as long as possible.

Welworth Avenue north of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the north half of Harrison Avenue. Access to residents is to be provided from the north. Signage at the intersection of Welworth and Dexter shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. The spacing of warning signs may be reduced to 200'.

One lane of traffic on Wentworth Avenue shall be maintained at all times as access from the north is limited. This lane shall be a minimum 10 feet in width.

Mariposa Drive north of Harrison Avenue to the end of the new return may only be closed to all traffic during construction of the north half of Harrison Avenue. Access to residents is to be provided from the north and from Eastrock Avenue to the east. Signage at the intersection of Mariposa and Dierks shall be as per BLR Standard 22-4. R11-4 signage shall be posted on the type III barricades.

One lane of traffic in each direction shall be maintained on Eastrock Avenue south of Harrison Avenue at all times. These lanes shall be a minimum 11 feet in width. Eastrock Avenue north of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the north half of Harrison Avenue. Access is to be provided from the intersection of Eastrock and Dierks. Signage at the intersection shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. Provide 3-way or 4-way stop controlled intersection at Eastrock Drive. Provide post mounted RI-1 stop signs with 2 red flags. Set existing signals to flashing red. Maintain existing signals for as long as possible.

Arnold Drive north of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the north half of Harrison Avenue. Access is to be provided from the intersection of Arnold and Dierks. Signage at the intersection shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. At no time shall Mariposa Drive, Eastrock Avenue and Arnold Drive be closed to all traffic together. Only one of these streets may be closed to all traffic at any given time.

One lane of traffic in each direction shall be maintained on Sandhutton Avenue south of Harrison Avenue at all times. These lanes shall be a minimum 11 feet in width. Sandhutton Avenue may be closed to traffic if no work is being done and all lanes are open at Stowmarket Avenue south of Harrison Avenue.

One lane of traffic in each direction shall be maintained on Stowmarket Avenue both north and south of Harrison Avenue at all times. These lanes shall be a minimum 11 feet in width. Provide 4-way stop controlled intersection at Stowmarket Avenue. Provide post mounted RI-1 stop signs with 2 red flags. Set existing signals to flashing red. Maintain existing signals for as long as possible.

Wendy Drive south of Harrison Avenue to the end of the new return may be closed to all traffic during construction of the south half of Harrison Avenue. Access is to be provided from the intersection of Wendy and Darlene. Signage at this intersection shall be as per BLR Standard 22. R11-4 signage shall be posted on the type III barricades. The spacing of warning signs may be reduced to 200'.

One lane of traffic in each direction shall be maintained on Mulford Road both north and south of Harrison Avenue at all times. These lanes shall be a minimum 12 feet in width and shall be composed of new and/or existing pavement. One left turn lane for both northbound and southbound traffic shall also be maintained at all times. These lanes shall be a minimum 11 feet in width and shall be composed of new and/or existing

pavement. On Harrison Avenue besides the two thru lanes, one left turn lane for both westbound and eastbound traffic shall be maintained at all times. These lanes also shall be a minimum 11 feet in width and shall be composed of new and/or existing pavement. At no time shall more then one quarter of the Harrison Avenue, Mulford Road intersection be under construction. Provide 4-way stop controlled intersection at Mulford Road. Provide post mounted RI-1 stop signs with 2 red flags. Set existing signals to flashing red. Maintain existing signals for as long as possible.

Access to entrances and driveways shall be as follows:

Only one entrance from Harrison Avenue to Hamilton Sundstrand may be closed to traffic at any given time.

Entrances to the Post Office from Harrison Avenue may only be closed when no work is being done at Eastrock Avenue and all lanes on Eastrock Avenue are open.

On all other commercial and business driveways access to the site must be maintained at all times. If the site has two or more access points one may be closed at any given time. If the site has only one access point to Harrison Avenue one lane a minimum 10 feet in width shall be maintained at all times.

Residential driveways may be closed for their replacement.

The contractor is to notify all property owners at least 24 hours prior to the commencement of any driveway construction activities.

<u>Traffic Signal Work</u>: No traffic signal equipment shall be installed until all of the traffic signal hardware is on the job site. The existing traffic signal system shall remain in operation during the modernization work. The work shall be scheduled so that a minimum of two signal indications for each phase remains in operation. No signal indication shall be absent for more than seven calendar days.

The Contractor will be allowed to shut down the existing signal system not to exceed 8 hours to replace the existing controller and cabinet. During the shutdown, the intersection will operate as a 4-way "Stop".

Temporary Pavement Marking: This work shall be done in accordance with Section 703 "Work Zone Pavement Markings".

All temporary pavement markings that will be operational during the winter months (December through March) shall be paint.

GENERAL INSTRUCTIONS

On the date that the Contractor begins work, he shall assume responsibility for the normal maintenance of all existing pavements, drives and temporary surface within the limits of the improvement. Normal maintenance shall include all repair work deemed necessary by the Engineer but shall not include snow removal operations. This responsibility shall end upon the completion and acceptance of all the pay items in this contract.

No work shall begin until all traffic control devices are in place and have been approved by the Engineer. Approval will be written.

The Contractor will be responsible to furnish proper location, relocation, installation, arrangement, maintenance and removal of all traffic control devices furnished and installed by him. Whenever operations indicate that a relocation of a proposed or existing traffic control device is advisable, as determined by the Engineer, the Contractor shall remove, relocate and reinstall the device in question. The Contractor will be required to furnish the necessary flaggers as specified in the Plans or required by the Engineer on a continuous basis whenever construction operations are in progress.

The contract will provide surveillance of all barricades, warning signs and lights which he has installed for 24 hours a day for every day during the duration of this contract. In the event of severe weather conditions, the contractor shall be required to furnish any additional personnel required to maintain all traffic control devices as may be required by the Engineer. Surveillance shall mean checking control devices periodically, but not less than once every 12 hours.

The Contractor shall provide the City of Rockford with the name, address and telephone number of two (2) persons who will be responsible for maintaining the traffic control devices and who will be available to the City on an immediate basis 24 hours a day. If, for any reason, one or both of the persons become unavailable, the Contractor shall furnish the same information for other individuals who will be available.

To ensure a prompt response to incidents involving the integrity of the work zone traffic control devices, said individuals must be able to respond within 15 minutes of any call by the Engineer. When the Engineer is notified or determines a deficiency exists, (s)he shall be the sole judge as to whether the deficiency is an immediate safety hazard. The Contractor shall dispatch sufficient resources within ONE hour of notification to make needed corrections of deficiencies that constitute an immediate safety hazard. Other deficiencies shall be corrected within 12 hours. If the Contractor fails to restore the required traffic control and protection within the time limits specified above, the Engineer will impose a daily monetary deduction for each 24-hour period (or portion thereof) the deficiency exists. This time period will begin with the time of notification to the Contractor and end with the Resident Engineer's acceptance of the corrections.

The presence of temporary traffic control drawings or standards in the project plans, whether a pay item or not, does not relieve the Contractor of his obligation to provide protection to the public in accordance with Article 107.14 of the Standard Specifications for Road and Bridge Construction. This article stipulates that the Contractor shall provide, to the satisfaction of the Engineer, all protection deemed necessary beyond that shown in the Plans or Special Provisions. The expense of this work to the Contractor shall be considered incidental to the contract.

When the speed limit is 40 M.P.H. or less, the sign spacing may be reduced to 200 feet centers.

Flashing lights shall be installed above the first two signs and above the closure barricades on the traveled lanes (two in each barricade).

The Contractor shall be responsible for locating, removing, storing, relocation and reerecting all traffic control signs. Signs shall be re-erected prior to any street reopening. Signs damaged by the contract shall be replaced at the contractor's cost. Worn and faded signs will be replaced by the City prior to re-erection by the Contractor. All traffic control devices must remain in place until specific authorization for removal is received from the Engineer.

Daily or periodic lane closures shall be erected <u>no earlier</u> than 9:00 A.M. and shall be removed <u>no later</u> than 3:30 P.M. regardless of the day of the week. In the event that a lane closure will remain for more than one calendar day, the Contractor shall notify the Engineer at least 6 hours in advance. Emergency lane closures shall be erected and removed at the explicit direction of the Engineer.

Arrowboards used shall be solar powered with engine generator back-up in case of power failure.

During resurfacing and grinding operations, flaggers and flagger signs at intersections shall be required when operations are within 30m (100 feet), if required by the Engineer.

The "WORKERS" (W21-1a(O)-48) signs shall be replaced with symbol ("Right or Left Lane Closed Ahead" (W4-2R or L(O)-48) signs.

"ROAD CONSTRUCTION AHEAD" signs shall be located on all side roads.

When the distance between successive patches is less than 700 feet, the entire operations may be considered as a work area for flagging and signing purposes. When the distance between successive patches exceeds 700 feet, additional warning signs, flaggers and taper shall be used. Under restricted sight distance conditions such additional devices and flaggers shall be required for distances less than 700 feet at the discretion of the Engineer.

Method and Measurements: Measurement for this work will be on a lump sum basis.

<u>Basis of Payment</u>: This work will be paid for at the contract lump sum price for <u>TRAFFIC CONTROL COMPLETE</u>, which price shall be payment in full for all labor, materials, temporary pavement, temporary striping, granular surface for access, transportation, handling and incidental work necessary to furnish, install, maintain and remove all traffic control devices as indicated on the Plans or in these Specifications and as directed by the Engineer. Temporary signal at Alpine Road will be paid for separately.

INSTALL EXISTING SIGN PANEL

This work shall conform to the applicable portions of Section 723 of the Standard Specifications. The two (2) signs shall be installed at East Rock Dr. at the locations shown on the plans and will be furnished by the City of Rockford and shall be transported by the Contractor.

This work will be paid for at the contract unit price per square foot for INSTALL EXISTING SIGN PANEL.

SERVICE INSTALLATION, TYPE B

This work shall conform to the applicable portions of Section 805 of the Standard Specifications. The service shall contain a 60 amp circuit breaker.

This work will be paid for at the contract unit price per each for SERVICE INSTALLATION, TYPE B.

FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL

This work shall conform to the applicable portions of Section 857 of the Standard Specifications. The equipment furnished shall be the latest EPAC, TS-1, M-50 model controller, fiber-optic ready manufactured by Eagle Signal. The assembly shall be Eagle MARC 360 System to be compatible with existing city equipment. The controller shall include manual control complete with push-button and a coiled cord. The cabinet shall include a separate 20-amp circuit breaker for the street lights. This item shall include all the work necessary to terminate the fiber optic interconnect cables necessary for signal coordination and to make the interconnect operational.

This work will be paid for at the contract unit price per each for FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL.

FULL-ACTUATED CONTROLLER IN EXISTING CABINET

This item shall comply with the applicable portions of Section 857 of the Standard Specifications. This work includes removing the existing controller (the existing controller shall remain the property of the City of Rockford traffic signal department) and installing the new controller including terminating all necessary fiber optic connections to make the interconnect and signal coordination operational. The equipment furnished shall be the latest EPAC, TS-1, M-50 model controller, fiber-optic ready as manufactured by Eagle Signal. The assembly shall be MARC 360 System to be compatible with existing City Equipment and shall include manual control complete with push-button and a coiled cord.

This work will be paid for at the contract unit price each for FULL-ACTUATED CONTROLLER IN EXISTING CABINET.

STEEL COMBINATION MAST ARM ASSEMBLY AND POLE

This work shall conform to the applicable portions of Section 877 of the Standard Specifications. A fifteen (15) foot truss-style street light arm mounted directly over the mast arm at a height of forty-five (45) feet shall be included. This arm shall accommodate both the luminaire and video detection camera. A 10-amp inline fuse and surge arrestor shall be installed in the mast arm base.

This work will be paid for at the contract unit price per each for STEEL COMBINATION MAST ARM ASSEMBLY AND POLE of the lengths specified.

CONCRETE FOUNDATION, TYPE E, 36 INCH DIAMETER

This item shall comply with the applicable portions of Section 878 of the Standard Specifications. The depth shall be as shown on the plans or as otherwise directed by the Engineer.

This work will be paid for at the contract unit price per foot for CONCRETE FOUNDATION, TYPE E, 36 INCH DIAMETER.

LIGHT DETECTOR & LIGHT DETECTOR AMPLIFIER

This item shall comply with the applicable portions of Section 887 of the Standard Specifications for Road and Bridge Construction. The equipment shall be as manufactured by Tomar Electronics brand and must be completely compatible with existing City of Rockford of Rockford equipment. Confirmation beacons shall be furnished and installed as part of this pay item. The light detector amplifier shall be the Tomar Opic-4 card and backed with the four channel capacity.

This work will be paid for at the contract unit price per each for LIGHT DETECTOR & LIGHT DETECTOR AMPLIFIER.

TEMPORARY TRAFFIC SIGNAL INSTALLATION

The above item shall comply with the applicable portions of section 890 of the Standard Specifications. Cable routing from the span wire pole to the nearest handhole can be above ground as long as adequate protection is placed around the cables. Adequate slack shall be provided to allow re-positioning of the signal heads to avoid obstructing the view of the mast arm mounted signals. The Contractor shall be responsible for disconnecting the appropriate mast arm signals depending on the traffic configuration on Harrison Ave. The City of Rockford will adjust the phasing of the Harrison Ave. signals as needed.

This work will be paid for at the contract unit price per lump sum for TEMPORARY TRAFFIC SIGNAL INSTALLATION.

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT

This work shall comply with the applicable portions of Section 895 of the Standard Specifications. The existing equipment to be removed shall include, but not be limited to what is listed on the plan sheets. Any items deemed salvageable by the City of Rockford shall be delivered by the Contractor to a site designated by the City of Rockford.

This work will be paid for at the contract unit price per each for REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT.

INLETS, TYPE 700

This work shall be performed in accordance with Section 602 of the Standard Specifications and the City of Rockford Engineering Department standard details shown on the plans.

A Neenah No. R-3246 (or approved equal) type frame and grate shall be used.

This work will be paid for at the contract unit price each for INLET TYPE 700.

BARE COPPER WIRE, 1/C NO. 8

This item shall comply with the applicable portions of Section 873 of the Standard Specifications. This cable shall be installed as a tracer wire along side all runs of fiber optic cable where a copper cable is not present.

This work will be paid for at the contract unit price per foot for BARE COPPER WIRE, 1/C NO. 8.

REMOVE EXISTING LIGHT POLE

The above item shall comply with the applicable portions of Section 895 of the Standard Specifications. The pole to be removed is in the south median of Forest View Rd. and is a direct bury pole. The cable shall be disconnected in the next base to the south and then abandoned in place. The pole, davit arms, and luminaries shall be removed and delivered to the City of Rockford to a location designated by the City.

This work will be paid for at the contract unit price per each for REMOVE EXISTING LIGHT POLE.

ELECTIC CABLE IN CONDUIT, 600B 1/C NO. 6 THHN/THWN

This item shall comply with the applicable portions of Section 817 of the Standard Specifications. This cable shall be installed as part of the roadway lighting installation.

This work will be paid for at the contract unit price per foot for ELECTRIC CABLE IN CONDUIT, 600 V 1/C NO. 6 THHN/THWN.

VIDEO VEHICLE DETECTION SYSTEM

This item shall include all material and labor necessary to furnish and install video detection systems at the locations shown.

The system to be installed is the Iteris Vantage System, latest model. It shall include four (4) cameras, the processor unit, connectors, software and all cabling necessary back to the controller. This system is necessary to provide compatibility with the Eagle controller to be installed on this project and existing detection equipment in the City of Rockford. All the equipment shall be installed according to manufacturer's recommendations. The video detection cameras shall be capable of being zoomed and focused from a connection in the controller cabinet. All equipment needed to provide this capability shall be included in this item.

The monitor to be furnished as part of this pay item shall be a Model VM 5094 as manufactured by Vicon Industries or an approved equal.

The monitor shall be a monochrome video monitor with a 9-in. picture tube. It shall have a resolution of 1000 TV lines (center). It shall provide looping video output with switchable 75 ohm termination located on the rear panel.

Front panel controls shall include power on/off, brightness, contrast, vertical hold, and horizontal hold. Input power shall be 120 VAC or 230 VAC, 50/60 Hz. Power

consumption shall be 19.5 W typical.

Dimensions shall not exceed: height, 9.4 in; width 8.6 in.; depth, 10.25 in. The weight shall not exceed 13.2 lb. The monitor shall comply with UL 2044 standards and with FCC limits for a Class A computing device in accordance with the specifications in Part 15 of FCC rules. Single and double rack mounting kits shall be available. The monitor shall be Vicon model VM 5094 or approved equal.

The monitors shall be installed so that they can also function as monitors for the Video Surveillance System to be installed at Forest View Dr. and Stowmarket Ave.

Two (2) spare cameras shall be furnished to the City of Rockford for the entire project.

Consultation and service shall be provided by Brown Traffic Products at no charge to the City of Rockford for a period of ninety (90) days following final acceptance of the traffic signals.

This work will be paid for at the contract unit price per each for VIDEO VEHICLE DETECTION SYSTEM.

VIDEO VEHICLE DETECTOR

This item shall include all material and labor necessary to furnish and install a video vehicle detector at the locations shown on the plans. The camera and cabling shall be connected to an existing Iteris Vantage System and shall be fully compatible with the video detection controller already in place. The video detection cameras shall be capable of being zoomed and focused from a connection in the controller cabinet. All necessary cabling including connection to the existing system shall be included in this item.

This work will be paid for at the contract unit price per each for VIDEO VEHICLE DETECTOR.

STORM SEWER (WATER MAIN REQUIREMENTS)

Effective June 12, 1997

Description: This work shall consist of furnishing and installing water main quality pipe at the locations shown on the plans.

Materials:

- a) Ductile iron water main Class 52
 Joints for Ductile Iron pipe shall be:
 - Mechanical Joints AWWA C111 and C600

2. Push-On-Joints – AWWA C111 and C600

b) Polyvinyl Chloride (PVC) Class 12454B (PVC 1120) or Class 12454C (PVC 1220).
Schedule 40 is required for 8" diameter and schedule 80 for larger sizes.

CONSTRUCTION REQUIREMENTS

The storm sewer water main shall be installed according to the applicable portions of Section 550 and 561 of the Standard Specifications and the Standard Specifications for Water and Sewer Main Construction. In case of conflict between the Standard Specifications, the Standard Specifications for Water and Sewer Main Construction in Illinois shall take precedence and shall govern.

No testing or disinfections of the newly laid storm sewer water main will be required. A watertight connection is required between storm sewer water main and the storm sewer.

Method of Measurement: Storm sewer water main of the various diameters will be measured for payment in feet, measured in place.

Basis of Payment: This work will be paid for at the contract unit price per foot for STORM SEWERS (WATER MAIN REQUIREMENTS), of the diameter specified.

VIDEO SURVEILLANCE SYSTEM, COMPLETE

Camera Enclosure, Outdoor

- A. The camera enclosure shall be a totally static (no external movement) 180 mm dome, manufactured using high-resolution video imaging. The dome shall be constructed of UV stabilized optically graded acrylic substrate, or equal.
- B. The outdoor dome shall consist of three (3) half spheres.
 - 1. The upper portion of the dome shall be comprised of two half spheres.
 - a. The inner half sphere shall have air vents located near the top to allow the dome to release hot air without allowing driving rain to infiltrate the dome housing. A thermostatically controlled 100W heater assembly and blower shall be included to keep the dome free of frost, ice and snow
 - b. The outer half sphere shall cover the inner half sphere with approximately 25 mm of space separating the two, providing dead air insulating properties. The outer half sphere shall be highly reflective and opaque to minimize the effects of radiated heat created by direct rays of the sun.

- c. The outer half sphere shall protrude below the equator to provide additional infiltration protection of wind driven rain.
- 2. The lower half sphere shall be clear to facilitate the highest performance video image possible in low light level conditions.
- C. The camera and other equipment within the dome enclosure shall be easily accessible by rotating the bottom portion of the dome, which shall drop clear to reveal the internal equipment. The bottom dome shall be connected to the upper dome with a safety wire.
- D. The dome enclosure shall contain a quick release mounting mechanism for the ease of installation, removal and maintenance of the pan and tilt, camera and zoom lens assembly.
- E. The dome enclosure shall have the capability of being installed using a heavy duty, "A" Frame, parapet mount. Mount shall attach to a luminaries pole and to the top of the dome using a two point connection to the pole and a single mount to the dome. All mounting hardware for the arm and support shall be provided. Pole plates shall be provided for each of the two mount positions. The supplier may install a special enclosure on the mount to install a 120 VAC to 24 VAC transformer where the power to the camera is a single three wire, 18 AWG stranded, power feed circuit. Power to the camera shall include power for the camera, camera controls and the internal 100watt heater, thermostatically controlled. The connector between the dome enclosure and the junction box mounted to the pole shall consist of the camera video as one conductor and a single multiple conductor in a single sheath for all power, heater, P/T/Z, etc. 19-conductor cable. This connector shall be installed as a single special purpose conductor link. The cable shall be supplied by the camera manufacturer to the length specified by the Contractor with a factory-installed connector installed at the camera termination. This cable shall not exceed 100m without factory approval. The enclosure shall include all necessary facilities for mounting, communication, control and powering of the camera system.

CCTV Solid-State CCD Color Camera

- A. The camera shall provide a minimum of 380 horizontal lines of resolution.
- B. The video sensor shall be a 13 mm format CCD sensor with 510 horizontal x 492 vertical picture elements. The Contractor may substitute a 8 mm format of equal performance characteristics. The camera shall be rated for a minimum 48 zoom capability utilizing a combination of mechanical and electronic techniques. The camera, lens and electronic design shall provide quality video at a range of 2.5 to 3.0Km.
- c. The camera shall have auto white balance through the lens.

- D. Signal noise ratio shall be 40db or greater (AGC off).
- E. Minimum illumination shall be .05 lux, with a f:2.4 lens (10-300 mm lens, minimum).
- F. The camera shall accept standard C-mount 1-inch x 32 threads per inch lenses.
- G. The camera shall be powered by 24VAC 60Hz with line locked operation.
- H. The camera shall be mounted together with the zoom lens and integrated into the pan and tilt device, along with the control receiver forming a totally integrated, easily removable assembly.
- Video output from the camera unit to the video driver shall be through a coaxial connector. The video driver to the main receiver shall be a fiber optic video line driver providing full video image NTSC, 30 frames per second, using a one single mode fiber.

Zoom Lens

- A. The zoom lens shall be a 10-300 mm lens, minimum, to provide a one and one half-mile range.
- B. The zoom lens shall have an F-stop of 1.6 or better, consistent with zoom lens requirement.
- c. The zoom lens shall have auto iris controlled by the camera. A manual iris override capability shall be available and be easily actuated by the system operator at the remote control location.
- D. The zoom lens shall be C-mount type, 1-inch by 32 threads per inch, or pre-approved design.
- E. The zoom lens shall provide feedback control information to the smart receiver/driver to verify both zoom lens and focus position.
- F. The zoom lens motors shall be protected from overload conditions by means of electronic current limiting.

Pan, Tilt Tracking System

- A. The pan, tilt device shall be capable of continuous, 360° rotation.
- B. The pan speed shall be operator and/or pre-shot controlled at velocity from .5'/second to 125'/second.

- c. The tilt speed shall be operator and/or pre-shot controlled at any velocity from 5'/second to 60'/second.
- D. The tilt travel shall be operator and/or pre-shot controlled from 0° to 90° downward.
- E. Up to 100 pre-shot positions per camera shall be reached quickly by means of the high-speed pan/tilt. Each pre-shot shall be defined by a pan angle, tilt angle, zoom angle, and focus setting.
- F. An <u>on-board</u> intelligent receiver/driver shall direct the pan and tilt to its preprogrammed destination via the shortest possible route.
- G. Up to 10 pre-programmed auto scan (Vector) files with up to 64 linked pre-shots per file shall be available per camera location.
- H. Pre-defined per-shot and/or Vector scan positions shall be simultaneously activated in up to 250 camera locations upon a single (one switch actuation) operator command, alarm input, or time initiated event.
- Up to sixteen separate zones (sectors) per camera location shall be programmed and "on-screen" identified with a 16 character alpha-numeric display while in the manual operation mode.
- J. The system shall provide provisions for backing up memory for storing and maintaining all program data and time/date information during temporary power outages. The use of EEPROM or Super-Cap technology shall be used for this function.
- K. The pan and tilt device (which includes camera/lens package and smart digital receiver driver) shall be easily and quickly removable via a quick disconnect mounting assembly and a single electrical connector to facilitate ease of system installation and maintenance procedures.

A joy-stick controller shall be installed to allow viewing and controlling the video monitor output to enable the camera and video to be seen and controlled from the controller cabinet. The joy-stick controller shall be an RVS3000 model as manufactured by Treehaven Technologies, Inc. or an approved equal. The monitor, a VM5094 as manufactured by Vicon Industries or approved equal was installed as part of the Video Vehicle Detection System pay item. This monitor shall be made capable of separately viewing either the video detection video output or the video surveillance video output.

The above work, including all cabling and connection back to the controller, will be paid for at the contract unit price each for VIDEO SURVEILLANCE SYSTEM COMPLETE.

EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C

This item shall comply with the applicable portions of Section 873 of the Standard Specifications. This cable shall be connected to the Emergency Vehicle Priority System Light Detector and shall include all work and materials to install and connect the cable as recommended by the manufacturer.

The above work shall be paid for at the contract unit price per foot for EMERGENCY VEHICLE PRIORITY SYSTEM, LINE SENSOR CABLE, NO. 20 3/C.

STORM SEWER WATER MAIN

This work shall conform to section 550 of the Standard Specifications and in accordance with the requirements of the Engineer.

Storm Sewer Water Main shall be Ductile Iron water main Class 52 pipe. Joints for ductile iron water main pipe shall conform to AWWA C111 and C600.

This work shall include sewer pipe, pipe bedding, making connections to existing structures, patching existing structures at new connections, stoppers and plugs, and any other incidental costs not specifically included for payment under other items.

All pipe and joints shall be tested by an approved testing laboratory in accordance with the most recent cited standard methods of AASHTO or ASTM at the Contractor's expense. Two (2) copies of each test certificate shall be promptly furnished to the Engineer.

Where unsuitable soil is encountered, pipe bedding of 4" well graded durable gravel, crushed stone, or slag will be required. Trench backfill to the subgrade elevation above the top of the pipe will be required on pipe under roadway areas.

Method of Measurement. Measurement for this work will be made per foot of the diameter specified.

Basis of Payment. This work will be paid for at the contract unit price per foot for STORM SEWERS WATER MAIN, of the diameter specified.

ELECTRIC CABLE IN CONDUIT, GROUNDING NO. 6 1/C

This item shall comply with the applicable portions of Section 817 of the Standard Specifications and Highway Standard 873001.

This work will be paid for at the contact unit price per foot for ELECTRIC CABLE IN CONDUIT, GROUNDING NO. 6 1/C.

DOUBLE INLETS, TYPE 700

This work shall be performed in accordance with Section 602 of the Standard Specifications and the City of Rockford Engineering Department standard details shown on the plans.

A Neenah No. R-3246 (or approved equal) type frame and grate shall be used.

This work will be paid for at the contract unit price each for DOUBLE INLETS, TYPE 700.

FIBER OPTIC CABLE IN CONDUIT, 48 FIBER, SINGLE MODE AND 24 FIBER MULTIMODE

This work shall consist of furnishing and installing a fiber optic cable of the type, size and number of fibers specified and shall meet the applicable requirements of Section 871 of the Standard Specifications.

General Requirements

Materials and Equipment

Materials and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture of the products. The fiber optic cable shall be OFS BrightWave or Corning conforming to the following specifications. The fiber optic shall be manufactured utilizing Corning glass fiber conforming to the following specifications. All materials and equipment furnished shall be completely free from defects and poor workmanship. All fibers shall be glass and be manufactured by Corning or pre-approved equal. The cable shall be rated for gigabyte data bandwidth. All fiber shall be loose tube construction for both indoor and outdoor installation. Indoor cabling shall use plenum rated conduit to within less than 50 foot of point of termination eliminating the requirement to convert to indoor cable.

Contractor Qualifications

Trained and experienced personnel shall supervise the fiber optic cable installation. Qualified technicians shall make the cable terminations and splices. The Contractor upon request of the Engineer shall provide documentation of qualifications and experience for fiber optic equipment installations. The Engineer shall determine if the Contractor is qualified to perform this work. The

Contractor shall have attended a certified fiber optic training class mandated by these specifications prior to starting work.

Codes Requirements

The fiber optic cable installation shall be in accordance with or exceed all minimal requirements of State codes, National codes, and manufacturer codes as applicable.

Miscellaneous Equipment

The Contractor shall furnish and install all necessary miscellaneous connectors and equipment to make a complete and operating installation in accordance with the plans, standard sheets, standard specifications, special provisions, and accepted good practice of the industry.

General Considerations

The cable shall meet all requirements stated within this specification. The cable shall be new, unused, and of current design and manufacture.

Fiber Characteristics

All fibers in the cable must be usable fibers and meet required specifications.

Multi-mode Fiber

Core diameter: 62.5 +3.0um Cladding diameter: 125.0 +2.0um Core-to-cladding offset: <3.0um Coating diameter 250 +15um

Graded Index

Attenuation uniformity: No point discontinuity shall be greater than 0.25 dB, except terminations or patch cords, at either 850nm or 1300nm. The coating shall be a layered UV cured acrylate applied by the fiber manufacturer. The coating shall be mechanically or chemically removable without damaging the fiber.

Factory cable rating shall be 3.5 dB/KM at 850 nM and 1.0 dB/KM at 1300 nM, or less. Installed tolerance shall be less than 3.85 dB/KM at 850 nM and less than 1.1 dB/KM at 1300 nM, testing tolerance. Multimode fiber shall be rated for serial gigabit Ethernet distances of 300 meters @ 850nM and 550 meters @ 1300 nM.

Single-Mode Fiber

Typical core diameter: 8.3um

Cladding diameter: 125 +1.0um by fiber end measurement

Core-to-cladding offset: <1.0um

City of Rockford Section 03-00520-00-WR Harrison Avenue

Coating diameter: 250 +15um

Attenuation uniformity: No point discontinuity shall be greater than 0.1 dB, except terminations or patch cords, at either 1310nm or 1550nm. The coating shall be a layered UV cured acrylate applied by the fiber manufacturer. The coating shall be mechanically or chemically removable without damaging the fiber.

Factory cable rating shall be 0.40 dB/KM at 1310 nM and 0.30 dB/KM at 1550 nM. Installed tolerance shall be less than 0.44 dB/KM at 1310 nM and less than 0.33 dB/KM at 1550 nM, testing tolerance. Single mode fibers shall be rated for serial one gigabit Ethernet distances of 5000 meters @ 1310 nM and serial ten gigabit Ethernet distances of 10,000 meters @ 13xx nM and 40,000 meters @ 1550 nM.

Fiber Specification Parameters

All fibers in the cable shall meet the requirements of this specification. The testing tolerance attenuation specification shall be a maximum attenuation for each fiber over the entire operating temperature range of the cable when installed.

The change in attenuation at extreme operational temperatures for single-mode fibers shall not be greater than 0.20 dB/km at 1550 nm, with 80 percent of the measured values no greater than 0.10 dB/km at 1550 nm.

Optical fibers shall be placed inside a loose buffer tube, minimum six (6) fibers per tube, normally twelve (12) fibers per tube. Actual number of fibers per tube shall be twelve fibers per tube unless specified differently on the Plans.

Multimode only – each buffer tube shall contain 12 or 6 fibers. Single-mode only – each buffer tube shall contain 12 or 6 fibers.

The buffer tubes will meet EIA/TIA-598, "Color coding of fiber optic cables."

All fiber cables shall be Gigabyte rated, i.e. multimode shall be 200/500 Meter for 850 and 1300 nM respectively and 5000 Meter for 1310 and 1550 nM.

<u>Single-mode fibers shall be placed in the first buffer tubes</u>. Multimode fibers shall be in the remaining buffer tubes. Fiber count, tubes of fiber, shall be as specified on the plans.

Fillers shall be included in the cable core to lend symmetry to the cable crosssection where needed. The central anti-buckling member shall consist of a glass reinforced plastic rod. The purpose of the central member is to prevent buckling of the cable.

The cable shall use a completely dry cable design without the use of gels and filling compounds. Dry water blocking material shall be used around the buffer tubes as well as internal to the tubes. Water blocking gels shall not be acceptable on this project.

Buffer tubes shall be stranded around a central member. Acceptable techniques include the use of the reverse oscillation, or "SZ", stranding process.

All dielectric cables (with no armoring) shall be sheathed with medium density polyethylene. The minimum nominal jacket thickness shall be 1.4 mm. Jacketing material shall be applied directly over the tensile strength members and flooding compound. Cable jacketing shall utilize the newer designs to provide maximum flexibility without loss or appreciable dB attenuation. Cable diameter shall not exceed 0.50 inch.

The jacket or sheath shall be marked with the manufacturer's name, the words "optical cable", the year of manufacture, number of fibers, type of fiber (SM or MM) and sequential feet or meter marks. The markings shall be repeated every one-meter or three feet. The actual length of the cable shall be within –0/+1% of the length marking. The marking shall be in a contrasting color to the cable jacket. The height of the marking shall be approximately 2.5 mm. A copy of the manufacturer fiber definition and shipping sheet identifying all tests, results and fiber indexes shall be provided to the Engineer on delivery of cable to the City of Rockford or shall be included with a contractor's listing of place(s) of installation when installed by a Contractor.

The maximum pulling tension shall be 600 pounds (2700 N) during installation.

Where ever possible, six (6) buffer tubes with twelve (12) fibers each, or subsets specified, shall be provided and designated as follows:

Buffer Tube/Fiber	Tube/Fiber Color
#1, 1 st tube or fiber	blue
#2, 2 nd tube or fiber	orange
#3, 3 rd tube or fiber	green
#4, 4 th tube or fiber	brown
#5, 5 th tube or fiber	slate
#6, 6 th tube or fiber	white
#7, 7 th tube or fiber	red
#8, 8 th tube or fiber	black

#9, 9 th tube or fiber	yellow
#10, 10 th tube or fiber	violet
#11, 11 th tube or fiber	rose
#12, 12 th tube or fiber	aqua

Quality Assurance Provisions

All optical fibers shall be proof tested by the fiber manufacturer at a minimum load of 100 kpsi.

All optical fibers shall be 100% attenuation tested at the manufacturer. The attenuation of each fiber shall be provided with each cable reel. The measured attenuation shall be for both 850 and 1300 frequency for multimode and 1310 or 1550 frequency for single mode. This documentation shall be provided with each spool. The Contractor shall designate on the Plans and on this (See 28.2.11) documentation the location where each spool has been installed and provide this data to the Engineer.

Cable Installed in Ducts and Conduits

A suitable cable feeder guide shall be used between the cable reel and the face of the duct and conduit to protect the cable and guide it into the duct off the reel. It shall be carefully inspected for jacket defects. If defects are noticed, the pulling operation shall be stopped immediately and the Engineer notified. Precautions shall be taken during installation to prevent the cable from being "kinked" or "crushed". A pulling eye shall be attached to the cable and used to pull the cable through the duct and conduit system. A pulling swivel shall be used to eliminate twisting of the cable. As the cable is played off the reel into the cable feeder guide, it shall be sufficiently lubricated with a type of lubricant recommended by the cable manufacturer. Dynamometers or breakaway pulling swing shall be used to ensure that the pulling line tension does not exceed the installation tension value specified by the cable manufacturer. The mechanical stress placed on a cable during installation shall not be such that the cable is twisted or stretched. The pulling of cable shall be hand assisted at each controller cabinet. The cable shall not be crushed kinked or forced around a sharp corner. If a lubricant is used it shall be of water based type and approved by the cable manufacturer

Storage of minimum slack cable in controller cabinets and additional slack at handholes shall be coiled. The slack coils shall be bound at a minimum of 3 points around the coil perimeter and supported in their static storage positions. The binding material and installation shall not bind or kink the cable. Storage of additional slack cable adjacent to conduit risers and support poles shall be as visibly marked/tagged as "CAUTION – FIBER OPTIC CABLE". Maximum length of cable pulling tensions shall not exceed the cable manufacturer's

recommendations. All fiber cables shall be marked with a metallic, or preapproved identifier in the handhole adjacent to the traffic signal cabinet or controller cabinet and on the cable in the traffic signal cabinet or controller cabinet at the point of termination. The identifier, both in the cabinet and in the handhole, shall indicate the direction the cable is going, cable contents [SM or SM/MM], and the abbreviated location for the other end destination. Fiber cabling between traffic controllers and adjacent controller locations shall be outdoor rated, loose tube fiber, when not linked by a direct, continuous conduit installation.

Minimum Bend Radius

For static storage, the cable shall not be bent at any location to less than ten times the diameter of the cable outside diameter or as recommended by the manufacturer. During installation, the cable shall not be bent at any location to less than twenty times the diameter of the cable outside diameter or as recommended by the manufacturer.

After the Fiber Optic Cable Installation

Each section of the cable shall be tested for continuity and attenuation as a minimum. If the attenuation is found not to be within the acceptable nominal values, the Contractor shall use an optical time domain reflectometer (OTDR) to locate points of localized loss caused by bends or kinks. If this is not successful the Contractor shall replace the damaged section of cable with no additional payment. Splices will not be allowed to repair the damaged section. After all fiber cable is installed between traffic controller cabinets and fiber links between fiber distribution points (FDP) complete links, all fibers, whether terminated or nonterminated, shall be tested with an OTDR. All fibers terminated shall be tested with a power meter. The Contractor may jumper termination points at controller cabinets to minimize the number of tests and run a single OTDR test between several controller cabinets, subject to the range of the OTDR. Links between FDP's shall be tested separately. Each OTDR trace, for documented test result submittal, shall be displayed individually and not be combined with other fiber traces as overlays. Multimode fiber shall be tested using 1300 nm and single mode fiber shall be tested at 1310 nM. The results of the OTDR test shall be provided on an electronic media (disk) and paper printout. The OTDR wave, pictorial diagram of dB loss over the length of fiber tested, shall be provided along with the measured data values. The printout shall contain the manufacturer's fiber optic Index of Refraction to the third decimal point for the fiber provided. The Contractor shall provide the Engineer with a written report showing all the values measured compared to the calculated values for length and coupler/connector losses at the completion of these tests. Outdoor patch cords between FDP and controller units less than 151 feet do not need be OTDR tested.

Documentation provided to the Engineer shall include a written indication of every splice, termination, patch cord, etc. for cable being measured. Power meter measurement recordings shall indicate the exact measured distance [OTDR or field measurement with cross reference for oscillation multiplier] on the sheet showing the power meter readings. Any deviations between fiber readings in the same tube shall be notated for OTDR graphs as well as deviations greater than 5% on power meter readings. Rated values for acceptable installation shall be based on the following parameters:

Patch cords/Pigtails

.60 MM & .15 SM dB each

Unicam Terminations

1.0 dB set of 2 [In and Out]

Splices

0.08 each

1 KM = 0.3077 KF where KF is 1000 feet

Data documentation shall include for each test between cabinets or between FDP sites, the length of fiber as measured by OTDR, frequency used in test on OTDR by each fiber type, distance to each splice, termination or patch cord jumper, dB loss rating by manufacture from spool documentation, index of refraction by type of fiber in section, and the dB loss of each section as measured in the final test for each fiber. A special test shall be made on all continuous spliced fiber from start to end that includes the total dB loss measured and the OTDR plot on electronic disk. Splice points shall be identified on the trace.

Cable Termination

Terminations shall be made using the method recommended by the connector All fibers shall utilize a fan-out kit of the size and type manufacturer. recommended by the manufacturer and of the number of fibers provided in each fiber tube. All fibers terminated shall utilize a ceramic ferrule (outdoor connections), ST, mechanical termination equal to Siecor UniCam connectors, or be a wide temperature (-40 to +170 degrees Fahrenheit) epoxy. Heat cured or epoxy type connections meeting the full temperature ratings are acceptable for this Project, including factory manufactured pigtails. The Contractor shall be required to provide proof of purchase of sufficient quantities of ceramic terminations for outdoor terminations to verify ceramic connector usage or temperature ratings on epoxy or heat cured processes prior to terminating any fibers. The Contractor may terminate fibers by splicing factory pigtails to the fiber ends and then connecting the pigtail to the fiber coupler in the fiber trav. When splicing pigtails to terminate, all splices shall be provided with the metal reinforced shrink tube protector. The contractor may terminate fibers by the use of UniCam mechanical termination connectors. All termination ST couplers shall be rated for dual fiber application, MM and SM.

Breakout Kits

The breakout kits or termination boxes used to terminate each fiber cable in the cabinet shall provide for the separation and protection of the individual fibers with the buffer tubing and jacketing materials. The termination housing shall be installed within a wall or shelf mountable interconnect housing which shall provide for storing fibers, ample room for feed through cable, strain relief for multiple cables within unit, and accommodate ST compatible connectors. All fiber pigtails shall be terminated through ST connectors on the wall or shelf mounted interconnect panel. All terminations shall be ST type, ceramic core (outdoor connections), and plug into the provided controller unit internal fiber optic modem. Acceptable enclosures for combination termination/splice points shall be MIC-024 or WDC-024 enclosures or pre-approved equal. Splices to pigtail fiber, where used, shall utilize fan out kit protection to the fiber, heat shrink tubing with metal bar reinforcement and 900 micron rated piatail insulation. Splices to factory pigtails shall use pigtails that are rated for a minimum temperature range of zero degrees to +150 degrees Fahrenheit. In the absence of pigtails meeting this temperature rating, fibers shall utilize loose tube fiber in fanout kit tubes and UniCam mechanical ST connectors. These splices, fiber cable to pigtails, may be external to splice trays mounted internally to the enclosure, when shown on the wiring diagrams. All other splices, not specified to be installed external to the fiber splice tray, shall be installed in splice trays and be supported with heat shrink tubing. Acceptable splice trays include MIC-024-048 or 067 series or pre-approved equal.

Connectors

Connectors shall be mechanical ST (ceramic ferrule-outdoor connections) compatible, field installable, and self-aligning and centering or factory fabricated pigtails. Connectors to the special devices used for Ethernet network connections shall utilize a factory converter cable of SC to ST or manufacturer specified converter patch cord. Fiber optic equipment, used for terminating fibers, shall be rated for the type of connectors used. Connectors shall be Siecor CamLite, UniCam, or NEMA temperature rated epoxy type, or Engineer approved equal.

Splices

The fiber cable shall be installed in continuous runs between cabinets. No splices shall be allowed, unless shown on the plans or for testing. Only mechanical splices, Siecor CamLite or approved equal will be allowed, when specified, such as testing of non-terminated fibers. Splices, where specified, shall be by fusion splice and shall be installed using an automatic fusion splicer. Splices between two fibers leaving the cabinet shall be supported in splice trays installed in splice enclosures. All splices shall be protected by heat shrink tubing designed for fiber optic splicing applications. Fibers being terminated in two separate termination or splice enclosures shall be supported between enclosures

by the use of buffer tubing or approved equal support material or shall be pigtail patch cords. Termination / splice enclosures shall be separated by less than 12 inches unless a conduit is installed between enclosures. All splices shall be performed by an automated splicer device that verifies the final splice termination quality. All splices shall be nominally .03 to .05 dB loss but shall be less than a 0.08 dB loss.

Light Source

An LED light source with a wavelength that is the system wavelength, 850 and 1300 nm for multimode and 1310 and 1550 nm for single mode, shall be used. The LED shall be stable within 0.1 dB in intensity over a time period sufficiently long to perform the measurement. The output of the LED shall overfill the input end of the launch fiber/cable in both numerical apertures (NA) and core diameter. The accuracy of the combined light source and power meter shall be less than .05 dB and be temperature compensated stabilized to 0.01 dB over the operating range of the meter(s).

The Contractor shall provide one each Light Source and Power Meter and/or one each 650 nM visible light source, Model VF13 or approved equal, to the Fiber Optic Coordinator or City of Rockford Technician complete with all attachments for measuring individual fibers of multimode at both 850 and 1300 nanometers and single mode at both 1310 and 1550 nanometers for spot testing/inspecting of installed and terminated fibers. This test kit shall include one each 200X power zoom scope for observing fiber ends for smoothness and fractures. AC power adapters shall be provided with all light and power meters as well as battery operation. This test kit shall remain the property of the City of Rockford. This test kit shall be made available from the beginning to completion of the project and be on-site at all times. This test kit shall be considered incidental to the cost of installing the fiber optic cable and no additional compensation shall be provided.

Power Meter

The detector in the power meter shall have an effective numerical aperture and active region that is larger than the receive reference cable and/or the fiber under test. The power meter shall have a minimum range from +3 DBMS to -40 DBMS. The power meter shall have an accuracy of +/-0.5 dB through the operating temperature and minimum resolution of 0.1 dB.

Launch Reference Attenuator

The launch attenuator, two each for single and multimode fiber testing, shall be utilized for all OTDR tests such that one launch cable shall be at the beginning of the fiber being tested and the second launch cable shall be on the end of the fiber being tested past the final connector. Only one launch cable shall be required when testing non-terminated fiber. The launch attenuator(s) shall be of

the same fiber core size and type as the fiber under test. The attenuator shall emulate 300 hundred foot fiber length, minimum, for multimode and 900 feet length, minimum, for single mode fiber or as specified by the OTDR manufacturer for stabilization of the pulse generation. Launch cables shall be of identical length for incoming and outgoing light during tests. ST connectors shall be utilized with each attenuator to connect the device to the test device, OTDR. One launce cable shall be installed on the start of the fiber being tested and one launch cable shall be installed on the end of each terminated to view the dB loss of the final connector.

The OTDR shall have the Threshold Loss set at a value to show each splice or termination junction of a single fiber in each tube with out showing the extraneous noise caused by handhole coils or turns into the cabinets. This level is normally a value [Threshold Loss] between 0.3 and 0.8 on the OTDR. This trace shall be provided for one fiber in each tube tested and each "event" shall be marked as to splice, jumper or patch cord. The Threshold Loss shall then be set to a value of 0.25 for multimode fiber tests and to a value of 0.10 for single mode fiber tests. The test of each fiber installed shall be conducted and any recorded events above this threshold shall be identified, such as jumper or patch cord. Events that are in excess the provided values shall be corrected prior to documentation submittal, such as terminations in excess of the rated value or bends in the fiber at the point of a splice entering of leaving the splice tray (See Testing). For measured values recorded in excess of the above (0.25 MM and 0.10 SM) listed values, refer to the paragraph 12.2 specification as hereinbefore defined. The Engineer reserves the right to spot test fiber terminations, splices, or re-testing of all fibers in a section to insure proper quality assurance both during and after installation and testing. Deviations from Engineer testing and report documentation shall be reviewed and the Contractor shall be able to retest any or all challenged measurements to verify a valid test. Inconsistent test results, in the sole opinion of the Engineer, shall be cause for the Contractor to retest the entire fiber installation.

Testing

General

The Contractor shall provide all personnel, equipment, instrumentation and supplies necessary to perform all testing. All testing shall be performed in an accepted manner and in accordance with the testing equipment manufacturer's recommendations. All data shall be recorded and submitted to the Traffic Engineer as hereinbefore specified. The Contractor shall provide one copy of operating software to read and view all OTDR traces.

Attenuation

The end-to-end attenuation shall be measured for each fiber for each link after installation and termination. A patch cord jumper cable shall be connected to both the light source and the receive cable to the power meter by The two reference cables shall then be the use of a connector (barrel). connected via a termination coupler and the power meter "zeroed" to eliminate the line loss. This process results in a reading of the actual line loss (dB) of the input connector, fiber cable, exiting connector and any other splices or jumpers installed in the measured test link. The calculated "loss" shall not include the input or departing cables in the loss calculation. The calculated fiber loss measured shall list the number of terminations, including the input and departing connectors, the number of splices and the number of patch cords used to jumper the link(s) into the measured final link. The measured values for each terminated fiber in each tube shall include the Tube number, fiber number, number of feet in the link, the number of splices, the number of patch cords and the number of connectors, if any. The length of optical cable shall be as measured by the OTDR rather than the fiber cable jacket as the fiber is a reverse oscillation process resulting in a greater optical distance than the fiber cable jacket. The value for both the OTDR length and the cable jacket shall be provided in the recorded documentation for each link distance. All distances shall be recorded in feet rather than meters for both recorded lengths.

Fibers that are not continuous from beginning of the link to the end of the link shall be noted in the documentation; otherwise, all fibers in a single tube may be listed with a single data entry for all required data listed above for all fibers in the tube. The fiber documentation for each fiber shall identify the fiber being tested by either fiber number or fiber coating color and be recorded by complete tube, Tube 1 through Tube 6, fiber 1 through fiber 12. The direction of the test shall be recorded for information purposes only to resolve discrepancies in replicating the test during inspections of the final installation. The power meter reading recordings shall log total dB loss over the length of the fiber measured, equivalent to a dB loss budget.

The output power levels at the network hardware transmitters and receivers shall be measured and recorded for system documentation. The power meter shall be connected to the transmitter side of the equipment with a system jumper. The transmit power level shall then be read and recorded

Each tube of a cable shall be in the same file divider where the tube cover OTDR page shows the overview of all splices, patch cords, terminations from start to end. The second section shall include all Power Meter readings and the mandated documentation to show the calculated line loss (losses). The third section shall contain all OTDR traces, one trace per screen. The fourth section

shall include the spool sheet for the fiber installed on the test section. An "explanation" sheet may be included where required to clarify an unusual reading that is valid but difficult to be explained through traditional data presentation, such as a video feed fiber that is attached to a jumper to provide continuous feed from the start to end of the tube length where other fibers in the same tube are simply spliced. The above format shall be repeated for each tube of a cable. Traffic multimode fiber measured in sections marked by traffic controller cabinets between Controller Sites may be sub-sectioned in an easy to understand format or may be jumpered using patch cords as a single OTDR Link with each section separated for power meter readings.

Continuity

Continuity tests shall be used to determine whether a test or system jumper does or does not pass light. A continuity test shall also be used to assure the fibers have not been crossed over in the jumper and that the transmit fiber goes to the receiver fiber. The visible light tester shall be utilized to illuminate faulty terminations or fibers with excessive bends failing to pass light.

To perform continuity test, a high-intensity red light (Visible Fault Identifier) light source shall be aimed into the connector at one end, while an observer watches for a flicker of light at the other end. One each 650 nm red NFL light source shall be furnished to the Engineer by the Contractor on request during the testing of the fiber by the Contractor for spot testing. This device shall be made available during testing of continuity to the Engineer to assist in verifying fault locations and connector bleeding.

OTDR Testing

An Optical Time Domain Reflectometer (OTDR) shall be used to evaluate the quality and length of cable reels prior to their use on the project. A minimum of one fiber per tube per reel shall be tested if payment for stored goods is requested. The fiber loss in dB/km and the length of each reel shall be recorded in the documentation. The maximum attenuation of the cable shall be as hereinbefore specified. This test does not require an electronic document; but is provided to insure that the fiber has been received in useable quality without shipment damage. The test results of the Contractor OTDR tests of received spools shall be provided to the Engineer, in a minimum of hard copy print, prior to receiving payment for stored goods.

An Optical Time Domain Reflectometer (OTDR) shall be used to evaluate the quality and length of cable installed on the project. This test shall be conducted on all fibers, terminated and not terminated, and shall be conducted after all terminations on the fibers for a link have been completed. The fiber loss in dB/km and the length of each reel shall be recorded in the documentation. The index of

City of Rockford Section 03-00520-00-WR Harrison Avenue

refraction, minimum of three decimal points, provided by the manufacturer on the spool documentation shall be used for the test on the OTDR. The maximum attenuation of the cable shall be as hereinbefore specified. A hard copy of OTDR signature traces, electronically and in printed form, for all fiber links shall be made and provided in the documentation as specified. The data provided shall be in easy to understand format and of sufficient detail to verify the results. Fiber testing shall include only one fiber trace per graph. One copy of the operating system software to view the fiber graphs shall be provided with the final documentation.

Documentation

The result of all testing shall be recorded along with date of test, name of person performing test, brand name, model number, serial number of equipment used during test, and any other pertinent information and data. The Contractor shall be responsible to provide input to the Engineer reviewing the recorded data documentation to resolve all questions or data discrepancies. A copy of the evaluation calculation equations to be used may be obtained by the Contractor by request and by supplying a floppy disk. (The evaluation FO Calculator is an EXCEL program worksheet that calculates design dB Loss based on required inputs.) Documentation shall be considered incidental to bid items and no additional compensation shall be provided.

The above work will be paid for at the contract unit price per foot for FIBER OPTIC CABLE IN CONDUIT, 48 FIBER SINGLE MODE AND 24 FIBER MULTIMODE.

LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 40 FT. M.H., 10 FT DAVIT ARM

This work shall conform to the applicable portions of Section 830 of the Standard Specifications. The pole shall have a mounting plate installed fifteen (15) feet above grade on the multi-use path side so that the specified path fixture can be installed onto the light pole.

The light poles shall be finished with a UV resistant coating of electrostatically applied polyester powder, or approved equivalent. Polyester coating shall be a minimum of 4 mils thick. Surface preparation shall be a chemical treatment process. The finish shall be oven-baked. The color shall be black.

This work will be paid for at the contract unit price each for LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 40 FT. M.H., 10 FT. DAVIT ARM.

LUMINAIRE, PULSE START METAL HALIDE, 150 WATT

This work shall conform to the applicable portions of Section 821 of the Standard Specifications. These fixtures and arms are to be furnished and installed along the multi-use path. The fixtures are as manufactured by Visionscapes, part No. ODN-IT2150P6PMBKC2H5/VSWA8 or approved equivalent. The fixture is 150 watt pulse start metal halide, type 2 full cutoff distribution, multi-tap ballast with a black powder coat finish.

This work will be paid for at the contract unit price each for LUMINAIRE, PULSE START METAL HALIDES, 150 WATT.

LUMINARE, PULSE START METAL HALIDE, 400 WATT

This work shall conform to the applicable portions of Section 821 of the Standard Specifications. These fixtures are to be furnished and installed on the 10 ft. Davit arms of the light poles. The fixtures are as manufactured by Visionscapes, part No. ODN-2T3400P6MAP-01BKC2H5 or approved equivalent. The fixture is 400 watt pulse start metal halide, type 3 full cutoff distribution, multi-tap ballast with black powder coat finish.

This work will be paid for at the contract unit price each for LUMINAIRE, PULSE START METAL HALIDE, 400 WATT.



Storm Water Pollution Prevention Plan

Route	EΔ	Route 303	Marked No
Section		3-00520-00-WR	Project No. <u>C-92-082-05</u>
County		Vinnebago	
Journ	y <u></u>	Vittlebago	
Enviro I certil accord submi	nment fy und dance tted. I	er penalty of law that this document and all atta with a system designed to assure that qualified Based on my inquiry of the person or persons who	achments were prepared under my direction or supervision in d personnel properly gathered and evaluated the information o manage the system, or those persons directly responsible for each of my knowledge and belief frue, accurate and complete.
am aw	vare th	at there are significant penalties for submitting fall violations.	se information, including the possibility of fine and imprisonment
IOI KIIC	owing ,	y joi au o i o .	
_	7		
1	0	Miller	April 26, 2006
199	(12E)	Signature	Date
City o	f Rock	ford, City Engineer	
Oity O	TROCK	Title	
			•
1.	Site D	Description	•
	a.	as necessary).	n activity which is the subject of this plan (use additional pages,
		ditches are to be replaced with concrete curb an modernized. The resurfacing section is from the	econstruction of an existing four-lane roadway. Roadside d gutter and storm sewer. Five signalized intersections are to be intersection of Harrison Avenue and 26 th Street east to Alpine ersection of Harrison Avenue and Alpine Road east until and Mulford Road intersections. This project consists of ding and paving.
	b.	portions of the construction site, such as grubbing	quence of major activities which will disturb soils for major ng, excavation and grading (use additional pages, as necessary):
		The sequence of events are as follows: clearing constructed in segments as shown in the approx	embankment,grading and paving. This project will be
		The sequence of events are as follows: clearing constructed in segments as shown in the approx	embankment,grading and paving. This project will be
		The sequence of events are as follows: clearing constructed in segments as shown in the approven	embankment,grading and paving. This project will be
	C.	The sequence of events are as follows: clearing constructed in segments as shown in the approximate total area of the construction site is estimate.	, embankment,grading and paving. This project will be red staging plans submitted by the contractor.

- d. The estimated runoff coefficients of the various areas of the site after construction activities are completed are contained in the project drainage study which is hereby incorporated by reference in this plan. Information describing the soils at the site is contained either in the Soils Report for the project, which is hereby incorporated by reference, or in an attachment to this plan.
- e. The design/project report, hydraulic report, or plan documents, hereby incorporated by reference, contain site map(s) indicating drainage patterns and approximate slopes anticipated after major grading activities, areas of major soil disturbance, the location of major structural and nonstructural controls identified in the plan, the location of areas where stabilization practices are expected to occur, surface waters (including wetlands), and locations where storm water is discharged to a surface water.
- f. The names of receiving water(s) and areal extent of wetland acreage at the site are in the design/project report or plan documents which are incorporated by reference as a part of this plan.

2. Controis

This section of the plan addresses the various controls that will be implemented for each of the major construction activities described in 1.b. above. For each measure discussed, the contractor that will be responsible for its implementation is indicated. Each such contractor has signed the required certification on forms which are attached to, and a part of, this plan:

a. Erosion and Sediment Controls

- Stabilization Practices. Provided below is a description of interim and permanent stabilization practices, including site-specific scheduling of the implementation of the practices. Site plans will ensure that existing vegetation is preserved where attainable and disturbed portions of the site will be stabilized. Stabilization practices may include: temporary seeding, permanent seeding, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, preservation of mature vegetation, and other appropriate measures. Except as provided in 2.a.(i).(A) and 2.b., stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased on all disturbed portions of the site where construction activity will not occur for a period of 21 or more calendar days.
 - (A) where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable thereafter.

Description of Stabilization Practices (use additional pages, as necessary):

Perimeter erosion control shall be placed prior to beginning earthwork. As earth excavation and embankment are being completed, the Contractor shall place ditch checks, inlet and pipe protection, erosion control blanket, and seeding as stages of the project are completed. Perimeter erosion barrier will be installed at additional locations as the project progresses. The Contractor will seed distrubed areas with temporary or permanent seeding as shown on the Erosion Control Plans or as directed by the Engineer.

(ii) Structural Practices. Provided below is a description of structural practices that will be implemented, to the degree attainable, to divert flows from exposed soils, store flows or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Such practices may include silt fences, earth dikes, drainage swales, sediment traps, check dams, subsurface drains, pipe slope drains, level spreaders, storm drain inlet protection, rock outlet protection, reinforced soil retaining systems, gabions and temporary or permanent sediment basins. The installation of these devices may be subject to Section 404 of the Clean Water Act.

Description of Structural Practices (use additional pages, as necessary):

Implementation of additional structural practices shall be at the direction of the Resident Engineer.

b. Storm Water Management

Provided below is a description of measures that will be installed during the construction process to control pollutants in storm water discharges that will occur after construction operations have been completed. The installation of these devices may be subject to Section 404 of the Clean Water Act.

- (I) Such practices may include: storm water detention structures (including wet ponds); storm water retention structures; flow attenuation by use of open vegetated swales and natural depressions; infiltration of runoff on site; and sequential systems (which combine several practices). The practices selected for implementation were determined on the basis of the technical guidance in Section 10-300 (Design Considerations) in Chapter 10 (Erosion and Sedimentation Control) of the Illinois Department of Transportation Drainage Manual. If practices other than those discussed in Section 10-300 are selected for implementation or if practices are applied to situations different from those covered in Section 10-300, the technical basis for such decisions will be explained below.
- Velocity dissipation devices will be placed at discharge locations and along the length of any outfall channel as necessary to provide a non-erosive velocity flow from the structure to a water course so that the natural physical and biological characteristics and functions are maintained and protected (e.g., maintenance of hydrologic conditions, such as the hydroperiod and hydrodynamics present prior to the initiation of construction activities).

Description of Storm Water Management Controls (use additional pages, as necessary):

Tempoary Ditch Checks and/or Perimeter Erosion Barrier shall be placed at culvert outlets as shown on the plan sheets or as directed by the Engineer.

c. Other Controls

- (i) Waste Disposal. No solid materials, including building materials, shall be discharged into Waters of the State, except as authorized by a Section 404 permit.
- (ii) The provisions of this plan shall ensure and demonstrate compliance with applicable State and/or local waste disposal, sanitary sewer or septic system regulations.

d. Approved State or Local Plans

The management practices, controls and provisions contained in this plan will be in accordance with IDOT specifications, which are at least as protective as the requirements contained in the Illinois Environmental Protection Agency's Illinois Urban Manual, 1995. Procedures and requirements specified in applicable sediment and erosion site plans or storm water management plans approved by local officials shall be described or incorporated by reference in the space provided below. Requirements specified in sediment and erosion site plans or site permits or storm water management site plans or site permits approved by local officials that are applicable to protecting surface water resources are, upon submittal of an NOI to be authorized to discharge under permit ILR10 incorporated by reference and are enforceable under this permit even if they are not specifically included in the plan.

Description of procedures and requirements specified in applicable sediment and erosion site plans or storm water management plans approved by local officials:

Refer to erosion control plan for further details.

3. Maintenance

The following is a description of procedures that will be used to maintain, in good and effective operating conditions, vegetation, erosion and sediment control measures and other protective measures identified in this plan (use additional pages, as necessary):

The Contractor will inspect weekly, or after any rainfall event, all erosion control measures in place. If any of the erosion control measures are found to be deficient, the Contractor will immediately repair said measures to applicable State Standards as shown on the Erosion Control Plan or as directed by the Engineer.

4. Inspections

Qualified personnel shall inspect disturbed areas of the construction site which have not been finally stabilized, structural control measures, and locations where vehicles enter or exit the site. Such inspections shall be conducted at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches or greater or equivalent snowfall.

- a. Disturbed areas and areas used for storage of materials that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters. Locations where vehicles enter or exit the site shall be inspected for evidence of off site sediment tracking.
- b. Based on the results of the inspection, the description of potential pollutant sources identified in section 1 above and pollution prevention measures identified in section 2 above shall be revised as appropriate as soon as practicable after such inspection. Any changes to this plan resulting from the required inspections shall be implemented within 7 calendar days following the inspection.
- c. A report summarizing the scope of the inspection, name(s) and qualifications of personnel making the inspection, the date(s) of the inspection, major observations relating to the implementation of this storm water pollution prevention plan, and actions taken in accordance with section 4.b. shall be made and retained as part of the plan for at least three (3) years after the date of the inspection. The report shall be signed in accordance with Part VI. G of the general permit.
- d. If any violation of the provisions of this plan is identified during the conduct of the construction work covered by this plan, the Resident Engineer or Resident Technician shall complete and file an "Incidence of Noncompliance" (ION) report for the identified violation. The Resident Engineer or Resident Technician shall use forms provided by the Illinois Environmental Protection Agency and shall include specific information on the cause of noncompliance, actions which were taken to prevent any further causes of noncompliance, and a statement detailing any environmental impact which may have resulted from the noncompliance. All reports of noncompliance shall be signed by a responsible authority in accordance with Part VI. G of the general permit.

The report of noncompliance shall be mailed to the following address:

Illinois Environmental Protection Agency Division of Water Pollution Control Attn: Compliance Assurance Section 1021 North Grand East Post Office Box 19276 Springfield, Illinois 62794-9276

5. Non-Storm Water Discharges

Except for flows from fire fighting activities, sources of non-storm water that is combined with storm water discharges associated with the industrial activity addressed in this plan must be described below. Appropriate pollution prevention measures, as described below, will be implemented for the non-storm water component(s) of the discharge. (Use additional pages as necessary to describe non-storm water discharges and applicable pollution control measures).

N/A



Contractor Certification Statement

This certification statement is a part of the Storm Water Pollution Prevention Plan for the project described below, in accordance with NPDES Permit No. ILR10, issued by the Illinois Environmental Protection Agency on May 14, 1998.

Project I	nformation:		
Route	FA Route 303	Marked N	0
Section	03-00520-00-WR	Project No.	C-92-082-05
County	Winnebago		
(NPDES	under penalty of law that I understand the terms b) permit (ILR 10) that authorizes the storm wate tified as part of this certification.	s of the general National er discharges associated	Pollutant Discharge Elimination System with industrial activity from the construction
	Signature		Date
	Title		
	Name of Firm		
	Street Address	 -	
City	State		
Žip C	ode		
	Telephone Number		

AGGREGATE SHIPPING TICKETS (BDE)

Effective: January 1, 2006

Add the following to Article 1003.01 of the Standard Specifications:

"(f) Shipping Tickets. Shipping tickets for the material shall be according to the current Bureau of Materials and Physical Research Policy Memorandum, "Designation of Aggregate Information on Shipping Tickets"."

Add the following to Article 1004.01 of the Standard Specifications:

"(f) Shipping Tickets. Shipping tickets for the material shall be according to the current Bureau of Materials and Physical Research Policy Memorandum, "Designation of Aggregate Information on Shipping Tickets"."

Add the following to Article 1005.01 of the Supplemental Specifications:

"(d) Shipping Tickets. Shipping tickets for the material shall be according to the current Bureau of Materials and Physical Research Policy Memorandum, "Designation of Aggregate Information on Shipping Tickets"."

BITUMINOUS CONCRETE SURFACE COURSE (BDE)

Effective: April 1, 2001 Revised: April 1, 2003

Replace the fourth paragraph of Article 406.23(b) of the Standard Specifications with the following:

"Mixture for cracks, joints, flangeways, leveling binder (machine method), leveling binder (hand method) and binder course in excess of 103 percent of the quantity specified by the Engineer will not be measured for payment.

Surface course mixture in excess of 103 percent of adjusted plan quantity will not be measured for payment. The adjusted plan quantity for surface course mixtures will be calculated as follows:

Adjusted Plan Quantity = C x quantity shown on the plans or as specified by the Engineer.

and where:

 G_{mh} = average bulk specific gravity from approved mix design.

U = Unit weight of surface course shown on the plans in kg/sq m/25 mm (lb/sq yd/in.), used to estimate plan quantity.

24.99 = metric constant.

46.8 = English constant.

If project circumstances warrant a new surface course mix design, the above equations shall be used to calculate the adjusted plan quantity for each mix design using its respective average bulk specific gravity."

BITUMINOUS EQUIPMENT, SPREADING AND FINISHING MACHINE (BDE)

Effective: January 1, 2005

Revise the fourth paragraph of Article 1102.03 of the Standard Specifications to read:

"The paver shall be equipped with a receiving hopper having sufficient capacity for a uniform spreading operation. The hopper shall be equipped with a distribution system to uniformly place a non-segregated mixture in front of the screed. The distribution system shall have chain curtains, deflector plates, and /or other devices designed and built by the paver manufacturer to prevent segregation during distribution of the mixture from the hopper to the paver screed. The Contractor shall submit a written certification that the devices recommended by the paver manufacturer to prevent segregation have been installed and are operational. Prior to paving, the Contractor, in the presence of the Engineer, shall visually inspect paver parts specifically identified by the manufacturer for excessive wear and the need for replacement. The Contractor shall supply a completed check list to the Engineer noting the condition of the parts. Worn parts shall be replaced. The Engineer may require an additional inspection prior to placement of the surface course or at other times throughout the work."

BUTT JOINTS (BDE)

Effective: April 1, 2004 Revised: April 1, 2005

Revise Article 406.18 of the Standard Specifications to read:

"406.18 Butt Joints. Butt joints shall be constructed according to the details shown on the plans. The surface removal shall be performed according to Section 440. Construction of butt joints shall not begin prior to beginning general operations on the project.

When butt joints are to be constructed under traffic, temporary ramps shall be constructed and maintained at both the upstream and downstream ends of the surface removal areas immediately upon completion of the surface removal operation. The temporary ramps shall be constructed by the following methods.

- (a) Temporary Bituminous Ramps. Temporary bituminous ramps shall have a minimum taper rate of 1:40 (V:H). The bituminous material used shall meet the approval of the Engineer. Cold-milled bituminous tailings will not be acceptable.
- (b) Temporary Rubber Ramps. Temporary rubber ramps shall only be used on roadways with permanent posted speeds of 55 mph or less. The ramps shall have a minimum taper rate of 1:30 (V:H). The leading edge of the rubber ramp shall have a maximum thickness of 6 mm (1/4 in.) and the trailing edge shall match the height of the adjacent pavement ± 6 mm (1/4 in.).

The rubber material shall conform to the following.

Property	Test Method	Requirement
Durometer Hardness, Shore A	ASTM D 2240	80 ±10
Tensile Strength	ASTM D 412	5500 kPa (800 psi) min.
Elongation, percent	ASTM D 412	100 min.
Specific Gravity	ASTM D 297	1.1-1.3
Brittleness	ASTM D 746	-40 °C (-40 °F)

The rubber ramps shall be installed according to the manufacturer's specifications and fastened with the anchors provided. Rubber ramps that fail to stay in place or create a traffic hazard shall be replaced immediately with temporary bituminous ramps at the Contractor's expense.

The temporary ramps shall be removed just prior to placing the proposed surface course. If work is suspended for the winter season prior to completion of surface course construction, precut butt joints shall be filled to the elevation of the existing pavement surface with compacted bituminous concrete surface course or binder course."

COARSE AGGREGATE FOR TRENCH BACKFILL, BACKFILL AND BEDDING (BDE)

Effective: April 1, 2001

Revised: November 1, 2003

Revise Article 208.02 of the Standard Specifications to read:

"208.02 Materials. Materials shall be according to the following Articles of Section 1000 -Materials:

- (a) Fine Aggregate (Note 1)......1003.04
- (b) Coarse Aggregate (Noté 2)1004.06
 - Note 1. The fine aggregate shall be moist to the satisfaction of the Engineer.
 - Note 2. The coarse aggregate shall be wet to the satisfaction of the Engineer."

Revise the first sentence of the second paragraph of subparagraph (b) in Article 208.03 of the Standard Specifications to read:

"Any material meeting the requirements of Articles 1003.04 or 1004.06 which has been excavated from the trenches shall be used for backfilling the trenches."

Add the following to the end of Article 542.02 of the Standard Specifications:

- "(bb) Fine Aggregate (Note 1)......1003.04
 - Note 1. The fine aggregate shall be moist to the satisfaction of the Engineer.
 - Note 2. The coarse aggregate shall be wet to the satisfaction of the Engineer."

Revise the first and second sentences of the second paragraph of subparagraph (a) of Article 542.04 of the Standard Specifications to read:

"The unstable and unsuitable material shall be removed to a depth determined by the Engineer and for a width of one diameter (or equivalent diameter) of the pipe on each side of the pipe culvert, and replaced with aggregate. Rock shall be removed to an elevation 300 mm (1 ft) lower than the bottom of the pipe or to a depth equal to 40 mm/m (1/2 in./ft) of ultimate fill height over the top of the pipe culvert, whichever is the greater depth, and for a width as specified in (b) below, and replaced with aggregate."

Revise the second paragraph of subparagraph (c) of Article 542.04 of the Standard Specifications to read:

"Well compacted aggregate, at least 100 mm (4 in.) in depth below the pipe culvert, shall be placed the entire width of the trench and for the length of the pipe culvert, except well compacted impervious material shall be used for the outer 1 m (3 ft) at each end of the pipe. When the trench has been widened by the removal and replacement of unstable or unsuitable material, the foundation material shall be placed for a width not less than the above specified widths on each side of the pipe. The aggregate and impervious material shall be approved by the Engineer and shall be compacted to the Engineer's satisfaction by mechanical means."

Revise subparagraph (e) of Article 542.04 of the Standard Specifications to read:

"(e) Backfilling. As soon as the condition of the pipe culvert will permit, the entire width of the trench shall be backfilled with aggregate to a height of at least the elevation of the center of the pipe. The aggregate shall be placed longitudinally along the pipe culvert, except at the outer 1 m (3 ft) at each end of the culvert which shall be backfilled with impervious material. The elevation of the backfill material on each side of the pipe shall be the same. The space under the pipe shall be completely filled. The aggregate and impervious material shall be placed in 200 mm (8 in.) layers, loose measurement. When using PVC, PE, or corrugated metal pipe, the aggregate shall be continued to a height of at least 300 mm (1 ft) above the top of the pipe and compacted to a minimum of 85 percent of standard lab density by mechanical means. When reinforced concrete pipes are used and the trench is within 600 mm (2 ft) of the pavement structure, the backfill shall be compacted to a minimum of 85 percent of standard lab density by mechanical means.

When using PVC, PE, or corrugated metal pipe a minimum of 300 mm (1 ft) of cover from the top of the pipe to the top of the subgrade will be required.

The installed pipe and its embedment shall not be disturbed when using movable trench boxes and shields, sheet pile, or other trench protection.

The remainder of the trench shall be backfilled with select material, from excavation or borrow, free from large or frozen lumps, clods or rock, meeting the approval of the Engineer. The material shall be placed in layers not exceeding 200 mm (8 in.) in depth, loose measurement and compacted to 95 percent of the standard laboratory density. Compaction shall be obtained by use of mechanical tampers or with approved vibratory compactors. Before compacting, each layer shall be wetted or dried to bring the moisture content within the limits of 80 to 110 percent of optimum moisture content determined according to AASHTO T 99 (Method C). All backfill material shall be deposited in the trench or excavation in such a manner as not to damage the culvert. The filling of the trench shall be carried on simultaneously on both sides of the pipe.

The Contractor may, at his/her expense, backfill the entire trench with aggregate in lieu of select material. The aggregate shall be compacted to the satisfaction of the Engineer by mechanical means.

The backfill material for all trenches and excavations made in the subgrade of the proposed improvement, and for all trenches outside of the subgrade where the inner edge of the trench is within 600 mm (2 ft) of the edge of the proposed pavement, curb, gutter, curb and gutter, stabilized shoulder, or sidewalk shall be according to Section 208. The trench backfill material shall be compacted to a minimum of 85 percent of standard lab density by mechanical means.

The Contractor may, at his/her expense, backfill the entire trench with controlled low strength material meeting the approval of the Engineer.

When the trench has been widened for the removal and replacement of unstable or unsuitable material, the backfilling with aggregate and impervious material, will be required for a width of at least the specified widths on each side of the pipe. The remaining width of each layer may be backfilled with select material. Each 200 mm (8 in.) layer for the entire trench width shall be completed before beginning the placement of the next layer."

Revise subparagraph (b) of Article 542.05 of the Standard Specifications to read:

"(b) Embankment. Embankment extending to an elevation of 300 mm (1 ft) over the top of the pipe shall be constructed according to Article 542.04(f), except the material up to the elevation of the center of the pipe and extending to a width of at least 450 mm (18 in.) on each side of the pipe, exclusive of the outer 1 m (3 ft) at each end of the pipe, shall consist of aggregate. At the outer 1 m (3 ft) at each end of the culvert, impervious material shall be used."

Add the following paragraph after the first paragraph of Article 542.10 of the Standard Specifications:

"Trench backfill will be measured for payment according to Article 208.03."

Add the following paragraph after the third paragraph of Article 542.11 of the Standard Specifications:

"Trench backfill will be paid for according to Article 208.04."

Add the following to of Article 550.02 of the Standard Specifications:

	1003.04
"(m) Fine Aggregate (Note 2)	1003.04 1004.06
(n) Coarse Aggregate (Note 3)	1004.06

- Note 2. The fine aggregate shall be moist to the satisfaction of the Engineer.
- Note 3. The coarse aggregate shall be wet to the satisfaction of the Engineer."

Revise the first two sentences of the third paragraph of Article 550.04 of the Standard Specifications to read:

"Well compacted, aggregate bedding material at least 100 mm (4 in.) in depth below the pipe, shall be placed for the entire width of the trench and length of the pipe. The aggregate shall be compacted to the satisfaction of the Engineer by mechanical means."

Revise Article 550.07 of the Standard Specifications to read:

"550.07 Backfilling. As soon as the condition of the pipe will permit, the entire width of the trench shall be backfilled with aggregate to a height of at least the elevation of the center of the pipe. The aggregate shall be placed longitudinally along the pipe. The elevation of the backfill material on each side of the pipe shall be the same. The space under the pipe shall be completely filled. The aggregate backfill material shall be placed in 200 mm (8 in.) layers, loose measurement and compacted to the satisfaction of the Engineer by mechanical means. When using PVC pipe, the aggregate shall be continued to a height of at least 300 mm (12 in.) above the top of the pipe.

The installed pipe and its embedment shall not be disturbed when using movable trench boxes and shields, sheet pile, or other trench protection.

The remainder of the trench and excavation shall be backfilled to the natural line or finished surface as rapidly as the condition of the sewer will permit. The backfill material shall consist of suitable excavated material from the trench or of trench backfill as herein specified. All backfill material shall be deposited in the trench or excavation in such a manner as not to damage the sewer and shall be compacted to the satisfaction of the Engineer by mechanical means. The filling of the trench shall be carried on simultaneously on both sides of the pipe.

The backfill material for trenches and excavation made in the subgrade of the proposed improvement, and for all trenches outside of the subgrade where the inner edge of the trench is within 600 mm (2 ft) of the edge of the proposed pavement, curb, gutter, curb and gutter, stabilized shoulder or sidewalk shall be according to Section 208. The backfill material shall be compacted to 85 percent of standard lab density by mechanical means.

All backfill material up to a height of 300 mm (1 ft) above the pipe shall be deposited in uniform layers not exceeding 200 mm (8 in.) thick, loose measurement. The material in each layer shall be compacted to the satisfaction of the Engineer by mechanical means. The

backfilling above this height shall be done according to Method 1, 2 or 3 as described below, with the following exceptions.

When trench backfill or excavated material meeting the requirements of Section 208 is required above the first 300 mm (1 ft) of the pipe, the layers shall not exceed 200 mm (8 in.). Gradations CA6 or CA10 shall not be used with Method 2 or Method 3.

- Method 1. The material shall be deposited in uniform layers not exceeding 300 mm (1 ft) thick, loose measurement, and each layer shall be compacted to the satisfaction of the Engineer by mechanical means.
- Method 2. The material shall be deposited in uniform layers not exceeding 300 mm (1 ft) thick, loose measurement, and each layer shall be either inundated or deposited in water.
- Method 3. The trench shall be backfilled with loose material, and settlement secured by introducing water through holes jetted into the backfill to a point approximately 600 mm (2 ft) above the top of the pipe. The holes shall be spaced as directed by the Engineer but shall be no farther than 2 m (6 ft) apart.

The water shall be injected at a pressure just sufficient to sink the holes at a moderate rate of speed. The pressure shall be such that the water will not cut cavities in the backfill material nor overflow the surface. If water does overflow the surface, it shall be drained into the jetted holes by means of shallow trenches.

Water shall be injected as long as it will be absorbed by the backfill material and until samples taken from test holes in the trench show a satisfactory moisture content. The Contractor shall bore the test holes not more than 15 m (50 ft) apart and at such other locations in the trench designated by the Engineer. As soon as the watersoaking has been completed, all holes shall be filled with soil and compacted by ramming with a tool approved by the Engineer.

Backfill material which has been watersoaked shall be allowed to settle and dry for at least 10 days before any surface course or pavement is constructed on it. The length of time may be altered, if deemed desirable, by the Engineer. Where the inner edge of the trench is within 600 mm (2 ft) of the edge of the proposed pavement, curb, gutter, curb and gutter, stabilized shoulder or sidewalk, the provisions of this paragraph shall also apply.

At the end of the settling and drying period, the crusted top of the backfill material shall be scarified and, if necessary, sufficient backfill material added, as specified in Method 1, to complete the backfilling operations.

The method used for backfilling and compacting the backfill material shall be the choice of the Contractor. If the method used does not produce results satisfactory to the Engineer, the Contractor will be required to alter or change the method being used so the resultant backfill will be satisfactory to the Engineer. Should the Contractor be required to alter or change the

method being used, no additional compensation will be allowed for altering or changing the method.

The Contractor may, at his/her expense, backfill the entire trench with controlled low strength material meeting the approval of the Engineer.

When sheeting and bracing have been used, sufficient bracing shall be left across the trench as the backfilling progresses to hold the sides firmly in place without caving or settlement. This bracing shall be removed as soon as practicable. Any depressions which may develop within the area involved in the construction operation due to settlement of the backfilling material shall be filled in a manner approved by the Engineer.

When the Contractor constructs the trench with sloped or benched sides according to Article 550.04, backfilling for the full width of the excavation shall be as specified, except no additional compensation will be allowed for trench backfill material required outside the vertical limits of the specified trench width.

Whenever excavation is made for installing sewer pipe across earth shoulders or private property, the topsoil disturbed by excavation operations shall be replaced as nearly as possible in its original position, and the whole area involved in the construction operations shall be left in a neat and presentable condition.

When using any PVC pipe, the pipe shall be backfilled with aggregate to 300 mm (1 ft) over the top of the pipe and compacted to a minimum of 85 percent of standard lab density by mechanical means.

When reinforced concrete pipes are used and the trench is within 600 mm (2 ft) of the pavement structure, the backfill shall be compacted to a minimum of 85 percent of standard lab density by mechanical means.

Deflection Testing for Storm Sewers. All PVC storm sewers will be tested for deflection not less than 30 days after the pipe is installed and the backfill compacted.

For PVC storm sewers with diameters 600 mm (24 in.) or smaller, a mandrel drag shall be used for deflection testing. For PVC storm sewers with diameters over 600 mm (24 in.), deflection measurements other than by a mandrel drag shall be used.

Where the mandrel is used, the mandrel shall be furnished by the Contractor and pulled by hand through the pipeline with a suitable rope or cable connected to each end. Winching or other means of forcing the deflection gauge through the pipeline will not be allowed.

The mandrel shall be of a shape similar to that of a true circle enabling the gauge to pass through a satisfactory pipeline with little or no resistance. The mandrel shall be of a design to prevent it from tipping from side to side and to prevent debris build-up from occurring between the channels of the adjacent fins or legs during operation. Each end of the core of the mandrel shall have fasteners to which the pulling cables can be attached. The mandrel shall have 9,

various sized fins or legs of appropriate dimension for various diameter pipes. Each fin or leg shall have a permanent marking that states its designated pipe size and percent of deflection allowable.

The outside diameter of the mandrel shall be 95 percent of the base inside diameter, where the base inside diameter is:

For all PVC pipe (as defined using ASTM D 3034 methodology):

If the pipe is found to have a deflection greater than specified, that pipe section shall be removed, replaced, and retested."

Revise subparagraph (c) of Article 1003.04 of the Standard Specifications to read:

"(c) Gradation. The fine aggregate gradation shall be as follows:

Revise the title of Article 1004.06 of the Standard Specifications to read:

"Coarse Aggregate for Blotter, Embankment, Backfill, Trench Backfill, French Drains, and Bedding."

Add the following to the end of subparagraph (c) of Article 1004.06 of the Standard Specifications:

CONCRETE ADMIXTURES (BDE)

Effective: January 1, 2003 Revised: July 1, 2004

Revise Article 1020.05(b) of the Standard Specifications to read:

"(b) Admixtures. Except as specified, the use of admixtures to increase the workability or to accelerate the hardening of the concrete will be permitted only when approved in writing by the Engineer. The Department will maintain an Approved List of Concrete Admixtures. When the Department permits the use of a calcium chloride accelerator, it shall be according to Article 442.02, Note 5.

When the atmosphere or concrete temperature is 18 °C (65 °F) or higher, a retarding admixture meeting the requirements of Article 1021.03 shall be used in the Class BD Concrete and portland cement concrete bridge deck overlays. The amount of retarding admixture to be used will be determined by the Engineer. The proportions of the ingredients of the concrete shall be the same as without the retarding admixture except that the amount of mixing water shall be reduced, as may be necessary, in order to maintain the consistency of the concrete as required. In addition, a high range water-reducing admixture shall be used in Class BD Concrete. The amount of high range water-reducing admixture will be determined by the Engineer. At the option of the Contractor, a water-reducing admixture may be used. Type I cement shall be used.

For Class PC and PS Concrete, a retarding admixture may be added to the concrete mixture when the concrete temperature is 18 °C (65 °F) or higher. Other admixtures may be used when approved by the Engineer, or if specified by the contract. If an accelerating admixture is permitted by the Engineer, it shall be the non-chloride type.

At the Contractor's option, admixtures in addition to an air-entraining admixture may be used for Class PP-1 concrete. The accelerator shall be the non-chloride type. If a water-reducing or retarding admixture is used, the cement factor may be reduced a maximum 18 kg/cu m (0.30 hundredweight/cu yd). If a high range water-reducing admixture is used, the cement factor may be reduced a maximum 36 kg/cu m (0.60 hundredweight/cu yd). Cement factor reductions shall not be cumulative when using multiple admixtures. An accelerator shall always be added prior to a high range water-reducing admixture, if both are used.

If Class C fly ash or ground granulated blast-furnace slag is used in Class PP-1 concrete, a water-reducing or high range water-reducing admixture shall be used. However, the cement factor shall not be reduced if a water-reducing, retarding, or high range water-reducing admixture is used. In addition, an accelerator shall not be used.

For Class PP-2 or PP-3 concrete, a non-chloride accelerator followed by a high range water-reducing admixture shall be used, in addition to the air-entraining admixture. For Class PP-3 concrete, the non-chloride accelerator shall be calcium nitrite.

For Class PP-2 or PP-3 concrete, the Contractor has the option to use a water-reducing admixture. A retarding admixture shall not be used unless approved by the Engineer. A water-reducing, retarding, or high range water-reducing admixture shall not be used to reduce the cement factor.

When the air temperature is less than 13 °C (55 °F) for Class PP-1 or PP-2 concrete, the non-chloride accelerator shall be calcium nitrite.

For Class PP-4 concrete, a high range water-reducing admixture shall be used in addition to the air-entraining admixture. The Contractor has the option to use a water-reducing admixture. An accelerator shall not be used. For stationary or truck mixed concrete, a retarding admixture shall be used to allow for haul time. The Contractor has the option to use a mobile portland cement concrete plant according to Article 1103.04, but a retarding admixture shall not be used unless approved by the Engineer. A water-reducing, retarding, or high range water-reducing admixture shall not be used to reduce the cement factor.

If the Department specifies a calcium chloride accelerator for Class PP-1 concrete, the maximum chloride dosage shall be 1.0 L (1.0 quart) of solution per 45 kg (100 lb) of cement. The dosage may be increased to a maximum 2.0 L (2.0 quarts) per 45 kg (100 lb) of cement if approved by the Engineer. If the Department specifies a calcium chloride accelerator for Class PP-2 concrete, the maximum chloride dosage shall be 1.3 L (1.3 quarts) of solution per 45 kg (100 lb) of cement. The dosage may be increased to a maximum 2.6 L (2.6 quarts) per 45 kg (100 lb) of cement if approved by the Engineer.

For Class PV, MS, SI, RR, SC and SH concrete, at the option of the Contractor, or when specified by the Engineer, a water-reducing admixture or a retarding admixture may be used. The amount of water-reducing admixture or retarding admixture permitted will be determined by the Engineer. The air-entraining admixture and other admixtures shall be added to the concrete separately, and shall be permitted to intermingle only after they have separately entered the concrete batch. The sequence, method and equipment for adding the admixtures shall be approved by the Engineer. The water-reducing admixture shall not delay the initial set of the concrete by more than one hour. Type I cement shall be used.

When a water-reducing admixture is added, a cement factor reduction of up to 18 kg/cu m (0.30 hundredweight/cu yd), from the concrete designed for a specific slump without the admixture, will be permitted for Class PV, MS, SI, RR, SC and SH concrete. When an approved high range water-reducing admixture is used, a cement factor reduction of up to 36 kg/cu m (0.60 hundredweight/cu yd), from a specific water cement/ratio without the admixture, will be permitted based on a 14 percent minimum water reduction. This is applicable to Class PV, MS, SI, RR, SC and SH concrete. A cement factor below 320 kg/cu m (5.35 hundredweight/cu yd) will not be permitted for Class PV, MS, SI, RR, SC and SH concrete. A cement factor reduction will not be

allowed for concrete placed underwater. Cement factor reductions shall not be cumulative when using multiple admixtures.

For use of admixtures to control concrete temperature, refer to Articles 1020.14(a) and 1020.14(b).

The maximum slumps given in Table 1 may be increased to 175 mm (7 in.) when a high range water-reducing admixture is used for all classes of concrete except Class PV and PP."

Revise Section 1021 of the Standard Specifications to read:

"SECTION 1021. CONCRETE ADMIXTURES

1021.01 General. Admixtures shall be furnished in liquid form ready for use. The admixtures may be delivered in the manufacturer's original containers, bulk tank trucks or such containers or tanks as are acceptable to the Engineer. Delivery shall be accompanied by a ticket which clearly identifies the manufacturer and trade name of the material. Containers shall be readily identifiable to the satisfaction of the Engineer as to manufacturer and trade name of the material they contain.

Prior to inclusion of a product on the Department's Approved List of Concrete Admixtures, the manufacturer shall submit a report prepared by an independent laboratory accredited by the AASHTO Accreditation Program. The report shall show the results of physical tests conducted no more than five years prior to the time of submittal, according to applicable specifications.

Tests shall be conducted using materials and methods specified on a "test" concrete and a "reference" concrete, together with a certification that no changes have been made in the formulation of the material since the performance of the tests. Per the manufacturer's option, the cement content for all required tests shall either be according to applicable specifications or 335 kg/cu m (5.65 cwt/cu yd). Compressive strength test results for six months and one year will not be required.

In addition to the report, the manufacturer shall submit AASHTO T 197 water content and set time test results on the standard cement used by the Department. The test and reference concrete mixture shall contain a cement content of 335 kg/cu m (5.65 cwt/cu yd). The manufacturer may select their lab or an independent lab to perform this testing. The laboratory is not required to be accredited by the AASHTO Accreditation Program.

Prior to the approval of an admixture, the Engineer may conduct all or part of the applicable tests on a sample that is representative of the material to be furnished. The test and reference concrete mixtures tested by the Engineer will contain a cement content of 335 kg/cu m (5.65 cwt/cu yd). For freeze-thaw testing, the Department will perform the test according to Illinois Modified AASHTO T 161, Procedure B.

The manufacturer shall include in the submittal the following information according to ASTM C 494; the average and manufacturing range of specific gravity, the average and manufacturing range of solids in the solution, and the average and manufacturing range of pH. The submittal shall also include an infrared spectrophotometer trace no more than five years old.

When test results are more than seven years old, the manufacturer shall re-submit the infrared spectrophotometer trace and the report prepared by an independent laboratory accredited by the AASHTO Accreditation Program.

All admixtures, except chloride-based accelerators, shall contain no more than 0.3 percent chloride by mass (weight).

1021.02 Air-Entraining Admixtures. Air-entraining admixtures shall conform to the requirements of AASHTO M 154.

If the manufacturer certifies that the air-entraining admixture is an aqueous solution of Vinsol resin that has been neutralized with sodium hydroxide (caustic soda), testing for compliance with the requirements may be waived by the Engineer. In the certification, the manufacturer shall show complete information with respect to the formulation of the solution, including the number of parts of Vinsol resin to each part of sodium hydroxide. Before the approval of its use is granted, the Engineer will test the solution for its air-entraining quality in comparison with a solution prepared and kept for that purpose.

- 1021.03 Retarding and Water-Reducing Admixtures. The admixture shall comply with the following requirements:
 - (a) The retarding admixture shall comply with the requirements of AASHTO M 194, Type B (retarding) or Type D (water-reducing and retarding).
 - (b) The water-reducing admixture shall comply with the requirements of AASHTO M 194, Type A.
 - (c) The high range water-reducing admixture shall comply with the requirements of AASHTO M 194, Type F (high range water-reducing) or Type G (high range waterreducing and retarding).

When a Type F or Type G high range water-reducing admixture is used, water-cement ratios shall be a minimum of 0.32.

Type F or Type G admixtures may be used, subject to the following restrictions:

For Class MS, SI, RR, SC and SH concrete, the water-cement ratio shall be a maximum of 0.44.

The Type F or Type G admixture shall be added at the jobsite unless otherwise directed by the Engineer. The initial slump shall be a minimum of 40 mm (1 1/2 in.)

prior to addition of the Type F or Type G admixture, except as approved by the Engineer.

When a Type F or Type G admixture is used, retempering with water or with a Type G admixture will not be allowed. An additional dosage of a Type F admixture, not to exceed 40 percent of the original dosage, may be used to retemper concrete once, provided set time is not unduly affected. A second retempering with a Type F admixture may be used for all classes of concrete except Class PP and SC, provided that the dosage does not exceed the dosage used for the first retempering, and provided that the set time is not unduly affected. No further retempering will be allowed.

Air tests shall be performed after the addition of the Type F or Type G admixture.

1021.04 Set Accelerating Admixtures. The admixture shall comply with the requirements of AASHTO M 194, Type C (accelerating) or Type E (water reducing and accelerating)"

CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE)

Effective: January 1, 2004 Revised: November 1, 2005

Revise the second and third sentences of the eleventh paragraph of Article 503.06 of the Standard Specifications to read:

"Forms on substructure units shall remain in place at least 24 hours. The method of form removal shall not result in damage to the concrete."

Delete the twentieth paragraph of Article 503.22 of the Standard Specifications.

Revise the "Unit Price Adjustments" table of Article 503.22 of the Standard Specifications to read:

"UNIT PRICE ADJUSTMENTS	
Type of Construction	Percent Adjustment in Unit Price
For concrete in substructures, culverts (having a waterway opening of more than 1 sq m (10 sq ft)), pump houses, and retaining walls (except concrete pilings, footings and foundation seals):	
When protected by: Protection Method II Protection Method I	115% 10%
For concrete in superstructures: When protected by: Protection Method II Protection Method I	123% 115%
For concrete in footings: When protected by: Protection Method I, II or III	107%
For concrete in slope walls: When protected by: Protection Method I	107%"

Delete the fourth paragraph of Article 504.05(a) of the Standard Specifications.

Revise the second and third sentences of the fifth paragraph of Article 504.05(a) of the Standard Specifications to read:

"All test specimens shall be cured with the units according to Article 1020.13."

Revise the first paragraph of Article 504.06(c)(6) of the Standard Specifications to read:

"Curing and Low Air Temperature Protection. The curing and protection for precast, prestressed concrete members shall be according to Article 1020.13 and this Article."

Revise the first sentence of the second paragraph of Article 504.06(c)(6) of the Standard Specifications to read:

"For curing, air vents shall be in place and shall be so arranged that no water can enter the void tubes during the curing of the members."

Revise the first sentence of the third paragraph of Article 504.06(c)(6) of the Standard Specifications to read:

"As soon as each member is finished, the concrete shall be covered with curing material according to Article 1020.13."

Revise the eighth paragraph of Article 504.06(c)(6) of the Standard Specifications to read:

"The prestressing force shall not be transferred to any member before the concrete has attained the compressive strength of 28,000 kPa (4000 psi) or other higher compressive release strength specified on the plans, as determined from tests of 150 mm (6 in.) by 300 mm (12 in.) cylinders cured with the member according to Article 1020.13. Members shall not be shipped until 28-day strengths have been attained and members have a yard age of at least 4 days."

Delete the third paragraph of Article 512.03(a) of the Standard Specifications.

Delete the last sentence of the second paragraph of Article 512.04(d) of the Standard Specifications.

Revise the "Index Table of Curing and Protection of Concrete Construction" table of Article 1020.13 of the Standard Specifications to read:

"INDEX TABLE OF C	CURING AND PROTECTION OF	F CONCRETE C	CONSTRUCTION
TYPE OF CONSTRUCTION	CURING METHODS	CURING PERIOD DAYS	LOW AIR TEMPERATURE PROTECTION METHODS
Cast-in-Place Concrete: 11/			
Pavement Shoulder	1020.13(a)(1)(2)(3)(4)(5) 3/5/	3	1020.13(c)
Base Course Base Course Widening	1020.13(a)(1)(2)(3)(4)(5) 1/2/	3	1020.13(c)
Driveway Median Curb Gutter Curb and Gutter Sidewalk Slope Wall	1020.13(a)(1)(2)(3)(4)(5) 4/5/	3	1020.13(c) ^{16/}
Catch Basin Manhole Iniet Valve Vault	1020.13(a)(1)(2)(3)(4)(5) 4/	3	1020.13(e)
Pavement Patching	1020.13(a)(1)(2)(3)(4)(5) 2/	3 ^{12/}	1020.13(c)
	1020.13(a)(1)(2)(3)(4)(5) 1/2/	3	442.06(h) and 1020.13(c)
Pavement Replacement	1020.13(a)(3)(5)	1	1020.13(c)
Railroad Crossing	1020.13(a)(3)(5)		1020.13(e)(1)(2)(3)
Piles Footings	1020.13(a)(1)(2)(3)(4)(5) 4/6/	7	1020.13(e)(1)(2)(3)
Foundation Seals	1020.13(a)(1)(2)(3)(4)(5) 1/7/	7	1020.13(e)(1)(2)(3)
Substructure	1020.13(a)(1)(2)(3)(5) ⁸ /	7	1020.13(e)(1)(2)
Superstructure (except deck)		7	1020.13(e)(1)(2) 17/
Deck	1020.13(a)(5)	7	1020.13(e)(1)(2)
Retaining Walls	1020.13(a)(1)(2)(3)(4)(5) 1/7/	7	1020.13(e)(1)(2)
Pump Houses	1020.13(a)(1)(2)(3)(4)(5) 1/	7	1020.13(e)(1)(2) ^{18/}
Culverts	1020.13(a)(1)(2)(3)(4)(5) 4/6/ 1020.13(a)(1)(2)(3)(5)	3	1020.13(c)
Other Incidental Concrete	1020.13(a)(1)(2)(3)(3)		1020.10(0)
Precast Concrete: 11/ Bridge Beams Piles Bridge Slabs Nelson Type Structural Member	1020.13(a)(3)(5) 9/ 10/		^{13/} 504.06(c)(6), 1020.13(e)(2) ^{19/}
All Other Precast Items	1020.13(a)(3)(4)(5) 2/9/10/	As required.	^{14/} 504.06(c)(6), 1020.13(e)(2) ^{19/}
Precast, Prestressed Concrete:			
All Items	1020.13(a)(3)(5) 9/ 10/	Until strand tensioning is released. 15/	504.06(c)(6), 1020.13(e)(2) ^{19/}

Notes-General:

- 1/ Type I, membrane curing only
- 2/ Type II, membrane curing only
- 3/ Type III, membrane curing only
- 4/ Type I, II and III membrane curing
- 5/ Membrane curing will not be permitted between November 1 and April 15.
- 6/ The use of water to inundate footings, foundation seals or the bottom slab of culverts is permissible when approved by the Engineer, provided the water temperature can be maintained at 7 °C (45 °F) or higher.
- 7/ Asphalt Emulsion for Waterproofing may be used in lieu of other curing methods when specified and permitted according to Article 503.18.
- 8/ On non-traffic surfaces which receive protective coat according to Article 503.19, a linseed oil emulsion curing compound may be used as a substitute for protective coat and other curing methods. The linseed emulsion curing compound will be permitted between April 16 and October 31 of the same year, provided it is applied with a mechanical sprayer according to Article 1101.09 (b), and meets the material requirements of Article 1022.07.
- 9/ Steam curing (heat and moisture) is acceptable and shall be accomplished by the method specified in Article 504.06(c)(6).
- 10/ A moist room according to AASHTO M 201 is acceptable for curing.
- 11/ If curing is required and interrupted because of form removal for cast-in-place concrete items, precast concrete products, or precast prestressed concrete products, the curing shall be resumed within two hours from the start of the form removal.
- 12/ Curing maintained only until opening strength is attained, with a maximum curing period of three days.
- 13/ The curing period shall end when the concrete has attained the mix design strength. The producer has the option to discontinue curing when the concrete has attained 80 percent of the mix design strength or after seven days. All strength test specimens shall remain with the units and shall be subjected to the same curing method and environmental condition as the units, until the time of testing.
- 14/ The producer shall determine the curing period or may elect to not cure the product. All strength test specimens shall remain with the units and shall be subjected to the same curing method and environmental condition as the units, until the time of testing.
- 15/ The producer has the option to continue curing after strand release.
- 16/ When structural steel or structural concrete is in place above slope wall, Article 1020.13(c) shall not apply. The protection method shall be according to Article 1020.13(e)(1).
- 17/ When Article 1020.13(e)(2) is used to protect the deck, the housing may enclose only the bottom and sides. The top surface shall be protected according to Article 1020.13(e)(1).
- 18/ For culverts having a waterway opening of 1 sq m (10 sq ft) or less, the culverts may be protected according to Article 1020.13(e)(3).
- 19/ The seven day protection period in the first paragraph of Article 1020.13(e)(2) shall not apply. The protection period shall end when curing is finished. For the third paragraph of Article 1020.13(e)(2), the decrease in temperature shall be according to Article 504.06(c)(6)."

Add the following to Article 1020.13(a) of the Standard Specifications:

"(5) Wetted Cotton Mat Method. After the surface of concrete has been textured or finished, it shall be covered immediately with dry cotton mats. The cotton mats shall be placed in a manner which will not mar the concrete surface. A texture resulting from the cotton mat material is acceptable. The cotton mats shall then be wetted immediately and thoroughly soaked with a gentle spray of water. For bridge decks, a foot bridge shall be used to place and wet the cotton mats.

The cotton mats shall be maintained in a wetted condition until the concrete has hardened sufficiently to place soaker hoses without marring the concrete surface. The soaker hoses shall be placed on top of the cotton mats at a maximum 1.2 m (4 ft) spacing. The cotton mats shall be kept wet with a continuous supply of water for the remainder of the curing period. Other continuous wetting systems may be used if approved by the Engineer.

After placement of the soaker hoses, the cotton mats shall be covered with white polyethylene sheeting or burlap-polyethylene blankets.

For construction items other than bridge decks, soaker hoses or a continuous wetting system will not be required if the alternative method keeps the cotton mats wet. Periodic wetting of the cotton mats is acceptable.

For areas inaccessible to the cotton mats on bridge decks, curing shall be according to Article 1020.13(a)(3)."

Revise the first paragraph of Article 1020.13(c) of the Standard Specifications to read:

"Protection of Portland Cement Concrete, Other Than Structures, From Low Air Temperatures. When the official National Weather Service forecast for the construction area predicts a low of 0 °C (32 °F), or lower, or if the actual temperature drops to 0 °C (32 °F), or lower, concrete less than 72 hours old shall be provided at least the following protection:"

Delete Article 1020.13(d) and Articles 1020.13(d)(1),(2),(3),(4) of the Standard Specifications.

Revise the first five paragraphs of Article 1020.13(e) of the Standard Specifications to read:

"Protection of Portland Cement Concrete Structures From Low Air Temperatures. When the official National Weather Service Forecast for the construction area predicts a low below 7 °C (45 °F), or if the actual temperature drops below 7 °C (45 °F), concrete less than 72 hours old shall be provided protection. Concrete shall also be provided protection when placed during the winter period of December 1 through March 15. Concrete shall not be placed until the materials, facilities, and equipment for protection are approved by the Engineer.

When directed by the Engineer, the Contractor may be required to place concrete during the winter period. If winter construction is specified, the Contractor shall proceed with the construction, including concrete, excavation, pile driving, steel erection, and all appurtenant work required for the complete construction of the item, except at times when weather conditions make such operations impracticable.

Regardless of the precautions taken, the Contractor shall be responsible for protection of the concrete placed and any concrete damaged by cold temperatures shall be removed and replaced at no additional cost to the Department."

Add the following at the end of the third paragraph of Article 1020.13(e)(1) of the Standard Specifications:

"The Contractor shall provide means for checking the temperature of the surface of the concrete during the protection period."

Revise the second sentence of the first paragraph of Article 1020.13(e)(2) of the Standard Specifications to read:

"The Contractor shall provide means for checking the temperature of the surface of the concrete or air temperature within the housing during the protection period."

Delete the last sentence of the first paragraph of Article 1020.13(e)(3) of the Standard Specifications.

Add the following Article to Section 1022 of the Standard Specifications:

"1022.06 Cotton Mats. Cotton mats shall consist of a cotton fill material, minimum 400 g/sq m (11.8 oz/sq yd), covered with unsized cloth or burlap, minimum 200 g/sq m (5.9 oz/sq yd), and be tufted or stitched to maintain stability.

Cotton mats shall be in a condition satisfactory to the Engineer. Any tears or holes in the mats shall be repaired."

Add the following Article to Section 1022 of the Standard Specifications:

"1022.07 Linseed Oil Emulsion Curing Compound. Linseed oil emulsion curing compound shall be composed of a blend of boiled linseed oil and high viscosity, heavy bodied linseed oil emulsified in a water solution. The curing compound shall meet the requirements of a Type I according to Article 1022.01, except the drying time requirement will be waived. The oil phase shall be 50 ± 4 percent by volume. The oil phase shall consist of 80 percent by mass (weight) boiled linseed oil and 20 percent by mass (weight) Z-8 viscosity linseed oil. The water phase shall be 50 ± 4 percent by volume."

Revise Article 1020.14 of the Standard Specifications to read:

"1020.14 Temperature Control for Placement. Temperature control for concrete placement shall be according to the following.

(a) Temperature Control other than Structures. The temperature of the concrete immediately before placement shall be a minimum of 10 °C (50 °F) and a maximum of 32 °C (90 °F). Aggregates and/or water shall be heated or cooled as necessary to produce concrete within these temperature limits.

When the temperature of the plastic concrete reaches 30 °C (85 °F), an approved retarding admixture shall be used or the approved water reducing admixture in use shall have its dosage increased by 50 percent over the dosage recommended on the Department's Approved List of Concrete Admixtures for the temperature experienced. The amount of retarding admixture to be used will be determined by the Engineer. This requirement may be waived by the Engineer when fly ash compensated mixtures are used.

Plastic concrete temperatures up to 35 °C (96 °F), as placed, may be permitted provided job site conditions permit placement and finishing without excessive use of water on and/or overworking of the surface. The occurrence within 24 hours of unusual surface distress shall be cause to revert to a maximum 32 °C (90 °F) plastic concrete temperature.

Concrete shall not be placed when the air temperature is below 5 °C (40 °F) and falling or below 2 °C (35 °F), without permission of the Engineer. When placing of concrete is authorized during cold weather, the Engineer may require the water and/or the aggregates to be heated to between 20 °C (70 °F) and 65 °C (150 °F). The aggregates may be heated by either steam or dry heat prior to being placed in the mixer. The apparatus used shall heat the mass uniformly and shall be so arranged as to preclude the possible occurrence of overheated areas which might damage the materials. No frozen aggregates shall be used in the concrete.

For pavement patching, refer to Article 442.06(e) for additional information on temperature control for placement.

(b) Temperature Control for Structures. The temperature of the concrete, as placed in the forms, shall be a minimum of 10 °C (50 °F) and a maximum of 32 °C (90 °F). Aggregates and/or water shall be heated or cooled as necessary to produce concrete within these temperature limits. When insulated forms are used, the temperature of the concrete mixture shall not exceed 25 °C (80 °F). If the Engineer determines that heat of hydration might cause excessive temperatures in the concrete, the concrete shall be placed at a temperature between 10 °C (50 °F) and 15 °C (60 °F). When concrete is placed in contact with previously placed concrete, the temperature of the concrete may be increased as required to offset anticipated heat loss.

Concrete shall not be placed when the air temperature is below 7 °C (45 °F) and falling or below 4 °C (40 °F), without permission of the Engineer. When placing of concrete is authorized during cold weather, the Engineer may require the water and/or the aggregates to be heated to between 20 °C (70 °F) and 65 °C (150 °F). The aggregates may be heated by either steam or dry heat prior to being placed in the mixer. The apparatus used shall heat the mass uniformly and shall be so arranged as to preclude the possible occurrence of overheated areas which might damage the materials. No frozen aggregates shall be used in the concrete.

When the temperature of the plastic concrete reaches 30 °C (85 °F), an approved retarding admixture shall be used or the approved water reducing admixture in use shall have its dosage increased by 50 percent over the dosage recommended on the Department's Approved List of Concrete Admixtures for the temperature experienced. The amount of retarding admixture to be used will be determined by the Engineer. This requirement may be waived by the Engineer when fly ash compensated mixtures are used.

(c) Temperature. The concrete temperature shall be determined according to ASTM C 1064."

DETECTABLE WARNINGS (BDE)

Effective: August 1, 2005

Replace Articles 424.08 – 424.12 of the Standard Specifications with the following:

"424.08 Curb Ramps. Curb ramps shall be constructed according to the Americans with Disabilities Act Accessibility Guidelines (ADAAG), the Illinois Accessibility Code, and as shown on the plans.

Curb ramps shall be constructed to the same thickness as the adjacent sidewalk with a minimum thickness of 100 mm (4 in.).

424.09 Detectable Warnings. Detectable warnings shall consist of a surface of truncated domes meeting the requirements of the ADAAG and the details shown on the plans.

Detectable warnings shall be installed at curb ramps, medians and pedestrian refuge islands, at-grade railroad crossings, transit platform edges, and other locations where pedestrians are required to cross a hazardous vehicular way. Detectable warnings shall also be installed at alleys and commercial entrances when permanent traffic control devices are present. The installation shall be an integral part of the walking surface and only the actual domes shall project above the walking surface.

The product or method used for installing detectable warnings shall come with the following documents which shall be given to the Engineer prior to use.

- (a) Manufacturer's certification stating the product is fully compliant with the ADAAG.
- (b) Manufacturer's five year warranty.
- (c) Manufacturer's specifications stating the required materials, equipment, and installation procedures.

Products that are colored shall be colored their entire thickness.

The materials, equipment, and installation procedures used shall be according to the manufacturer's specifications.

- **424.10 Backfill.** After the concrete has been cured, the spaces along the edges of the sidewalk and ramps shall be backfilled with approved material. The material shall be compacted until firm and the surface neatly graded.
- 424.11 Disposal of Surplus Material. Surplus or waste material shall be disposed of according to Article 202.03.

424.12 Method of Measurement. This work will be measured for payment in place and the area computed in square meters (square feet). Curb ramps will be measured for payment as sidewalk. No deduction will be made for detectable warnings located within the ramp.

Detectable warnings will be measured for payment in place and the area computed in square meters (square feet).

Earth excavation will be measured for payment according to Article 202.07.

424.13 Basis of Payment. This work will be paid for at the contract unit price per square meter (square foot) for PORTLAND CEMENT CONCRETE SIDEWALK, of the thickness specified.

Detectable warnings will be paid for at the contract unit price per square meter (square foot) for DETECTABLE WARNINGS.

Earth excavation will be paid for according to Article 202.08."

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION

Effective: September 1, 2000 Revised: June 22, 2005

FEDERAL OBLIGATION. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the DBE Directory or most recent addendum.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100% state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100% state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE firms performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of

- (a) The bidder documents that firmly committed DBE participation has been obtained to meet the goal; or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

DBE LOCATOR REFERENCES. Bidders may consult the DBE Directory as a reference source for DBE companies certified by the Department. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.state.il.us.

<u>BIDDING PROCEDURES</u>. Compliance with the bidding procedures of this Special Provision is required prior to the award of the contract and the failure of the as-read low bidder to comply will render the bid not responsive.

(a) In order to assure the timely award of the contract, the as-read low bidder shall submit a Disadvantaged Business Utilization Plan on Department form SBE 2026 within seven (7) working days after the date of letting. To meet the seven (7) day requirement, the bidder may send the Plan by certified mail or delivery service within the seven (7) working day period. If a question arises concerning the mailing date of a Plan, the mailing date will be established by the U.S. Postal Service postmark on the original certified mail receipt from the U.S. Postal Service or the receipt issued by a delivery service. responsibility of the bidder to ensure that the postmark or receipt date is affixed within the seven (7) working days if the bidder intends to rely upon mailing or delivery to satisfy the submission day requirement. The Plan is to be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). It is the responsibility of the bidder to obtain confirmation of telefax delivery. The Department will not accept a Utilization Plan if it does not meet the seven (7) day submittal requirement and the bid will be declared not responsive. In the event the bid is declared not responsive due to a failure to submit a Plan or failure to comply with the bidding procedures set forth herein, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty, and may deny authorization to bid the project if re-advertised for bids. The Department reserves the right to invite any other bidder to submit a Utilization Plan at any time for award consideration or to extend the time for award.

- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. The signatures on these forms must be original signatures. All elements of information indicated on the said form shall be provided, including but not limited to the following:
 - (1) The name and address of each DBE to be used;
 - (2) A description, including pay item numbers, of the commercially useful work to be done by each DBE;
 - (3) The price to be paid to each DBE for the identified work specifically stating the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
 - (4) A commitment statement signed by the bidder and each DBE evidencing availability and intent to perform commercially useful work on the project; and
 - (5) If the bidder is a joint venture comprised of DBE firms and non-DBE firms, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s).
- (d) The contract will not be awarded until the Utilization Plan submitted by the bidder is approved. The Utilization Plan will be approved by the Department if the Plan commits sufficient commercially useful DBE work performance to meet the contract goal. The Utilization Plan will not be approved by the Department if the Plan does not commit sufficient DBE performance to meet the contract goal unless the bidder documents that it made a good faith effort to meet the goal. The good faith procedures of Section VIII of this special provision apply. If the Utilization Plan is not approved because it is deficient in a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no less than a five (5) working day period in order to cure the deficiency.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments

made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100% goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE firm does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100% goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100% goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE firm does not count toward the DBE goal.
- (d) DBE as a trucker: 100% goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contact. Credit will be given for the full value of all such DBE trucks operated using DBE employed drivers. Goal credit will be limited to the value of the reasonable fee or commission received by the DBE if trucks are leased from a non-DBE company.
- (e) DBE as a material supplier:
 - (1) 60% goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
 - (2) 100% goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
 - (3) 100% credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

GOOD FAITH EFFORT PROCEDURES. If the bidder cannot obtain sufficient DBE commitments to meet the contract goal, the bidder must document in the Utilization Plan the good faith efforts made in the attempt to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary

and reasonable steps are those which could reasonably be expected to obtain sufficient DBE participation. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere *pro forma* efforts are not good faith efforts; rather, the bidder is expected to have taken those efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- (a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.
 - (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
 - (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
 - (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
 - (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
 - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a bidder to perform the work of a contract with its own

organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.

- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that a good faith effort has not been made, the Department will notify the bidder of that preliminary determination by contacting the responsible company official designated in the Utilization Plan. The preliminary determination shall include a statement of reasons why good faith efforts have not been found, and may include additional good faith efforts that the bidder could take. The notification will designate a five (5) working day period during which the bidder shall take additional efforts. The bidder is not limited by a statement of additional efforts, but may take other action beyond any stated additional efforts in order to obtain additional DBE commitments. The bidder shall submit an amended Utilization Plan if additional DBE commitments to meet the contract goal are secured. If additional DBE commitments sufficient to meet the contract goal are not secured, the bidder shall report the final good faith efforts made in the time allotted. All additional efforts taken by the bidder will be considered as part of the bidder's good faith efforts. If the bidder is not able to meet the goal after taking additional efforts, the Department will make a pre-final determination of the good faith efforts of the bidder and will notify the designated responsible company official of the reasons for an adverse determination.
 - (c) The bidder may request administrative reconsideration of a pre-final determination adverse to the bidder within the five (5) working days after the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen

Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The pre-final determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issue of whether an adequate good faith effort was made to meet the contract goal. In addition, the request shall be considered a consent by the bidder to The request will be forwarded to the Department's extend the time for award. Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten (10) working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.

- (a) No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. If a DBE listed in the Utilization Plan is terminated for reasons other than convenience, or fails to complete its work on the contract for any reason, the Contractor shall make good faith efforts to find another DBE to substitute for the terminated DBE. The good faith efforts shall be

directed at finding another DBE to perform at least the same amount of work under the contract as the DBE that was terminated, but only to the extent needed to meet the contract goal or the amended contract goal. The Contractor shall notify the Bureau of Small Business Enterprises of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Bureau and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Bureau will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.

- (c) The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefor to the DBE by the Contractor, but not later than thirty (30) calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Report on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the Report shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Plan, the Department will deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages.
- (d) The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (e) Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

EPOXY COATING ON REINFORCEMENT (BDE)

Effective: April 1, 1997 Revised: January 1, 2003

For work outside the limits of bridge approach pavement, all references to epoxy coating in the Highway Standards and Standard Specifications for reinforcement, tie bars and chair supports will not apply for pavement, shoulders, curb, gutter, combination curb and gutter and median.

EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)

Effective: August 1, 2001 Revised: November 1, 2001

When the Engineer is notified or determines an erosion and/or sediment control deficiency(s) exists, he/she will direct the Contractor in writing to correct the deficiency. The Contractor shall then correct the deficiency within 24 hours. The deficiency may be any lack of repair, maintenance, or implementation of erosion and/or sediment control devices included in the contract, or any failure to comply with the conditions of the National Pollutant Discharge Elimination System (NPDES) Storm Water Permit for Construction Site Activities.

If the Contractor fails to correct the deficiency(s) within 24 hours, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency exists. The time period will begin with the initial written notification to the Contractor and end with the Engineer's acceptance of the corrected work. The per calendar day deduction will be either \$1000.00 or 0.05 percent of the awarded contract value, whichever is greater.

If the Contractor fails to respond, the Engineer may correct the deficiencies and deduct the cost from monies due or which may become due the Contractor. This corrective action shall in no way relieve the Contractor of his/her contractual requirements or responsibilities.

EXPANSION JOINTS (BDE)

Effective: August 1, 2003

Add the following paragraph after the second paragraph of Article 420.10(e) of the Standard Specifications:

"After the dowel bars are oiled, plastic expansion caps shall be secured to the bars maintaining a minimum expansion gap of 50 mm (2 in.) between the end of the bar and the end of the cap. The caps shall fit snuggly on the bar and the closed end shall be watertight. For expansion joints formed using dowel bar basket assemblies, the caps shall be installed on the alternating free ends of the bars. For expansion joints formed using a construction header, the caps shall be installed on the exposed end of each bar once the header has been removed and the joint filler material has been installed."

FLAGGER VESTS (BDE)

Effective: April 1, 2003 Revised: January 1, 2006

Revise the first sentence of Article 701.04(c)(1) of the Standard Specifications to read:

"The flagger shall be stationed to the satisfaction of the Engineer and be equipped with a fluorescent orange, fluorescent yellow/green or a combination of fluorescent orange and fluorescent yellow/green vest meeting the requirements of the American National Standards Institute specification ANSI/ISEA 107-2004 for Conspicuity Class 2 garments and approved flagger traffic control signs conforming to Standard 702001 and Article 702.05(e)."

Revise Article 701.04(c)(6) of the Standard Specifications to read:

"(6) Nighttime Flagging. Flaggers shall be illuminated by an overhead light source providing a minimum vertical illuminance of 108 lux (10 fc) measured 300 mm (1 ft) out from the flagger's chest. The bottom of any luminaire shall be a minimum of 3 m (10 ft) above the pavement. Luminaire(s) shall be shielded to minimize glare to approaching traffic and trespass light to adjoining properties.

The flagger vest shall be a fluorescent orange or fluorescent orange and fluorescent yellow/green vest meeting the requirements of the American National Standards Institute specification ANSI/ISEA 107-1999 for Conspicuity Class 3 garments."

FREEZE-THAW RATING (BDE)

Effective: November 1, 2002

Revise the first sentence of Article 1004.02(f) of the Standard Specifications to read:

"When coarse aggregate is used to produce portland cement concrete for base course, base course widening, pavement, driveway pavement, sidewalk, shoulders, curb, gutter, combination curb and gutter, median, paved ditch or their repair using concrete, the gradation permitted will be determined from the results of the Department's Freeze-Thaw Test."

HAND VIBRATOR (BDE)

Effective: November 1, 2003

Add the following paragraph to Article 1103.17(a) of the Standard Specifications:

"The vibrator shall have a non-metallic head for areas containing epoxy coated reinforcement. The head shall be coated by the manufacturer. The hardness of the non-metallic head shall be less than the epoxy coated reinforcement, resulting in no damage to the epoxy coating. Slip-on covers will not be allowed."

LIGHT EMITTING DIODE (LED) PEDESTRIAN SIGNAL HEAD (BDE)

Effective: November 1, 2005 | Revised: April 1, 2006

Add the following paragraph to the end of Article 802.03 of the Standard Specifications:

"The warranty for light emitting diode (LED) modules, including the maintained minimum luminous intensities, shall cover a minimum of 60 months from the date of delivery."

Revise Article 881.01 of the Standard Specifications to read:

"881.01 Description. This work shall consist of furnishing and installing a conventional pedestrian signal head or light emitting diode (LED) pedestrian signal head."

Revise Article 881.02(a) of the Standard Specifications to read:

"(a) Pedestrian Signal Heads......1078.02"

Revise the first paragraph of Article 881.04 of the Standard Specifications to read:

"881.04 Basis of Payment. This work will be paid for at the contract unit price each for PEDESTRIAN SIGNAL HEAD or PEDESTRIAN SIGNAL HEAD, LED of the type specified and of the material type when specified."

Revise Article 1078.02(b) of the Standard Specifications to read:

- "(b) Optical Unit. Only symbolic walk (walking person) and don't walk (upraised palm) indications shall be used.
 - (1) Conventional Pedestrian Signal. Each signal section shall have an optical unit according to Article 1078.01(c), except the lamp for a 300 mm (12 in.) section shall be nominal 90 W, 1040 lumens with a minimum average rated life of 8,000 hours (0.91 years) and the lamp for a 225 mm (9 in.) section shall be nominal 54 W, 530 lumens with a minimum average rated life of 8,000 hours (0.91 years).
 - (2) LED Pedestrian Signal. The pedestrian LED signal heads shall meet the requirements of the Institute of Transportation Engineers (ITE) LED purchase specification, "Pedestrian Traffic Control Signal Indications - Part 2: LED Pedestrian Traffic Signal Modules", or applicable successor ITE specifications, except as modified herein. The LEDs utilized in the modules shall not be Aluminum Gallium Arsenide (AlGaAs) material technology. The LED signal heads shall also meet the following requirements:
 - a. Physical and Mechanical Requirements. The power supply for the LED module shall be integrated with the unit.

- Photometric Requirements. The illuminated portion of the module shall be uniformly and completely dispersed with the LEDs.
- c. Electrical Requirements. The pedestrian LED signal module shall be EPA Energy Star qualified.

The individual LEDs shall be wired such that a catastrophic loss or the failure of one LED will result in the loss of not more than five percent of the signal module light output.

d. Warranty. The LED modules shall be warrantied according to Article 802.03."

LIGHT EMITTING DIODE (LED) SIGNAL HEAD (BDE)

Effective: April 1, 2002 Revised: November 1, 2005

Add the following paragraph to the end of Article 802.03 of the Standard Specifications:

"The warranty for light emitting diode (LED) modules, including the maintained minimum luminous intensities, shall cover a minimum of 60 months from the date of delivery."

Revise Article 880.01 of the Standard Specifications to read:

"880.01 Description. This work shall consist of furnishing and installing a conventional signal head, optically programmed signal head or light emitting diode (LED) signal head."

Revise Article 880.02(a) of the Standard Specifications to read:

"(a) Signal Heads......1078.01"

Revise the first sentence of the first paragraph of Article 880.03 of the Standard Specifications to read:

"The signal head shall be installed on a post, bracket, span wire or mast arm as shown on the plans."

Revise the first paragraph of Article 880.04 of the Standard Specifications to read:

"880.04 Basis of Payment. This work will be paid for at the contract unit price each for SIGNAL HEAD, OPTICALLY PROGRAMMED SIGNAL HEAD, or SIGNAL HEAD, LED of the type specified and of the material type when specified."

Revise Article 1078.01 of the Standard Specifications to read:

"1078.01 Signal Head, Optically Programmed Signal Head and Light Emitting Diode (LED) Signal Head."

Add the following to Article 1078.01(c) of the Standard Specifications:

- "(3) The LED signal section shall be according to the following:
 - a. General Requirements. The LED signal head shall meet the requirements of the Institute of Transportation Engineers (ITE) LED purchase specification, "Vehicle Traffic Control Signal Heads, Part 2: LED Vehicle Traffic Signal Modules", and "Vehicle Traffic Control Signal Heads, Part 3: LED Vehicle Arrow Traffic Signal Modules", or applicable successor ITE specifications, except as modified herein. The LEDs utilized in the modules shall not be Aluminum Gallium Arsenide (AIGaAs) material technology.

- b. Physical and Mechanical Requirements. The power supply for the LED module shall be integrated with the unit.
- c. Photometric Requirements. The candlepower values for yellow 300 mm (12 in.) circular modules shall be equal to the corresponding values for green 300 mm (12 in.) circular modules as listed in Table 1 of Section 4 of the aforementioned ITE specification based on normal use in traffic signal operation over the operating temperature range.

The illuminated portion of the arrow module shall be uniformly and completely dispersed with the LEDs.

d. Electrical Requirements. When applicable to the particular module type, the LED signal module shall be EPA Energy Star qualified. For yellow 300 mm (12 in.) circular and arrow modules, the wattage requirements shall be as follows:

Module Type	Maximum Watts (W) at 74 °C (165 °F)	Nominal Watts (W) at 25 °C (77 °F)
300 mm (12 in.) Yellow Circular	25	22
300 mm (12 in.) Yellow Arrow	12	10

The individual LEDs shall be wired such that a catastrophic loss or the failure of one LED will result in the loss of not more than five percent of the signal module light output.

e. Warranty. The LED modules shall be warrantied according to Article 802.03."

MULCHING SEEDED AREAS (BDE)

Effective: January 1, 2005

Delete Article 251.02(a) of the Standard Specifications.

Add the following to Article 251.02 of the Standard Specifications:

Delete Article 251.03(b)(1) of the Standard Specifications.

Add the following to Article 251.03 of the Standard Specifications:

"(d) Method 4. This method shall consist of applying compost combined with a performance additive designed to bind/stabilize the compost. The compost/performance additive mixture shall be applied to the surface of the slope using a pneumatic blower at a depth of 50 mm (2 in.)."

Revise the first sentence of the first paragraph of Article 251.06(b) of the Standard Specifications to read:

"Mulch Methods 1, 2, 3, and 4 will be measured for payment in hectares (acres) of surface area mulched."

Revise Article 251.07 of the Standard Specifications to read:

"251.07 Basis of Payment. This work will be paid for at the contract unit price per hectare (acre) for MULCH, METHOD 1; MULCH, METHOD 2; MULCH, METHOD 3; or MULCH, METHOD 4; and at the contract unit price per square meter (square yard) for EROSION CONTROL BLANKET or HEAVY DUTY EROSION CONTROL BLANKET."

Add the following after the second paragraph of Article 1081.05(b) of the Standard Specifications:

"Chemical Compost Binder. Chemical compost binder shall be a commercially available product specifically recommended by the manufacturer for use as a compost stabilizer.

The compost binder shall be nonstaining and nontoxic to vegetation and the environment. It shall disperse evenly and rapidly and remain in suspension when agitated in water.

Prior to use of the compost binder, the Contractor shall submit a notarized certification by the manufacturer stating that it meets these requirements. Chemical compost binder shall be packaged, stored, and shipped according to the manufacturer's recommendations with the net quantity plainly shown on each package or container."

MULTILANE PAVEMENT PATCHING (BDE)

Effective: November 1, 2002

Pavement broken and holes opened for patching shall be completed prior to weekend or holiday periods. Should delays of any type or for any reason prevent the completion of the work, temporary patches shall be constructed. Material able to support the average daily traffic and meeting the approval of the Engineer shall be used for the temporary patches. The cost of furnishing, placing, maintaining, removing and disposing of the temporary work, including traffic control, shall be the responsibility of the Contractor.

PARTIAL PAYMENTS (BDE)

Effective: September 1, 2003

Revise Article 109.07 of the Standard Specifications to read:

"109.07 Partial Payments. Partial payments will be made as follows:

(a) Progress Payments. At least once each month, the Engineer will make a written estimate of the amount of work performed in accordance with the contract, and the value thereof at the contract unit prices. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1000.00 will be approved for payment other than the final payment.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved. Furthermore, progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c).

(b) Material Allowances. At the discretion of the Department, payment may be made for materials, prior to their use in the work, when satisfactory evidence is presented by the Contractor. Satisfactory evidence includes justification for the allowance (to expedite the work, meet project schedules, regional or national material shortages, etc.), documentation of material and transportation costs, and evidence that such material is properly stored on the project or at a secure location acceptable and accessible to the Department.

Material allowances will be considered only for nonperishable materials when the cost, including transportation, exceeds \$10,000 and such materials are not expected to be utilized within 60 days of the request for the allowance. For contracts valued under \$500,000, the minimum \$10,000 requirement may be met by combining the principal (material) product of no more than two contract items. An exception to this two item limitation may be considered for any contract regardless of value for items in which material (products) are similar except for type and/or size.

Material allowances shall not exceed the value of the contract items in which used and shall not include the cost of installation or related markups. Amounts paid by the Department for material allowances will be deducted from estimates due the Contractor as the material is used. Two-sided copies of the Contractor's cancelled checks for materials and transportation must be furnished to the Department within 60 days of payment of the allowances or the amounts will be reclaimed by the Department."

PAVEMENT THICKNESS DETERMINATION FOR PAYMENT (BDE)

Effective: April 1, 1999 Revised: January 1, 2004

Description. This work shall consist of determining pavement thickness for payment for full depth bituminous concrete and all pcc pavements. Pavement pay items that individually contain at least 840 sq m (1000 sq yd) of contiguous pavement will be subject to this Special Provision with the following exclusions: temporary pavements; variable width pavement; radius returns and side streets less than 125 m (400 ft) in length; and turn lanes of constant width less than 125 m (400 ft) in length. The areas of pavement excluded from the pay adjustment as described in this Special Provision will be cored according to Article 407.10 of the Standard Specifications. Temporary pavements are defined as pavements constructed and removed under this contract.

<u>Materials</u>. Rapid set materials shall be obtained from the Department's approved list of Packaged, Dry, Rapid Hardening Cementitous Materials For Concrete Repairs. Coarse aggregate may be added to the mortar if allowed by the manufacturer's instructions on the package. Mixing shall be according to the manufacture's recommendations.

Equipment. Cores shall be taken utilizing an approved coring machine. The cores shall have a diameter of 50 mm (2 in.). The cores shall be measured utilizing an approved measuring device.

CONSTRUCTION REQUIREMENTS

<u>Tolerance in Thickness</u>. Determination of the pavement thickness shall be performed after the pavement surface tests and all corrective grinding are complete according to Article 407.09 of the Standard Specifications. Adjustments made in the contract unit price for pavement thickness will be in addition to and independent of those made for the Profile Index.

The pavement will be divided into approximately equal lots of not more than 1500 m (5000 ft) in length. When the length of a continuous strip of pavement is less than 1500 m (5000 ft), these short lengths of pavement, ramps, turn lanes, and other short sections of continuous pavement shall be grouped together to form lots of approximately 1500 m (5000 ft) in length. Short segments between structures will be measured continuously with the structure segments omitted. Each lot will be subdivided into ten equal sublots. The width of a sublot and lot will be the width from the pavement edge to the adjacent lane line, from one lane line to the next, or between pavement edges for single-lane pavements.

Fifty millimeter (Two inch) cores shall be taken from the pavement by the Contractor at random locations selected by the Engineer. When computing the thickness of a lot, one core will be taken per sublot. Core locations will be specified by the Engineer prior to beginning the coring operations.

The Contractor and the Engineer shall witness the coring operations, the measurement, and recording of the cores. Core measurements will be determined immediately upon removal from

the core bit and prior to moving to the next core location. Upon concurrence of the length, the core samples may be discarded.

<u>Patching Holes</u>. Upon completion of coring, all core holes shall be filled with a rapid set mortar or concrete. Only enough water to permit placement and consolidation by rodding shall be used, and the material shall be struck-off flush with the adjacent pavement.

For a rapid set mortar mixture, one part packaged rapid set cement shall be combined with two parts fine aggregate, by volume; or a packaged rapid set mortar shall be used. For a rapid set concrete mixture, a packaged rapid set mortar shall be combined with coarse aggregate according to the manufacturer's instructions or a packaged rapid set concrete shall be used. Mixing of a rapid set mortar or concrete shall be according to the manufacturer's instructions.

Deficient Sublot. When the thickness of the core in a sublot is deficient by more than ten percent of plan thickness, the Contractor will have the option of taking three additional cores selected at random by the Engineer within the same sublot at the Contractor's expense. The thickness of the additional three cores will be averaged with the original core thickness. When the average thickness shows the sublot to be deficient by ten percent or less, no additional action is necessary. If the Contractor chooses not to take additional cores, the pavement in the sublot shall be removed and replaced at the Contractor's expense. When additional cores are taken and the average thickness of the additional cores show the sublot to be deficient by more than ten percent, the pavement in that sublot shall be removed and replaced at the Contractor's expense. When requested in writing by the Contractor, the Engineer, at his/her option, may permit in writing such thin pavement to remain in place. For Bituminous Concrete Pavement (Full Depth) allowed to remain in place, additional lift(s) may be placed, at the Contractor's expense, to bring the deficient pavement to plan thickness when the Engineer determines grade control conditions will permit such lift(s). The material thickness(es), areas to be overlaid, and method of placement used for additional lift(s) will be approved by the Engineer. When the thin pavement is removed and replaced or additional lifts are placed, the replacement pavement will be retested for thickness at the Contractor's expense. When the thin pavement is left in place and no additional lift(s) are placed, no payment will be made for the deficient pavement sublot. The thickness of the original core taken in the sublot will be used in determining the payment for the entire lot and no adjustment to the pay factor will be made for any corrective action taken.

Deficient Lot. After analyzing the cores, the Percent Within Limits will be calculated. A lot of pavement represented by the Percent Within Limits (PWL) of 60 percent or less, shall be removed and replaced at the Contractor's expense. When requested in writing by the Contractor, the Engineer, at his/her option, may permit in writing such pavement to remain in place. For Bituminous Concrete Pavement (Full Depth), allowed to remain in place, additional lift(s) may be placed, at the Contractor's expense, to bring the deficient pavement to plan thickness when the Engineer determines grade control conditions will permit such lift(s). The material, thickness(es), areas to be overlaid and method of placement used for the additional lift(s) will be approved by the Engineer. After either corrective action, the Contractor shall core the lot according to the "Coring Procedures" at no additional cost to the Department. The PWL will then be recalculated for the lot, however, the pay factor for the lot will be a maximum of 100 percent. When requested in writing by the Contractor, the Engineer, at his/her option, may

permit in writing, the lot to remain in place. When the lot is left in place and no additional lifts are placed the pay factor for the lot will be based on the calculated PWL.

Right of Discovery. When the Engineer has reason to believe the random core selection process will not accurately represent the true conditions of the work, he/she may order cores in addition to those specified. The additional cores shall be taken at specific locations determined by the Engineer. The Engineer will provide notice to the Contractor containing an explanation of the reasons for his/her action. These additional cores and locations will be determined prior to commencement of coring operations. When the additional cores show the pavement to be deficient by more than ten percent, additional cores shall be taken at locations determined by the Engineer to determine the limits of the deficient pavement area. The deficient pavement area will be defined as the area between two acceptable cores. An acceptable core is a core with a thickness of 90 percent or more of plan thickness. The defined pavement area shall be removed and replaced at the Contractor's expense. When requested by the Contractor, the Engineer, at his/her option, may permit in writing such thin pavement to remain in place. On Bituminous Concrete Pavement (Full Depth) allowed to remain in place, additional lift(s) may be placed to bring the deficient pavement to plan thickness when the Engineer determines that grade control conditions will permit such lift(s). The material, thickness(es), areas to be overlaid and method of placement for the additional lift(s) will be approved by the Engineer. When the thin pavement is removed and replaced or additional lifts are placed, the replacement pavement will be retested for thickness at the Contractor's expense. When the thin pavement is left in place and no additional lift(s) are placed, no payment will be made for the deficient pavement. When the additional cores show the pavement to be deficient by ten percent or less the additional cores will be paid for according to Article 109.04. When the additional cores show the pavement to be deficient by more than ten percent the additional cores taken in the deficient area shall be at the Contractor's expense.

<u>Profile Index Adjustment</u>. After any section of pavement is removed and replaced or any additional lifts are added, the corrected areas shall be tested for pavement smoothness and any necessary Profile Index adjustments and/or corrections will be made based on these final profile readings. Such surface testing shall be performed at the Contractor's expense.

Core Analysis. Cores will be analyzed according to the following:

(a) Definition:

x_i = Individual values (core lengths) under consideration

n = Number of individual values under consideration (10 per lot)

 \bar{x} = Average of the values under consideration

LSL = Lower Specification Limit (LSL = 0.98 plan thickness for pavement)

Q_L = Lower Quality Index

S = Sample Standard Deviation

PWL = Percent Within Limits

Determine \bar{x} for the lot to the nearest two decimal places.

Compute the sample standard deviation to the nearest three decimal places using:

$$S = \sqrt{\frac{\sum (x_i - \overline{x})^2}{n - 1}} \quad \text{where} \quad \Sigma (x_i - \overline{x})^2 = (x_1 - \overline{x})^2 + (x_2 - \overline{x})^2 + \dots + (x_{10} - \overline{x})^2$$

Determine the Lower Quality Index to the nearest two decimal places using:

$$Q_{L} = \frac{\left(\bar{x} - LSL\right)}{S}$$

Determine the percentage that will fall above the Lower Specification Limit (LSL) by going to the attached Table and utilizing calculated Q_L . Read the appropriate PWL value from the Table. For Q_L values less than zero the value shown in the table must be subtracted from 100 to obtain PWL.

Pay Adjustment. The following pay adjustment equation will be used to determine (to the nearest two decimal places) the pay factor for each lot.

Pay Factor (PF) in percent = 55 + 0.5 (PWL)

If \bar{x} for a lot is less than the plan thickness, the maximum pay factor for that lot will be 100 percent.

<u>Total Payment</u>. The payment will be based on the appropriate pay items in Sections 407, 420, and 421. The final payment will be adjusted according to the following equation:

Total Payment = TPF[CUP (TOTPAVT - DEFPAVT)]

TPF = Total Pay Factor

CUP = Contract Unit Price

TOTPAVT = Area of Pavement Subject to Coring

DEFPAVT = Area of Deficient Pavement

The TPF for the entire pavement will be the average of the PF for all the lots, however, not more than 102 percent of plan quantity will be paid.

Deficient pavement is defined as an area of pavement represented by a sublot deficient by more than 10 percent which is left in place with no additional thickness added.

All work involved in determining the total payment will be included in the contract unit prices of the pay items involved.

																	_														
Percent in Limits	(PWL)	8 8 8 8 8 8 2 2 2	39.92	88 88 8 84 9	3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	99.95	96.96	99.98	99.97	99:38	86.98	8 8	86.96	83 83 84		98.98			100.00		•										
Quality Index	* (Ö)	4444 444	2.44	2,45	2.47	2.49	2.50	2.51	2.53	2.54	2.55	2.30	2.58	2.59	2.60	2.62	2.63	7.04 	> 2.65												
Percent in Limits	(PWL)	98.83 98.88 98.92 98.97	99.01	99.06 99.10	99.14	99.22	99.26	99.29	99.32	99.39	99.42	99. G	99.50	99.53	99.56	99.58	99.63 89.63	96.98 96.98	99.68	99.70	99.73	99.75	99.77	20.00	99.81	28.66 	99.84	99.80	99.87	99.88	
Quality	* (g)	2 2 2 2 2 2 2 2 3 2 2 2 3	2.04	2 2 05 2 06 2 06	2.07	2.03	2,10	2.11	2.12	2.14	2.15	2.16	2.18	2.19	2.20	2.21	2.23	2.22	2.25	2.26	2.28	2.29	2.30	2.31	2.3	2.34	2.35	2.36	2.5	2.39	
<u>-</u>		95.46 95.70 95.81	95.93	96.05 96.16	96.27	96.48	96.59	96.69	96.78	96.97	70.76	97.16	97.33	97.42	97.51	97.59	97.75	97.83	97.91	97.98	88.7	98.18	98.25	98,31	98.4	98,50	98.56	98.61	98.57	98.78	
	, (g)	8.2.6.8	1.64	1.65	1.67	. 6. 8. 6.	1 70	1.7	2.7	1.74	1.75	1.76	1.78	1.79	1.80	£ 6	8.	1.84	.8 .8	1.86	. 8	1.89	8:1	1.9	193	1.94	1.95	1.96	1.97	1.99	
Fi Wife	(PWIL)	88.97 89.17 89.38	89.58	89.79 89.99	90.19	86.09 86.09	8	8.6	요 5.6	9 9 52.52	91.70	91.87	25.05 42.02	92.39	92.56	92.72	33.58	93.21	93,37	93,52	7.88	93.98	94.13	94.27	26 A	94.68	94.82	94.95	95.08 5.08	95.33 95.33	_
_ >	*(0)	8222	1.24	1.25	1.27	2. 1.26 1.26	5		23.3	. .	56.	8	1.37	8.6	1.40	4.1	¥. £.	4.1	1.45	1.46	7.4. A. 4.	64.	05.	<u>7.</u>	52. 52	<u> 4</u>	35,	1.56	1.57	S &	
<u>=</u>	(PWL)	78.43 78.72 79.02	79.61	79.90	80.47	80.76 81.04	5	2 2 2 2	88.88	82.16 82.43	82.71	82.97	83.24	88.7	84.03	84.28	2 2 2 5	85.04	85.29	85.53	85.77	86.26	86.50	86.73	86.96 2.36	87.43	87.66	87.88	88.10	8 8	obtain PWI
_	*(O)	0.80	0.84	0.85	0.87	0.88		0.00	0.92	0.93	0.95	96.0	76.0	08.0 08.0	5	10.	1.02	40.	, T	9.1	1.07	8.8	ć		1.12	1.13	1.15	1.16	1.17	<u>5</u> 5	le from 100 fc
f in	(PWIL)	65.07 65.43 65.79	66.51	66.87	67.57	67.93	-	98.63 68.63	69.32	69.67 70.01	70.36	2.6	71.04	71.38	30 02	72.39	72.72	73.39	C7. C7.	74.04	74.36	75.01	75 23	75.64	75.96	76.27	76.00	77.21	77.51	77.82	fo table val
	xepul (a)**	0.42	2.0 4.0	0.45	0.40	0.48	! ;	0.00 0.00 0.00	0.52	0.53	- L	 6 6 6 6	0.57	0.58	8	0.61	0.62	9.0	100	8 8	0.67	0.00	, F	0.72	0.72	0.73	, <u>1</u>	0.75	0.77	0.78	0.39 64.71 0.78 6.12 0.39 0.39 0.47 0.48 0
	Limits (PWL) (50.03 50.38	51.15 51.54	51.92	22,23	53.07	}	8. 2 2. 2 2. 2	¥ ¥ 4 8	54.99		8 8 6 8 6 8	56.51	26.83 27.83 27.23	į (28.93 29.93	58.40	26.75 50.15	i	දු දැ	60.28	8 8 8 8		<u>2</u> €	62.14	25.55 25.55	3 6	83.63	83.88	8 8 8 8	24.7
	L C)*	0.00	0.03 40.04	0.05	0.06	80.0	3	0.10	0.12	0.13	5 6	0.15	0.17	0.18	<u> </u>	0.20	0.22	0.23		0.25	0.27	0.28	3	0.30	0.32	0.33	5	0.30	0.37	0.38	- SC 0
_			_																												

PAYMENTS TO SUBCONTRACTORS (BDE)

Effective: June 1, 2000 Revised: January 1, 2006

Federal regulations found at 49 CFR §26.29 mandate the Department to establish a contract clause to require Contractors to pay subcontractors for satisfactory performance of their subcontracts and to set the time for such payments.

State law also addresses the timing of payments to be made to subcontractors and material suppliers. Section 7 of the Prompt Payment Act, 30 ILCS 540/7, requires that when a Contractor receives any payment from the Department, the Contractor shall make corresponding, proportional payments to each subcontractor and material supplier performing work or supplying material within 15 calendar days after receipt of the Department payment. Section 7 of the Act further provides that interest in the amount of two percent per month, in addition to the payment due, shall be paid to any subcontractor or material supplier by the Contractor if the payment required by the Act is withheld or delayed without reasonable cause. The Act also provides that the time for payment required and the calculation of any interest due applies to transactions between subcontractors and lower-tier subcontractors and material suppliers throughout the contracting chain.

This Special Provision establishes the required federal contract clause, and adopts the 15 calendar day requirement of the State Prompt Payment Act for purposes of compliance with the federal regulation regarding payments to subcontractors. This contract is subject to the following payment obligations.

When progress payments are made to the Contractor according to Article 109.07 of the Standard Specifications, the Contractor shall make a corresponding payment to each subcontractor and material supplier in proportion to the work satisfactorily completed by each subcontractor and for the material supplied to perform any work of the contract. The proportionate amount of partial payment due to each subcontractor and material supplier throughout the contracting chain shall be determined by the quantities measured or otherwise determined as eligible for payment by the Department and included in the progress payment to the Contractor. Subcontractors and material suppliers shall be paid by the Contractor within 15 calendar days after the receipt of payment from the Department. The Contractor shall not hold retainage from the subcontractors. These obligations shall also apply to any payments made by subcontractors and material suppliers to their subcontractors and material suppliers; and to all payments made to lower tier subcontractors and material suppliers throughout the contracting chain. Any payment or portion of a payment subject to this provision may only be withheld from the subcontractor or material supplier to whom it is due for reasonable cause.

This Special Provision does not create any rights in favor of any subcontractor or material supplier against the State or authorize any cause of action against the State on account of any payment, nonpayment, delayed payment, or interest claimed by application of the State Prompt Payment Act. The Department will not approve any delay or postponement of the 15 day requirement except for reasonable cause shown after notice and hearing pursuant to Section

7(b) of the State Prompt Payment Act. State law creates other and additional remedies available to any subcontractor or material supplier, regardless of tier, who has not been paid for work properly performed or material furnished. These remedies are a lien against public funds set forth in Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c), and a recovery on the Contractor's payment bond according to the Public Construction Bond Act, 30 ILCS 550.

PAYROLLS AND PAYROLL RECORDS (BDE)

Effective: August 10, 2005

<u>FEDERAL AID CONTRACTS</u>. Add the following State of Illinois requirements to the Federal requirements contained in Section V of Form FHWA-1273:

"The payroll records shall include each worker's name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid.

The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form."

STATE CONTRACTS. Revise Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

"IV. COMPLIANCE WITH THE PREVAILING WAGE ACT

- 1. Prevailing Wages. All wages paid by the Contractor and each subcontractor shall be in compliance with The Prevailing Wage Act (820 ILCS 130), as amended, except where a prevailing wage violates a federal law, order, or ruling, the rate conforming to the federal law, order, or ruling shall govern. The Contractor shall be responsible to notify each subcontractor of the wage rates set forth in this contract and any revisions thereto. If the Department of Labor revises the wage rates, the Contractor will not be allowed additional compensation on account of said revisions.
- 2. Payroll Records. The Contractor and each subcontractor shall make and keep, for a period of three years from the date of completion of this contract, records of the wages paid to his/her workers. The payroll records shall include each worker's name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid. Upon two business days' notice, these records shall be available, at all reasonable hours at a location within the State, for inspection by the Department or the Department of Labor.
- 3. Submission of Payroll Records. The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form.

Each submittal shall be accompanied by a statement signed by the Contractor or subcontractor which avers that: (i) such records are true and accurate; (ii) the hourly rate paid to each worker is not less than the general prevailing rate of hourly wages required by the Act; and (iii) the Contractor or subcontractor is aware that filing a payroll record that he/she knows to be false is a Class B misdemeanor.

4. Employee Interviews. The Contractor and each subcontractor shall permit his/her employees to be interviewed on the job, during working hours, by compliance investigators of the Department or the Department of Labor."

PERSONAL PROTECTIVE EQUIPMENT (BDE)

Effective: July 1, 2004

All personnel, excluding flaggers, working outside of a vehicle (car or truck) within 7.6 m (25 ft) of pavement open to traffic shall wear a fluorescent orange, fluorescent yellow/green or a combination of fluorescent orange and fluorescent yellow/.green vest meeting the requirements of the American National Standards Institute specification ANSI/ISEA 107-1999 for Conspicuity Class 2 garments. Other types of garments may be substituted for the vest as long as the garments have manufacturers tags identifying them as meeting the ANSI Class 2 requirement.

PORTLAND CEMENT (BDE)

Effective: January 1, 2005 Revised: November 1, 2005

Add the following paragraph after the last paragraph of Article 1001.01 of the Standard Specifications.

"For portland cement according to ASTM C 150, the bill of lading shall state if limestone has been added. The bill of lading shall also state that the limestone addition is not in excess of five percent by mass (weight) of the cement."

PORTLAND CEMENT CONCRETE (BDE)

Effective: November 1, 2002

Add the following paragraph after the fourth paragraph of Article 1103.01(b) of the Standard Specifications:

"The truck mixer shall be approved before use according to the Bureau of Materials and Physical Research's Policy Memorandum, "Approval of Concrete Plants and Delivery Trucks"."

Add the following paragraph after the first paragraph of Article 1103.01(c) of the Standard Specifications:

"The truck agitator shall be approved before use according to the Bureau of Materials and Physical Research's Policy Memorandum, "Approval of Concrete Plants and Delivery Trucks"."

Add the following paragraph after the first paragraph of Article 1103.01(d) of the Standard Specifications:

"The nonagitator truck shall be approved before use according to the Bureau of Materials and Physical Research's Policy Memorandum, "Approval of Concrete Plants and Delivery Trucks"."

Revise the first sentence of the first paragraph of Article 1103.02 of the Standard Specifications to read:

"The plant shall be approved before production begins according to the Bureau of Materials and Physical Research's Policy Memorandum, "Approval of Concrete Plants and Delivery Trucks"."

PORTLAND CEMENT CONCRETE PATCHING (BDE)

Effective: January 1, 2001 Revised: January 1, 2004

Revise Note 1 of Article 442.02 of the Standard Specifications, to read:

"Note 1. When patching ramp pavements and two lane pavements with two way traffic, Class PP-2, PP-3, or PP-4 concrete shall be used for Class A, Class B and Class C patching. For all other pavements, Class PP-1, PP-2, PP-3, or PP-4 concrete shall be used, at the Contractor's option, for Class A, Class B and Class C patching."

Delete Note 2 of Article 442.02 of the Standard Specifications.

Add the following to Article 442.02 of the Standard Specifications:

"(I) Calcium Chloride (Note 5)1013.01

Note 5. The calcium chloride accelerator, when permitted by the Department, shall be Type L (Liquid) with a minimum of 32.0 percent by mass (weight) of calcium chloride."

Revise the first paragraph of Article 442.06(e) of the Standard Specifications to read:

"(e) Concrete Placement. For Class A, Class B and Class C Patches, concrete shall be placed according to Article 420.07 and governed by the limitations set forth in Article 1020.14, except that the maximum temperature of the mixed concrete immediately before placing shall be 35 °C (96 °F), the required use of an approved retarding admixture when the plastic concrete reaches 30 °C (85 °F) shall not apply."

Revise the first paragraph of Article 442.06(h) of the Standard Specifications to read:

"(h) Curing and Protection. In addition to Article 1020.13, when the air temperature is less than 13 °C (55 °F), the Contractor shall cover the patch with minimum R12 insulation until opening strength is reached. Insulation is optional when the air temperature is 13 °C - 35 °C (55 °F - 96 °F). Insulation shall not be placed when the air temperature is greater than 35 °C (96 °F)."

Revise the second paragraph of Article 701.05(e)(1)d.1. of the Standard Specifications to read:

"No open holes, broken pavement, or partially filled holes shall remain overnight for bituminous patching or when the Department specifies only Class PP-2, PP-3, or PP-4 concrete be used. The only exception is conditions beyond the control of the Contractor."

Revise Article 701.05(e)(2)b. of the Standard Specifications to read:

"b. Strength Tests. For patches constructed with Class PP-1, PP-2, PP-3, or PP-4 concrete, the pavement may be opened to traffic when test specimens cured with the patches have obtained a minimum flexural strength of 4150 kPa (600 psi) or a minimum compressive strength of 22,100 kPa (3200 psi) according to Article 1020.09.

For patches constructed with Class PP-2, PP-3, or PP-4 concrete which can obtain a minimum flexural strength of 4150 kPa (600 psi) or a minimum of compressive strength of 22,100 kPa (3200 psi) in 16 hours, the pavement may be opened to traffic at a lower opening strength. The specimens cured with the patches shall have obtained a minimum flexural strength of 2050 kPa (300 psi) or a minimum compressive strength of 11,000 kPa (1600 psi) according to Article 1020.09, to permit opening pavement to traffic.

With the approval of the Engineer, concrete strength may be determined according to AASHTO T 276. The strength-maturity relationship shall be developed from concrete which has an air content near the upper specification limit. The strength-maturity relationship shall be re-established if the mix design or materials are changed."

Revise Article 701.05(e)(2)c. of the Standard Specifications to read:

"c. Construction Operations. For Class PP-2, PP-3, or PP-4 concrete used on ramp pavements and two lane pavements with two way traffic, or when the Department specifies only Class PP-2, PP-3, or PP-4 concrete be used for other pavements, Contractor construction operations shall be performed in a manner which allows the patches to be opened the same day and before nightfall. If patches are not opened before nightfall, the additional traffic control shall be at the Contractor's expense. Any time patches cannot be opened before nightfall, the Contractor shall change subsequent construction operations or the mix design. The changes shall be at no additional cost to the Department."

Revise Table 1 of Article 1020.04 of the Standard Specifications by replacing Class PP concrete with the following:

"TABLE	1. CLASSES OF PORT	LAND CEMENT	CONCRETE AND MIX DESIG	GN CRITERIA
Class of Concrete	Use	Specification Section Reference	Cement Factor kg/cu m (cwt/cu yd)	Max. Water/Cement Ratio kg/kg (lb/lb)
PP-1	PCC Pavement Patching Bridge Deck Patching	442	Type I Cement 385 to 445 (6.50 to 7.50) Type III Cement 365 to 425 (6.20 to 7.20)	0.44

PP-2	PCC Pavement Patching Bridge Deck Patching	442	Type I Cement 435 (7.35)	0,38
PP-3	PCC Pavement Patching Bridge Deck Patching	442	Type III Cement 435 (7.35)	0.35
PP-4	PCC Pavement Patching Bridge Deck Patching	442	Rapid Hardening Cement 355 to 370 (6.00 to 6.25)	0.50

For PP-1, the Contractor has the option to replace the Type I Cement with Class C fly ash or ground granulated blast-furnace slag. The amount of cement replaced shall not exceed 15 percent by mass (weight), at a minimum replacement ratio of 1.5:1.

For PP-2, the Contractor has the option to replace the Type I cement with ground granulated blast-furnace slag. The amount of cement replaced shall not exceed 30 percent by mass (weight), at a minimum replacement ratio of 1:1.

For PP-3, in addition to the cement, 60 kg/cu m (100 lb/cu yd) of ground granulated blast-furnace slag and 30 kg/cu m (50 lb/cu yd) of microsilica are required. For an air temperature greater than 30 °C (85 °F), the Contractor has the option to replace the Type III cement with Type I cement.

For PP-4, the cement shall be from the Department's "Approved List of Packaged, Dry, Rapid Hardening Cementitious Materials for Concrete Repairs".

TABLE 1.	TABLE 1. (CONT'D) CLASSES OF PORTLAND CEMENT CONCRETE AND MIX DESIGN CRITERIA					
Class of Concrete	Slump, mm (in.)	Mix Design Compressive Strength, kPa (psi) Hours 48	Mix Design Flexural Strength, kPa (psi) Hours 48	Air Content, %	Coarse Aggregate Gradations Permitted	
PP – 1	100 (4) Max	22,100 (3200)	4150 (600)	4.0 - 7.0	CA-7, CA-11, CA-13, CA14, or CA-16	
PP - 2	150 (6) Max	22,100 (3200)	4150 (600)	4.0 – 6.0	CA-7, CA-11, CA-13, CA14, or CA-16	
PP-3	100 (4) Max	22,100 (3200)	4150 (600)	4.0 – 6.0	CA-7, CA-11, CA-13, CA14, or CA-16	
PP 4	150 (6) Max	22,100 (3200)	4150 (600)	4.0 – 6.0	CA-7, CA-11, CA-13, CA14, or CA-16	

For PP-1, PP-2, PP-3 or PP-4; only CA-13, CA-14, or CA-16 may be used for bridge deck patching. In addition, the mix design strength at 48 hours shall be increased to 27,500 kPa (4,000 psi) compressive or 4,650 kPa (675 psi) flexural for bridge deck patching.

For PP-1, the slump may be increased to 150 mm (6 in.) Max if a high range water-reducing admixture is used."

Delete Article 1020.05(g) of the Standard Specifications.

PRECAST CONCRETE PRODUCTS (BDE)

Effective: July 1, 1999

Revised: November 1, 2004

<u>Product Approval</u>. Precast concrete products shall be produced according to the Department's current Policy Memorandum, "Quality Control/Quality Assurance Program for Precast Concrete Products". The Policy Memorandum applies to precast concrete products listed under the Products Key of the "Approved List of Certified Precast Concrete Producers".

<u>Precast Concrete Box Culverts</u>. Add the following sentence to the end of the fourth paragraph of Article 540.06:

"After installation, the interior and exterior joint gap between precast concrete box culvert sections shall not exceed 38 mm (1 1/2 in.)."

<u>Portland Cement Replacement</u>. For precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or ground granulated blast-furnace (GGBF) slag shall be governed by the AASHTO or ASTM standard specification referenced in the Standard Specifications.

For all other precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or GGBF slag shall be approved by the Engineer. Class F fly ash shall not exceed 15 percent by mass (weight) of the total portland cement and Class F fly ash. Class C fly ash shall not exceed 20 percent by mass (weight) of the total portland cement and Class C fly ash. GGBF slag shall not exceed 25 percent by mass (weight) of the total portland cement and GGBF slag.

Concrete mix designs, for precast concrete products, shall not consist of portland cement, fly ash and GGBF slag.

Ready-Mixed Concrete. Delete the last paragraph of Article 1020.11(a) of the Standard Specifications.

Shipping. When a precast concrete product has attained the specified strength, the earliest the product may be loaded, shipped, and used is on the fifth calendar day. The first calendar day shall be the date casting was completed.

Acceptance. Products which have been lot or piece inspected and approved by the Department prior to July 1, 1999, will be accepted for use on this contract.

419.doc

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)

Effective: November 1, 2002

Revise Article 503.02(c) of the Standard Specifications to read:

"(c) Preformed Expansion Joint Filler......1051"

Revise Article 637.02(d) of the Standard Specifications to read:

"(d) Preformed Expansion Joint Filler......1051"

Add the following Article to Section 1051 of the Standard Specifications:

"1051.10 Preformed Recycled Rubber Joint Filler. Preformed recycled rubber joint filler shall consist of ground tire rubber, free of steel and fabric, combined with ground scrap or waste polyethylene. It shall not have a strong hydrocarbon or rancid odor and shall meet the physical property requirements of ASTM D 1752. Water absorption by volume shall not exceed 5.0 percent."

PUBLIC CONVENIENCE AND SAFETY (BDE)

Effective: January 1, 2000

Add the following paragraph after the fourth paragraph of Article 107.09 of the Standard Specifications:

"On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical."

RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE)

Effective: January 1, 2000 Revised: April 1, 2002

Revise Article 1004.07 to read:

"1004.07 RAP Materials. RAP is reclaimed asphalt pavement resulting from cold milling or crushing of an existing dense graded hot-mix asphalt pavement. RAP must originate from routes or airfields under federal, state or local agency jurisdiction. The Contractor shall supply documentation that the RAP meets these requirements.

- (a) Stockpiles. The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. No additional RAP will be allowed on top of the pile after the pile has been sealed.
 - (1) Homogeneous. Homogeneous RAP stockpiles shall consist of RAP from Class I/ Superpave, or equivalent mixtures only and represent the same aggregate quality, but shall be at least C quality or better, the same type of crushed aggregate (either crushed natural aggregate, ACBF slag, or steel slag), similar gradation and similar AC content. If approved by the Engineer, combined single pass surface/binder millings may be considered "homogenous", with a quality rating dictated by the lowest coarse aggregate quality present in the mixture. Homogenous stockpiles shall meet the requirements of Article 1004.07(d). Homogeneous RAP stockpiles not meeting these requirements may be processed (crushing and screening) and retested.
 - (2) Conglomerate. Conglomerate RAP stockpiles shall consist of RAP from Class I/ Superpave, or equivalent mixtures only. The coarse aggregate in this RAP shall be crushed aggregate only and may represent more than one aggregate type and/or quality but shall be at least C quality or better. This RAP may have an inconsistent gradation and/or asphalt cement content prior to processing. All conglomerate RAP shall be processed prior to testing by crushing to where all RAP shall pass the 16 mm (5/8 in.) or smaller screen. Conglomerate RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department. Conglomerate RAP stockpiles shall meet the requirements of Article 1004.07(d).
 - (3) Conglomerate "D" Quality (DQ). Conglomerate DQ RAP stockpiles shall consist of RAP containing coarse aggregate (crushed or round) that is at least D quality or better. This RAP may have an inconsistent gradation and/or asphalt content. Conglomerate DQ RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department. Conglomerate DQ RAP shall meet the requirements of Article 1004.07(d).

Reclaimed Superpave Low ESAL IL-9.5L surface mixtures shall only be placed in conglomerate DQ RAP stockpiles due to the potential for rounded aggregate.

- (4) Other. RAP stockpiles that do not meet the requirements of the stockpile categories listed above shall be classified as "Other". "Other" RAP stockpiles shall not be used in any of the Department's bituminous mixtures.
- (b) Use. The allowable use of a RAP stockpile shall be set by the lowest quality of coarse aggregate in the RAP stockpile. Class I/Superpave surface mixtures are designated as containing Class B quality coarse aggregate only. Superpave Low ESAL IL-19.0L binder and IL-9.5L surface mixtures are designated as Class C quality coarse aggregate only. Class I/Superpave binder mixtures, bituminous base course mixtures, and bituminous base course widening mixtures are designated as containing Class C quality coarse aggregate only. Bituminous stabilized subbase and BAM shoulders are designated as containing Class D quality coarse aggregate only. Any mixture not listed above shall have the designated quality determined by the Department.

RAP containing steel slag or other expansive material, as determined by the Department, shall be homogeneous and will be approved for use in Class I/Superpave (including Low ESAL) surface mixtures only. RAP stockpiles for use in Class I/Superpave mixtures (including Low ESAL), base course, base course widening and Class B mixtures shall be either homogeneous or conglomerate RAP stockpiles except conglomerate RAP stockpiles shall not be used in Superpave surface mixture Ndesign 50 or greater. RAP for use in bituminous aggregate mixtures (BAM) shoulders and BAM stabilized subbase shall be from homogeneous, conglomerate, or conglomerate DQ stockpiles.

Additionally, RAP used in Class I/Superpave surface mixtures shall originate from milled or crushed mixtures only, in which the coarse aggregate is of Class B quality or better. RAP stockpiles for use in Class I/Superpave (including Low ESAL) binder mixes as well as base course, base course widening and Class B mixtures shall originate from milled or processed surface mixture, binder mixture, or a combination of both mixtures uniformly blended to the satisfaction of the Engineer, in which the coarse aggregate is of Class C quality or better.

- (c) Contaminants. RAP containing contaminants, such as earth, brick, sand, concrete, sheet asphalt, bituminous surface treatment (i.e. chip seal), pavement fabric, etc., will be unacceptable unless the contaminants are removed to the satisfaction of the Engineer. Sheet asphalt shall be stockpiled separately.
- (d) Testing. All RAP shall be sampled and tested either during or after stockpiling.

For testing during stockpiling, washed extraction samples shall be run at the minimum frequency of one sample per 450 metric tons (500 tons) for the first 1800 metric tons (2,000 tons) and one sample per 1800 metric tons (2,000 tons) thereafter. A minimum of five tests shall be required for stockpiles less than 3600 metric tons (4,000 tons).

For testing existing stockpiles, the Contractor shall submit a plan for approval to the District proposing a satisfactory method of sampling and testing the RAP pile either insitu or by restockpiling. The sampling plan shall meet the minimum frequency required above and detail the procedure used to extract representative samples throughout the pile for testing.

Before extraction, each field sample shall be split to test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedure. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

All of the extraction results shall be compiled and averaged for asphalt content and gradation. Individual extraction test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	Homogeneous / Conglomerate	Conglomerate "D" Quality
25 mm (1 in.)		± 5%
12.5 mm (1/2 in.)	± 8%	± 15%
4.75 mm (No. 4)	± 6%	± 13%
2.36 mm (No. 8)	± 5%	
1.18 mm (No. 16)		± 15%
600 μm (No. 30)	± 5%	
75 μm (No. 200)	± 2.0%	± 4.0%
AC	± 0.4%	± 0.5%

If more than 20 percent of the individual sieves are out of the gradation tolerances, or if more than 20 percent of the asphalt content test results fall outside the appropriate tolerances, the RAP will not be allowed to be used in the Department's bituminous concrete mixtures unless the RAP representing the failing tests is removed from the stockpile to the satisfaction of the Engineer. All test data and acceptance ranges shall be sent to the District for evaluation.

With the approval of the Engineer, the ignition oven may be substituted for extractions according to the Illinois Test Procedure, "Calibration of the Ignition Oven for the Purpose of Characterizing Reclaimed Asphalt Pavement (RAP)".

(e) Designs. At the Contractor's option, bituminous concrete mixtures may be constructed utilizing RAP material meeting the above detailed requirements. The amount of RAP included in the mixture shall not exceed the percentages specified in the plans.

RAP designs shall be submitted for volumetric verification. If additional RAP stockpiles are tested and found that no more than 20 percent of the results, as defined under "Testing" herein, are outside of the control tolerances set for the original RAP stockpile

and design, and meets all of the requirements herein, the additional RAP stockpiles may be used in the original mix design at the percent previously verified.

(f) Production. The coarse aggregate in all RAP used shall be equal to or less than the nominal maximum size requirement for the bituminous mixture being produced.

To remove or reduce agglomerated material, a scalping screen, crushing unit or comparable sizing device approved by the Engineer shall be used in the RAP feed system to remove or reduce oversized material. If material passing the sizing device adversely affects the mix production or quality of the mix, the sizing device shall be set at a size specified by the Engineer.

If the RAP control tolerances or QC/QA test results require corrective action, the Contractor shall cease production of the mixture containing RAP and either switch to the virgin aggregate design or submit a new RAP design.

REFLECTIVE CRACK CONTROL TREATMENT (BDE)

Effective: April 1, 2006

Revise the third sentence of the first paragraph of Article 443.01 of the Standard Specifications to read:

"Strip reflective crack control treatment shall be either System A, B, C, or D at the option of the Contractor."

Add the following to Article 443.03 of the Standard Specifications:

"(g) Hot-Poured Joint Sealer......1050.02"

Revise Article 443.09 of the Standard Specifications to Article 443.10.

Revise Article 443.10 of the Standard Specifications to Article 443.11.

Add the following Article to the Standard Specifications:

"Article 443.09 Reflective Crack Control System D. The stress relief membrane shall be applied when the surface temperature is a minimum of 10 °C (50 °F) and rising.

- (a) Tack Coat Placement for Membrane. The tack coat shall be applied to the existing surface using one of the following methods.
 - (1) A hand held wand with a nozzle that produces a fan shaped spray to apply the tack coat evenly according to the rate specified by the manufacturer.
 - (2) A hand held wand without a spray nozzle. The tack coat shall be spread with a squeegee according to the rate specified by the manufacturer.
 - (3) A distributor bar attached to a distributor truck, for longitudinal applications only. The distributor bar nozzles shall be set at 20 degrees to the axis of the bar and the tack coat shall be applied according to the rate specified by the manufacturer. Application of the tack coat directly from a distributor bar attached to a distributor truck will not be permitted for transverse applications.

membrane shall be centered over the crack or joint on the existing surface and with a minimum of 150 mm (6 in.) of the membrane extending beyond the edges of the joint.

The material shall be laid smooth with no uplifted edges. The stress relief membrane shall be placed and rolled immediately with a riding static drum roller or a rubber tire roller. A maximum of three minutes shall pass between the first and second rolling efforts.

The stress relief membrane shall be butted where transverse and longitudinal joints meet or where two rolls must be joined. When required, the stress relief membrane shall be cut with a razor knife from the woven polyester side.

The stress relief membrane shall be placed at least two hours in advance of paving operations. If application must immediately precede the paving operation, hot-poured joint sealer may be required as a tack coat to bond the stress relief membrane to the existing surface.

- (c) Traffic Exposure. Exposing the membrane to traffic shall be minimized. Small amounts of washed sand may be used to blot excess asphalt cement tack coat when necessary to facilitate movement of traffic or construction equipment over the membrane prior to placement of the overlay. Damaged membranes shall be removed and replaced.
- (d) Paving Tack Coat/Paving. Paving operations shall only begin when the membrane is thoroughly bonded to the existing surface. The membrane may be exposed to moisture and rain prior to the application of the overlay, however, the stress relief membrane must be dry at the time the overlay is placed.

A slow-set emulsified asphalt paving tack coat (such as SS-1, SS-1h, CSS-1, or CSS-1h) shall be applied prior to paving over the membrane. Cutback asphalts shall not be used. Hot-mix asphalt or dry washed sand may be placed ahead of the paver if the membrane is sticking to the tires of the paving equipment. The minimum asphalt overlay thickness (total) shall be 50 mm (2 in.) compacted.

When using a vibratory roller for compaction, it shall be set to the lowest amplitude and highest frequency settings."

Add the following Article to the Standard Specifications:

"1062.04 Reflective Crack Control System D. The stress relief membrane shall be 900 mm (36 in.) wide and 4 mm (0.15 in.) thick and shall be a system of materials manufactured in a composite three layer fashion with the following properties.

	Stress Relief Membrane					
Property	Value	Test Method				
Cold Flex	No cracking or separation of fabric	ASTM D 146 (modified)				
Tensile Strength (Peak)	700 N/mm (4,000 psi) min.	ASTM D 412 (modified)				
Elongation (at Peak Tensile)	10 % min.	ASTM D 412 (modified)				
Weight	3.7 kg/sq m (0.76 lbs/sq ft)					
Density (mastic)	1100 kg/cu m (69 lbs/cu ft) min.	ASTM D 70				
Thickness	4 mm (0.15 in.)	ASTM E 154-93 Subsection 10.0 ASTM D 1790				
Absorption (mastic)	1 % max.	ASTM D 517				
Brittleness	Passes	ASTM D 517				
Softening Point (mastic)	104 °C (220 °F)	ASTM D 36				

The bottom layer of the composite shall be a low strength, nonwoven, geotextile and shall be according to AASHTO M 288-92. The bottom geotextile shall be designed to fully bond with the existing pavement with the help of a tack coat. It shall be capable of accommodating sufficiently large stresses at the joint/crack without breaking its bond with the slab. The middle layer of the composite shall be a viscoelastic membrane designed to prevent water entry into the pavement through the cracks and/or joints in the pavement. It also acts as a stress absorbing member interlayer between the overlay and the underlying pavement. The top layer shall be a high strength woven geotextile with a tensile strength of 700 N/mm (4,000 psi) at five percent strain according to ASTM D 4595. The top geotextile shall be designed to fully bond with the overlay and provide high stiffness and reinforcement to the overlay.

The stress relief membrane shall be stored in an inside enclosure with temperatures not exceeding 49 °C (120 °F). Any material that becomes wet prior to installation shall be removed from the iobsite and discarded.

The manufacturer shall furnish a certification with each shipment of stress relief membrane, stating the amount of product furnished, and that the material complies with these requirements."

REINFORCEMENT BARS (BDE)

Effective: November 1, 2005 Revised: November 2, 2005

Revise Article 1006.10(a) of the Supplemental Specifications to read:

- "(a) Reinforcement Bars. Reinforcement bars will be accepted according to the current Bureau of Materials and Physical Research Policy Memorandum, "Reinforcement Bar and Dowel Bar Plant Certification Procedure". The Department will maintain an approved list of producers.
 - (1) Reinforcement Bars (Non-Coated). Reinforcement bars shall be according to ASTM A 706M (A 706), Grade 420 (60) for deformed bars and the following.
 - a. Chemical Composition. The chemical composition of the bars shall be according to the following table.

CHEMICAL COMPOSITION					
Element 1/	Heat Analysis (% maximum)	Product Analysis (% maximum)			
Carbon	0.30	0.33			
Manganese	1.50	1.56			
Phosphorus	0.035	0.045			
Sulfur	0.045	0.055			
Silicon	0.50	0.55			
Nickel	2/	2/			
Chromium	2/	2/			
Molybdenum	2/	2/			
Copper	2/	2/			
Titanium	2/	2/			
Vanadium	2/	2/			
Columbium	2/	2/			
Aluminum	2/, 3/	21, 3/			
Tin 4/	0.040	0.044			

- Note 1/. The bars shall not contain any traces of radioactive elements.
- Note 2/. There is no composition limit but the element must be reported.
- Note 3/. If aluminum is not an intentional addition to the steel for deoxidation or killing purposes, residual aluminum content need not be reported.

Note 4/. If producer bar testing indicates an elongation of 15 percent or more and passing of the bend test, the tin composition requirement may be waived.

- Heat Numbers. Bundles or bars at the construction site shall be marked or tagged with heat identification numbers of the bar producer.
- c. Guided Bend Test. Bars may be subject to a guided bend test across two pins which are free to rotate, where the bending force shall be centrally applied with a fixed or rotating pin of a certain diameter as specified in Table 3 of ASTM A 706M (A 706). The dimensions and clearances of this guided bend test shall be according to ASTM E 190.
- d. Spiral Reinforcment. Spiral reinforcement shall be deformed or plain bars conforming to the above requirements or cold-drawn steel wire conforming to AASHTO M 32.
- (2) Epoxy Coated Reinforcement Bars. Epoxy coated reinforcement bars shall be according to Article 1006.10(a)(1) and shall be epoxy coated according to AASHTO M 284M (M 284) and the following.
 - a. Certification. The epoxy coating applicator shall be certified under the Concrete Reinforcing Steel Institute's (CRSI) Epoxy Plant Certification Program.
 - b. Coating Thickness. The thickness of the epoxy coating shall be 0.18 to 0.30 mm (7 to 12 mils). When spiral reinforcment is coated after fabrication, the thickness of the epoxy coating shall be 0.18 to 0.50 mm (7 to 20 mils).
 - c. Cutting Reinforcement. Reinforcement bars may be sheared or sawn to length after coating, providing the end damage to the coating does not extend more than 13 mm (0.5 in.) back and the cut is patched before any visible rusting appears. Flame cutting will not be permitted."

SEEDING AND SODDING (BDE)

Effective: July 1, 2004 Revised: August 1, 2005

Revise Class 1A and 2A seeding mixtures shown in Table 1 of Article 250.07 of the Standard

Specifications to read:

"Table 1 - SEEDING MIXTURES					
	Class – Type	Seeds	kg/hectare (lb/acre)		
1A	Salt Tolerant Lawn Mixture 7/	Bluegrass Perennial Ryegrass Audubon Red Fescue Rescue 911 Hard Fescue Fults Salt Grass*	70 (60) 20 (20) 20 (20) 20 (20) 70 (60)		
2A	Salt Tolerant Roadside Mixture 7/	Alta Fescue or Ky 31 Perennial Ryegrass Audubon Red Fescue Rescue 911 Hard Fescue Fults Salt Grass 1/	70 (60) 20 (20) 20 (30) 20 (30) 70 (60)"		

Revise Note 7 of Article 250.07 of the Standard Specifications to read:

"Note 7. In Districts 1 through 6, the planting times shall be April 1 to June 15 and August 1 to November 1. In Districts 7 through 9, the planting times shall be March 1 to June 1 and August 1 to November 15. Seeding may be performed outside these dates provided the Contractor guarantees a minimum of 75 percent uniform growth over the entire seeded area(s) after one growing season. The guarantee shall be submitted to the Engineer in writing prior to performing the work. After one growing season, areas not sustaining 75 percent uniform growth shall be interseeded or reseeded, as determined by the Engineer, at the Contractor's expense."

Add the following sentence to Article 252.04 of the Standard Specifications:

"Sod shall not be placed during the months of July and August."

Revise the first paragraph of Article 252.08 of the Standard Specifications to read:

"252.08 Sod Watering. Within two hours after the sod has been placed, water shall be applied at a rate of 25 L/sq m (5 gal/sq yd). Additional water shall be applied every other day at a rate of 15 L/sq m (3 gal/sq yd) for a total of 15 additional waterings. During periods exceeding 26 °C (80 °F) or subnormal rainfall, the schedule of additional waterings may be altered with the approval of the Engineer."

Revise Article 252.09 of the Standard Specifications to read:

"252.09 Supplemental Watering. During periods exceeding 26 °C (80 °F) or subnormal rainfall, supplemental watering may be required after the initial and additional waterings. Supplemental watering shall be performed when directed by the Engineer. Water shall be applied at the rate specified by the Engineer within 24 hours of notice."

Revise the first and third paragraphs of Article 252.12 of the Standard Specifications to read:

"252.12 Method of Measurement. Sodding will be measured for payment in place and the area computed in square meters (square yards). To be acceptable for final payment, the sod shall be growing in place for a minimum of 30 days in a live, healthy condition. When directed by the Engineer, any defective or unacceptable sod shall be removed, replaced and watered by the Contractor at his/her own expense."

"Supplemental watering will be measured for payment in units of 1000 L (1000 gal) of water applied on the sodded areas. Waterings performed in addition to those required by Article 252.08 or after the 30 day establishment period will be considered as supplemental watering."

Replace the first paragraph of Article 252.13 of the Standard Specifications with the following:

- "252.13 Basis of Payment. Sodding will be paid for at the contract unit price per square meter (square yard) for SODDING or SODDING, SALT TOLERANT according to the following schedule.
 - (a) Initial Payment. Upon placement of sod, 25 percent of the pay item will be paid.
 - (b) Final Payment. Upon acceptance of sod, the remaining 75 percent of the pay item will be paid."

Revise Article 1081.03(b) of the Standard Specifications to read:

"(b) Salt Tolerant Sod.

Variety	Percent by Weight
Buffalo Grass	30%
Buchloe Dactyloides	
Amigo Fineleaf Tall Fescue	20%
Audubon Red Fescue	15%
Rescue 911 Hard Fescue	15%
Rugby Kentucky Bluegrass	5%
Fults Pucinnellia Distans	15%"

Revise Table II of Article 1081.04(c)(6) of the Standard Specifications to read:

	_	ΤA	BLE II			
Maria ta af Canada	Hard Seed Percent Maximum	Purity Percent Minimum	Pure, Live Seed Percent Minimum	Weed Percent Maximum	Secondary Noxious Weeds No. per kg (oz) Max. Permitted*	Remarks
Variety of Seeds	20	92	89	0.50	211 (6)	1/
Alfalfa	20	90	75	0.50	175 (5)	-
Brome Grass	- 15	92	87	0.30	211 (6)	2/
Clover, Alsike	15	92	83	0.50	211 (6)	-
Clover, Crimson	15	92	87	0.30	211 (6)	-
Clover, Ladino	20	92	87	0.30	211 (6)	-
Clover, Red	20 30	92	87	0.30	211 (6)	3/
Clover, White Dutch	0	97	82	0.10	105 (3)	-
Audubon Red Fescue	U	97	82	1.00	105 (3)	-
Fescue, Alta or Ky. 31	-	97	82	1.00	105 (3)	-
Fescue, Creeping Red	-	98	85	0.10	70 (2)	-
Fults Salt Grass	0	97	80	0.30	247 (7)	5/
Kentucky Bluegrass	-	97 92	84	0.50	211 (6)	3/
Lespedeza, Korean	20	92 92	88	0.50	70 (2)	4/
Oats	-	90	78	1.50	175 (5)	4/
Orchard Grass	-	90	78	1.80	175 (5)	4/
Redtop	-	90 97	85	0.30	175 (5)	4/
Ryegrass, Perennial, Annual	-	97 92	83	0.50	70 (2)	4/
Rye, Grain, Winter	-	92 97	82	0.10	105 (3)	-
Rescue 911 Hard Fescue	0	97 92	84	0.50	175 (5)	4/
Timothy	-	92 92	67	1.00	211 (6)	3/ & 6/
Vetch, Crown	30		88	1.00	70 (2)	4/
Vetch, Spring	30	92		1.00	105 (3)	4/
Vetch, Winter	15	92	83 89	0.50	70 (2)	4/
Wheat, hard Red Winter		92		0.50		

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)

Effective: November 1, 2005

<u>Definition</u>. Self-consolidating concrete is a flowable mixture that does not require mechanical vibration for consolidation.

<u>Usage</u>. Self-consolidating concrete may be used for cast-in-place concrete construction items involving Class MS and SI concrete. Self-consolidating concrete may also be used for drilled shafts.

Materials. Materials shall be according to the following.

(a) <u>Self-Consolidating Admixtures</u>. The self-consolidating admixture system shall consist of either a high range water-reducing admixture only or a high range water-reducing admixture combined with a separate viscosity modifying admixture. The one or two component admixture system shall be capable of producing a concrete that can flow around reinforcement and consolidate under its own weight without additional effort and without segregation.

The high range water-reducing admixture shall comply with the requirements of AASHTO M 194, Type F.

The viscosity modifying admixture will be evaluated according to the test methods and mix design proportions referenced in AASHTO M 194, except the following physical requirements shall be met:

- (1) For initial and final set times, the allowable deviation of the test concrete from the reference concrete shall not be more than 1.0 hour earlier or 1.5 hours later.
- (2) For compressive and flexural strengths, the test concrete shall be a minimum of 90 percent of the reference concrete at 3, 7, and 28 days.
- (3) The length change of the test concrete shall be a maximum 135 percent of the reference concrete. However, if the length change of the reference concrete is less than 0.030 percent, the length change of the test concrete shall be a maximum 0.010 percentage units greater than the reference concrete.
- (4) The relative durability factor of the test concrete shall be a minimum 80 percent.
- (b) Fine Aggregate. A fine aggregate used alone in the mix design shall not have an expansion greater than 0.30 percent per ASTM C 1260. For a blend of two or more fine aggregates, the resulting blend shall not have an expansion greater than 0.30 percent.

The aggregate blend expansion will be calculated as follows:

Aggregate Blend Expansion = $(a/100 \times A) + (b/100 \times B) + (c/100 \times C) + \dots$ etc.

Where: a, b, c, ... = percent of aggregate blend A, B, C, ... = aggregate expansion according to ASTM C 1260

Mix Design Criteria. Article 1020.04 of the Standard Specifications shall apply except as follows:

- (a) The minimum cement factor shall be according to Article 1020.04 of the Standard Specifications or as specified. The maximum cement factor shall be 418 kg/cu m (7.05 cwt/cu yd). The cement factor shall not be reduced if a water-reducing, retarding, or high range water-reducing admixture is used.
- (b) The maximum allowable water/cement ratio shall be according to Article 1020.04 of the Standard Specifications or 0.44, whichever is lower.
- (c) The slump requirements shall not apply.
- (d) The coarse aggregate gradations shall be CA 11, CA 13, CA 14, CA 16, or a blend of these gradations. CA 11 shall not be used for drilled shafts or when the Engineer approves a horizontal flow distance greater than 9 m (30 ft). The fine aggregate proportion shall be a maximum 50 percent by mass (weight) of the total aggregate used.
- (e) The slump flow range shall be ± 50 mm (± 2 in.) of the Contractor target value, and within the overall Department range of 510 mm (20 in.) minimum to 710 mm (28 in.) maximum.
- (f) The visual stability index shall be a maximum of 1.
- (g) The J-ring value shall be a maximum of 100 mm (4 in.). The Contractor may specify a lower maximum in the mix design.
- (h) The L-box blocking ratio shall be a minimum of 60 percent. The Contractor may specify a higher minimum in the mix design.
- (i) The column segregation index shall be a maximum 15 percent.
- (j) The hardened visual stability index shall be a maximum of 1.

Test Methods. Illinois Test Procedures SCC-1, SCC-2, SCC-3, SCC-4, SCC-5, SCC-6, and Illinois Modified AASHTO T 22, 23, 121, 126, 141, 152, 177, 196, and 309 shall be used for testing of self-consolidating concrete mixtures.

Mix Design Submittal. The Contractor's Level III PCC Technician shall submit a mix design according to the "Portland Cement Concrete Level III Technician" course manual, except target slump information is not applicable and will not be required. However, a slump flow target range

shall be submitted. In addition, the design mortar factor may exceed 1.10 and durability test data will be waived.

A J-ring value shall be submitted if a lower mix design maximum will apply. An L-box blocking ratio shall be submitted if a higher mix design minimum will apply. The Contractor shall also indicate applicable construction items for the mix design.

Trial mixture information will also be required by the Engineer. A trial mixture is a batch of concrete tested by the Contractor to verify the Contractor's mix design will meet specification requirements. Trial mixture information shall include test results as specified in the "Portland Cement Concrete Level III Technician" course manual. Test results shall also include slump flow, visual stability index, J-ring value, L-box blocking ratio, column segregation index, and hardened visual stability index. For the trial mixture, the slump flow shall be near the midpoint of the proposed slump flow target range.

<u>Trial Batch</u>. A minimum 1.5 cu m (2 cu yd) trial batch shall be produced, and the self-consolidating concrete admixture dosage proposed by the Contractor shall be used. The slump flow shall be within 25 mm (1.0 in.) of the maximum slump flow range specified by the Contractor, and the air content shall be within the top half of the allowable specification range.

The trial batch shall be scheduled a minimum of 21 calendar days prior to anticipated use, and shall be performed in the presence of the Engineer.

The Contractor shall provide the labor, equipment, and materials to test the concrete. The mixture will be evaluated by the Engineer for strength, air content, slump flow, visual stability index, J-ring value, L-box blocking ratio, column segregation index, and hardened visual stability index.

Upon review of the test data from the trial batch, the Engineer will verify or deny the use of the mix design and notify the Contractor. Verification by the Engineer will include the Contractor's target slump flow range. If applicable, the Engineer will verify the Contractor's maximum J-ring value and minimum L-box blocking ratio.

A new trial batch will be required whenever there is a change in the source of any component material, proportions, dosage of the self-consolidating concrete admixture, batch sequence, mixing speed, mixing time, or as determined by the Engineer. The testing criteria for the new trial batch will be determined by the Engineer.

When necessary, the trial batches shall be disposed of according to Article 202.03 of the Standard Specifications.

Mixing Portland Cement Concrete. In addition to Article 1020.11 of the Standard Specifications, the mixing time for central-mixed concrete shall not be reduced as a result of a mixer performance test. Truck-mixed or shrink-mixed concrete shall be mixed in a truck mixer for a minimum of 100 revolutions.

Wash water, if used, shall be completely discharged from the drum or container before the succeeding batch is introduced.

The batch sequence, mixing speed, and mixing time shall be appropriate to prevent cement balls and mix foaming for central-mixed, truck-mixed, and shrink-mixed concrete.

<u>Falsework and Forms</u>. In addition to Articles 503.05 and 503.06 of the Standard Specifications, the Contractor shall design falsework and forms for full hydrostatic head pressure of the concrete. Forms shall be tight to prevent leakage of fluid concrete.

<u>Placing and Consolidating</u>. Concrete placement and consolidations shall be according to Article 503.07 of the Standard Specifications except as follows:

Revise the third paragraph of Article 503.07 of the Standard Specifications to read:

"Open troughs and chutes shall extend as nearly as practicable to the point of deposit. The drop distance of concrete shall not exceed 1.5 m (5 ft). If necessary, a tremie shall be used to meet this requirement. The maximum distance of horizontal flow from the point of deposit shall be 9 m (30 ft), unless approved otherwise by the Engineer. For drilled shafts, free fall placement will not be permitted."

Delete the sixth, seventh, eighth and ninth paragraphs of Article 503.07 of the Standard Specifications.

Revise the eleventh paragraph of Article 503.07 of the Standard Specifications to read:

"Concrete shall be placed in continuous layers. When it is necessary by reason of an emergency to place less than a complete horizontal layer in one operation, such layer shall terminate in a vertical bulkhead. In order that the concrete will not be injured and that there shall be no line of separation between the batches, the separate batches shall follow each other closely as recommended by the manufacturer of the self-consolidating concrete admixture(s). In no case shall the interval of time between the placing of successive batches be greater than 20 minutes. Concrete shall be rodded with a piece of lumber or conduit if the material has lost its fluidity prior to placement of additional concrete. Any other method for restoring the fluidity of the concrete shall be approved by the Engineer. If ready-mixed concrete is used, the requirements of Article 1020.11 shall apply. Delivery of mixed concrete shall be regulated so that there will not be an interruption in the placing of concrete in the forms, as recommended by the manufacturer of the self-consolidating concrete admixture(s). In no case shall the interval of time be greater than 20 minutes."

Quality Control by Contractor at Plant. The specified test frequencies for aggregate gradation, aggregate moisture, air content, unit weight/yield, and temperature shall be performed as indicated in the contract plans.

Slump flow, visual stability index, and J-ring or L-box tests shall be performed as needed to control production. The column segregation index test and hardened visual stability index test will not be required to be performed at the plant.

Quality Control by Contractor at Jobsite. The specified test frequencies for air content, strength, and temperature shall be performed as indicated in the contract plans.

Slump flow, visual stability index, and J-ring or L-box tests shall be performed on the first two truck deliveries of the day, and every 40 cu m (50 cu yd) thereafter. The Contractor shall select either the J-ring or L-box test for jobsite testing.

The column segregation index test will not be required to be performed at the jobsite. The hardened visual stability index test shall be performed on the first truck delivery of the day, and every 230 cu m (300 cu yd) thereafter. Slump flow, visual stability index, J-ring value or L-box blocking ratio, air content, and concrete temperature shall be recorded for each hardened visual stability index test.

The Contractor shall retain all hardened visual stability index cut cylinder specimens until the Engineer notifies the Contractor that the specimens may be discarded.

If mix foaming or other potential detrimental material is observed during placement or at the completion of the pour, the material shall be removed while the concrete is still plastic.

Quality Assurance by Engineer at Plant. For air content and aggregate gradation, quality assurance independent sample testing and split sample testing will be performed as indicated in the contract plans.

For slump flow, visual stability index, and J-ring or L-box tests, quality assurance independent sample testing and split sample testing will be performed as determined by the Engineer.

Quality Assurance by Engineer at Jobsite. For air content and strength, quality assurance independent sample testing and split sample testing will be performed as indicated in the contract plans.

For slump flow, visual stability index, J-ring or L-box, and hardened visual stability index tests, quality assurance independent sample testing will be performed as determined by the Engineer.

For slump flow and visual stability index quality assurance split sample testing, the Engineer will perform tests at the beginning of the project on the first three tests performed by the Contractor. Thereafter, a minimum of ten percent of total tests required of the Contractor will be performed per plant, which will include a minimum of one test per mix design. The acceptable limit of precision will be 25 mm (1 in.) for slump flow, and a limit of precision will not apply to the visual stability index.

For the J-ring or the L-box quality assurance split sample testing, a minimum of 80 percent of the total tests required of the Contractor will be witnessed by the Engineer per plant, which will

include a minimum of one witnessed test per mix design. The Engineer reserves the right to conduct quality assurance split sample testing. The acceptable limit of precision will be 25 mm (1 in.) for the J-ring value and ten percent for the L-box blocking ratio.

For each hardened visual stability index test performed by the Contractor, the cut cylinders shall be presented to the Engineer for determination of the rating. The Engineer reserves the right to conduct quality assurance split sample testing. A limit of precision will not apply to the hardened visual stability index.

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)

Effective: July 1, 2004

Revised: November 1, 2005

<u>Definition</u>. Self-consolidating concrete is a flowable mixture that does not require mechanical vibration for consolidation.

Usage. Self-consolidating concrete may be used for precast concrete products.

Materials. Materials shall be according to the following.

(a) <u>Self-Consolidating Admixtures</u>. The self-consolidating admixture system shall consist of either a high range water-reducing admixture only or a high range water-reducing admixture combined with a separate viscosity modifying admixture. The one or two component admixture system shall be capable of producing a concrete that can flow around reinforcement and consolidate under its own weight without additional effort and without segregation.

The high range water-reducing admixture shall comply with the requirements of AASHTO M 194, Type F.

The viscosity modifying admixture will be evaluated according to the test methods and mix design proportions referenced in AASHTO M 194, except the following physical requirements shall be met:

- (1) For initial and final set times, the allowable deviation of the test concrete from the reference concrete shall not be more than 1.0 hour earlier or 1.5 hours later.
- (2) For compressive and flexural strengths, the test concrete shall be a minimum of 90 percent of the reference concrete at 3, 7 and 28 days.
- (3) The length change of the test concrete shall be a maximum 135 percent of the reference concrete. However, if the length change of the reference concrete is less than 0.030 percent, the length change of the test concrete shall be a maximum 0.010 percentage units greater than the reference concrete.
- (4) The relative durability factor of the test concrete shall be a minimum 80 percent.
- (b) <u>Fine Aggregate</u>. A fine aggregate used alone in the mix design shall not have an expansion greater than 0.30 percent per ASTM C 1260. For a blend of two or more fine aggregates, the resulting blend shall not have an expansion greater than 0.30 percent.

The aggregate blend expansion will be calculated as follows:

Aggregate Blend Expansion = $(a/100 \times A) + (b/100 \times B) + (c/100 \times C) + \dots$ etc.

Where: a, b, c, ... = percent of aggregate blend
A, B, C, ... = aggregate expansion according to ASTM C 1260

Mix Design Criteria. The mix design criteria shall be as follows:

- (a) The minimum cement factor shall be according to Article 1020.04 of the Standard Specifications or as specified. The maximum cement factor shall be 418 kg/cu m (7.05 cwt/cu yd).
- (b) The maximum allowable water/cement ratio shall be according to Article 1020.04 of the Standard Specifications or 0.44, whichever is lower.
- (c) The slump requirements of Article 1020.04 of the Standard Specifications shall not apply.
- (d) The coarse aggregate gradations shall be CA 11, CA 13, CA 14, CA 16, or a blend of these gradations. CA 11 shall not be used when the Engineer approves a horizontal flow distance greater than 9 m (30 ft). The fine aggregate proportion shall be a maximum 50 percent by mass (weight) of the total aggregate used.
- (e) The slump flow range shall be ±50 mm (±2 in.) of the Contractor target value, and within the overall Department range of 510 mm (20 in.) minimum to 710 mm (28 in.) maximum.
- (f) The visual stability index shall be a maximum of 1.
- (g) The J-ring value shall be a maximum of 100 mm (4 in.). The Contractor may specify a lower maximum in the mix design.
- (h) The L-box blocking ratio shall be a minimum of 60 percent. The Contractor may specify a higher minimum in the mix design.
- (i) The column segregation index shall be a maximum 15 percent.
- (j) The hardened visual stability index shall be a maximum of 1.

Mix Design Approval. The Contractor shall obtain mix design approval according to the Department's Policy Memorandum "Quality Control/Quality Assurance Program for Precast Concrete Products".

STABILIZED SUBBASE AND BITUMINOUS SHOULDERS SUPERPAVE (BDE)

Effective: April 1, 2002 Revised: August 1, 2005

<u>Description</u>. This work shall consist of constructing stabilized subbase and bituminous shoulders Superpave according to Sections 312 and 482 respectively, of the Standard Specifications and the special provision, "Quality Control/Quality Assurance of Bituminous Concrete Mixtures" except as modified herein.

Revise Article 312.03(b) of the Standard Specifications to read:

"(b) RAP Material (Note 3)"

Revise Note 2 of Article 312.03 of the Standard Specifications to read:

"Note 2. Gradation CA 6, CA 10, or CA 12 shall be used."

Revise Note 3 of Article 312.03 of the Standard Specifications to read:

"Note 3. RAP shall meet the requirements of the special provision "RAP for Use in Bituminous Concrete Mixtures". RAP containing steel slag shall be permitted for use in top-lift surface mixtures only."

Revise Note 4 of Article 312.03 of the Standard Specifications to read:

"Note 4. Unless otherwise specified on the plans, the bituminous material shall be performance graded asphalt cement, PG58-22. When more than 15 percent RAP is used, a softer PG binder may be required as determined by the Engineer."

Revise Article 312.06 of the Standard Specifications to read:

"312.06 Mixture Design. The Contractor shall submit mix designs for approval, for each required mixture. Mix designs shall be developed by Level III personnel who have completed the course, "Superpave Mix Design Upgrade". The mixtures shall be designed according to the respective Illinois Modified AASHTO references listed below:

AASHTO MP 2 Standard Specification for Superpave Volumetric Mix Design

AASHTO R 30 Standard Practice for Mixture Conditioning of Hot-Mix Asphalt (HMA)

AASHTO PP 28 Standard Practice for Designing Superpave HMA

AASHTO T 209 Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures

AASHTO T 312 Preparing and Determining the Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor

AASHTO T 308 Determining the Asphalt Content of Hot Mix Asphalt (HMA) by the Ignition Method

(a) Job Mix Formula (JMF). The JMF shall be according to the following limits:

Ingredient	Percent by Dry Weight
Aggregate	94.0 to 96.0
Asphalt Cement	4 0 to 6.0*
Aspnait Cement	1 /
Dust/AC Ratio	

*Upper limit may be raised for the lower or top lifts if the Contractor elects to use a highly absorptive coarse and/or fine aggregate requiring more than six percent asphalt. The additional asphalt shall be furnished at no cost to the Department.

When RAP material is being used, the JMF shall be according to the following limits:

Ingredient	Percent by Dry Weight
Virgin Aggregate(s)	46.0 to 96.0
RAP Material(s) (Note 1)	0 to 50
Mineral Filler (if required)	0 to 5.0
Asphalt Cement	4.0 to 7.0
Dust/AC Ratio	1.4
Dustro Natio	***************************************

Note 1. If specified on the plans, the maximum percentage of RAP shall be as specified therein.

It is recommended that the selected combined aggregate gradation not pass through the restricted zones specified in Illinois Modified AASHTO MP 2.

(b) Volumetric Requirements.

Design Compactive	Design Air Voids
Effort	Target (%)
N _{DES} =30	2.0

(c) Determination of Need for Anti-Stripping Additive. The mixture designer shall determine if an additive is needed in the mix to prevent stripping. The determination will be made on the basis of tests performed according to Illinois Modified AASHTO T 283 using 4 in. Marshall bricks. To be considered acceptable by the Engineer as a mixture not susceptible to stripping, the ratio of conditioned to unconditioned split tensile strengths (TSR) shall be equal to or greater than 0.75. Mixtures, either with or without an additive, with TSR values less than 0.75 will be considered unacceptable.

If it is determined that an additive is required, the additive may be hydrated lime, slaked quicklime, or a liquid additive, at the Contractor's option. The liquid additive shall be selected from the Department's list of approved additives and may be limited to those which have exhibited satisfactory performance in similar mixes.

Dry hydrated lime shall be added at a rate of 1.0 to 1.5 percent by weight of total dry aggregate. Slurry shall be added in such quantity as to provide the required amount of hydrated lime solids by weight of total dry aggregate. The exact rate of application for all anti-stripping additives will be determined by the Engineer. The method of application shall be according to Article 406.12 of the Standard Specifications."

Revise Article 312.08 of the Standard Specifications to read:

"312.08 Mixture Production. When a hot-mix plant conforming to Article 1102.01 is used, the aggregate shall be dried and heated in the revolving dryer to a temperature of 120 °C (250 °F) to 175 °C (350 °F).

The aggregate and bituminous material used in the bituminous aggregate mixture shall be measured separately and accurately by weight or by volume. When the aggregate is in the mixer, the bituminous material shall be added and mixing continued for a minimum of 35 seconds and until a homogeneous mixture is produced in which all particles of the aggregate are coated. The mixing period, size of the batch and the production rate shall be approved by the Engineer.

The ingredients shall be heated and combined in such a manner as to produce a mixture which, when discharged from the mixer, shall be workable and vary not more 10 °C (20 °F) from the temperature set by the Engineer.

When RAP material(s) is used in the bituminous aggregate mixture, the virgin aggregate(s) shall be dried and heated in the dryer to a temperature that will produce the specified resultant mix temperature when combined with the RAP material.

The heated virgin aggregates and mineral filler shall be combined with RAP material in such a manner as to produce a bituminous mixture which when discharged from the mixer shall not vary more than 15 °C (30 °F) from the temperature set by the Engineer. The combined ingredients shall be mixed for a minimum of 35 seconds and until a homogeneous mixture as to composition and temperature is obtained. The total mixing time shall be a minimum of 45 seconds consisting of dry and wet mixing. Variation in wet and dry mixing times may be permitted, depending on the moisture content and amount of salvaged material used. The mix temperature shall not exceed 175 °C (350 °F). Wide variations in the mixture temperature will be cause for rejection of the mix.

(a) Personnel. The QC Manager and Level 1 Technician shall have successfully completed the Department's "Superpave Field Control Course".

(b) Required Tests. Testing for stabilized subbase and bituminous shoulders shall be conducted to control the production of the bituminous mixture using the test methods identified and performed at a frequency not less than indicated in the following table.

Parameter	Frequency of Tests Non-Class I Mixtures	Test Method
Aggregate Gradation Hot bins for batch and continuous plants. Individual cold-feeds or combined belt-feed for drier-drum plants. (% passing seives: 12.5 mm (1/2 ln.), 4.75 mm (No. 4), 75 µm (No. 200))	1 gradation per day of production. The first day of production shall be washed ignition oven test on the mix. Thereafter, the testing shall alternate between dry gradation and washed ignition oven test on the mix. The dry gradation and the washed ignition oven test results shall be plotted on the same control chart.	Iflinois Procedure (See Manual of Test Procedures for Materials).
Asphalt Content by ignition oven (Note 1.)	1 per day	Illinois-Modified AASHTO T 308
Air Voids Bulk Specific Gravity of Gyratory Sample	1 per day	Illinois-Modified AASHTO T 312
Maximum Specific Gravity of Mixture	1 per day	Illinois-Modified AASHTO T 209

Note 1. The Engineer may waive the ignition oven requirement for AC content if the aggregates to be used are known to have ignition AC content calibration factors which exceed 1.5 percent. If the ignition oven requirement is waived, other Department approved methods shall be used to determine the AC content.

During production, the ratio of minus 75 μm (#200) sieve material to total asphalt cement shall be not less than 0.6 nor more than 1.6, and the moisture content of the mixture at discharge from the mixer shall not exceed 0.5 percent. If at any time the ratio of minus 75 μm (#200) material to asphalt or moisture content of the mixture falls outside the stated limits, production of the mix shall cease. The cause shall be determined and corrective action satisfactory to the Engineer shall be initiated prior to resumption of production.

During production, mixture containing an anti-stripping additive will be tested by the Engineer for stripping according to Illinois Modified AASHTO T 283. If the mixture fails to meet the TSR criteria for acceptance, no further mixture will be accepted until the Contractor takes such action as is necessary to furnish a mixture meeting the criteria.

(c) Control Charts/Limits. Control charts/limits shall be according to QC/QA requirements for Non-Class I Mixtures except air voids and density shall be plotted on the control charts within the following control limits:

Individual Test Control Limits		
Voids ±1.2%		
Density ^{1/}	93.0 – 97.4% of G _{mm}	

1/ Except when placed as first lift over unimproved subgrade. When the exception applies, the first lift over unimproved subgrade shall be compacted to an average density of not less than 95 percent nor greater than 102 percent of the target density obtained on the growth curve.

Replace Article 312.10 of the Standard Specifications with the following:

"312.10 Placing. After the subgrade has been compacted and is acceptable to the Engineer, the bituminous aggregate mixture shall be spread upon it with a mechanical spreader. The maximum compacted thickness of each lift shall be 150 mm (6 in.) provided the required density is obtained. The minimum compacted thickness of each lift shall be according to the following table:

Nominal Maximum Aggregate Size of Mixture	Minimum Compacted Lift Thickness
CA 12 – 12.5 mm (1/2 in.)	38 mm (1 1/2 in.)
CA 10 - 19 mm (3/4 in.)	57 mm (2 1/4 in.)
CA 6 – 25 mm (1 in.)	76 mm (3 in.)

The surface of each lift shall be clean and dry before succeeding lifts are placed."

Revise Article 482.02 of the Standard Specifications to read:

"482.02 Materials. Materials shall meet the requirements of Article 312.03. For the top lift, the aggregate used shall meet the gradation requirements for a CA 10 or CA 12. Blending of aggregates to meet these gradation requirements will be permitted."

Revise the first paragraph of Article 482.04 of the Standard Specifications to read:

"482.04 General. For pavement and shoulder resurfacing projects, Superpave binder and surface course mixtures may be used in lieu of bituminous aggregate mixture for the resurfacing of shoulders, at the option of the Contractor, or shall be used when specified on the plans."

Revise Article 482.04(c) of the Standard Specifications to read:

"(c) Mixture Production312.08"

Revise Article 482.05 of the Standard Specifications to read:

"482.05 Composition of Bituminous Aggregate Mixture. The composition of the mixture shall be according to Article 312.06, except that the amount of asphalt cement used in the top lift shall be increased up to 0.5 percent more than that required in the lower lifts. For resurfacing projects when the Superpave binder and surface course mixtures option is used, the asphalt cement used in the top lift shall not be increased. Superpave mixtures used on the top lift of such shoulders shall meet the gradation requirements of the special provision "Superpave Bituminous Concrete Mixtures".

For shoulder and strip construction, the composition of the Superpave binder and surface course shall be the same as that specified for the mainline pavement."

In the following locations of Section 482 of the Standard Specifications, change "Class I" to "Superpave":

the second paragraph of Article 482.04 the first sentence of the second paragraph of Article 482.06 the first sentence of the fourth paragraph of Article 482.06 the second sentence of the fourth paragraph of Article 482.06 the first sentence of the third paragraph of Article 482.08(b)

Revise the first paragraph of Article 482.06 of the Standard Specifications to read:

"482.06 Placing. This work shall be according to Article 312.10 as modified herein. The mechanical spreader for the top lift of shoulders shall meet the requirements of Article 1102.03 when the shoulder width is 3 m (10 ft) or greater."

Revise Article 482.09 of the Standard Specifications to read:

"482.09 Basis of Payment. When bituminous shoulders are constructed along the edges of the completed pavement structure, this work will be paid for at the contract unit price per square meter (square yard) for BITUMINOUS SHOULDERS SUPERPAVE of the thickness specified. The specified thickness shall be the thickness shown on the plans at the edge of the pavement.

On pavement and shoulder resurfacing projects, the shoulder resurfacing will be paid for at the contract unit price per metric ton (ton) for BITUMINOUS SHOULDERS SUPERPAVE.

The construction of shoulder strips for resurfacing pavements will be paid according to the special provision, "Superpave Bituminous Concrete Mixtures"."

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: April 2, 2005

To account for the preparatory work and operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting in accordance with Article 108.01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

SUBGRADE PREPARATION (BDE)

Effective: November 1, 2002

Revise the tenth paragraph of Article 301.03 of the Standard Specifications to read:

"Equipment of such weight, or used in such a way as to cause a rut in the finished subgrade of 13 mm (1/2 in.) or more in depth, shall be removed from the work or the rutting otherwise prevented."

SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE)

Effective: January 1, 2000 Revised: April 1, 2004

<u>Description</u>. This work shall consist of designing, producing and constructing Superpave bituminous concrete mixtures using Illinois Modified Strategic Highway Research Program (SHRP) Superpave criteria. This work shall be according to Sections 406 and 407 of the Standard Specifications and the special provision, "Quality Control/Quality Assurance of Bituminous Concrete Mixtures", except as follows.

Materials.

- (a) Fine Aggregate Blend Requirement. The Contractor may be required to provide FA 20 manufactured sand to meet the design requirements. For mixtures with Ndesign ≥ 90, at least 50 percent of the required fine aggregate fraction shall consist of either stone sand, slag sand, or steel slag sand meeting the FA/FM 20 gradation.
- (b) Reclaimed Asphalt Pavement (RAP). If the Contractor is allowed to use more than 15 percent RAP, as specified in the plans, a softer performance-graded binder may be required as determined by the Engineer.

RAP shall meet the requirements of the special provision, "RAP for Use in Bituminous Concrete Mixtures".

RAP will not be permitted in mixtures containing polymer modifiers.

RAP containing steel slag will be permitted for use in top-lift surface mixtures only.

(c) Bituminous Material. The asphalt cement (AC) shall be performance-graded (PG) or polymer modified performance-graded (SBS-PG or SBR-PG) meeting the requirements of Article 1009.05 of the Standard Specifications for the grade specified on the plans.

The following additional guidelines shall be used if a polymer modified asphalt is specified:

- (1) The polymer modified asphalt cement shall be shipped, maintained, and stored at the mix plant according to the manufacturer's requirements. Polymer modified asphalt cement shall be placed in an empty tank and shall not be blended with other asphalt cements.
- (2) The mixture shall be designed using a mixing temperature of 163 \pm 3 °C (325 \pm 5 °F) and a gyratory compaction temperature of 152 \pm 3 °C (305 \pm 5 °F).
- (3) Pneumatic-tired rollers will not be allowed unless otherwise specified by the Engineer. A vibratory roller meeting the requirements of Article 406.16 of the

Standard Specifications shall be required in the absence of the pneumatic-tired roller.

Laboratory Equipment.

- (a) Superpave Gyratory Compactor. The superpave gyratory compactor (SGC) shall be used for all QC/QA testing.
- (b) Ignition Oven. The ignition oven shall be used to determine the AC content. The ignition oven shall also be used to recover aggregates for all required washed gradations.

The Engineer may waive the ignition oven requirement for AC content if the aggregates to be used are known to have ignition AC content calibration factors which exceed 1.5 percent. If the ignition oven requirement is waived, other Department approved methods shall be used to determine the AC content.

Mixture Design. The Contractor shall submit mix designs, for approval, for each required mixture. Mix designs shall be developed by Level III personnel who have successfully completed the course, "Superpave Mix Design Upgrade". Articles 406.10 and 406.13 of the Standard Specifications shall not apply. The mixtures shall be designed according to the respective Illinois Modified AASHTO references listed below.

AASHTO MP 2	Standard Specification for Superpave Volumetric Mix Design
AASHTO R 30	Standard Practice for Mixture Conditioning of Hot-Mix Asphalt (HMA)
AASHTO PP 28	Standard Practice for Designing Superpave HMA
AASHTO T 209	Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
AASHTO T 312	Preparing and Determining the Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor
AASHTO T 308	Determining the Asphalt Content of Hot Mix Asphalt (HMA) by the Ignition Method

(a) Mixture Composition. The ingredients of the bituminous mixture shall be combined in such proportions as to produce a mixture conforming to the composition limits by weight. The gradation mixture specified on the plans shall produce a mixture falling within the limits specified in Table 1.

TABLE 1. MIXTURE COMPOSITION (% PASSING)1/								
II 25 0 mm			IL-19.0 mm		IL-12.5 mm ^{4/}		IL-9.5 mm ^{4/}	
Sieve Size	min	max	min	max	min	max	min	max
37.5 mm (1 1/2 in.)		100						
25 mm (1 in.)	90	100		100	<u> </u>			
19 mm (3/4 in.)		90	82	100		100		
12.5 mm (1/2 in.)	45	75	50	85	90	100		100
9.5 mm (3/8 in.)						89	90	100
4.75 mm (#4)	24	4221	24	50 ^{2/}	28	65	28	65
2.36 mm (#8)	16	31	20	36	28	48 ^{3/}	28	48 ^{3/}
1.18 mm (#16)	10	22	10	25	10	32	10	32
600 μm (#30)						<u> </u>		<u> </u>
300 μm (#50)	4	12	4	12	4	15	4	15
150 μm (#100)	3	9	3	9	3	10	3	10
75 μm (#200)	3	6	3	6	4	6	4	6

- 1/ Based on percent of total aggregate weight.
- 2/ The mixture composition shall not exceed 40 percent passing the 4.75 mm (#4) sieve for binder courses with Ndesign ≥ 90.
- 3/ The mixture composition shall not exceed 40 percent passing the 2.36 mm (#8) sieve for surface courses with Ndesign ≥ 90.
- 4/ The mixture composition for surface courses shall be according to IL-12.5 mm or IL-9.5 mm, unless otherwise specified by the Engineer.

One of the above gradations shall be used for leveling binder as specified in the plans and according to Article 406.04 of the Standard Specifications.

It is recommended that the selected combined aggregate gradation not pass through the restricted zones specified in Illinois Modified AASHTO MP 2.

- (b) Dust/AC Ratio for Superpave. The ratio of material passing the 75 μm (#200) sieve to total asphalt cement shall not exceed 1.0 for mixture design (based on total weight of mixture).
- (c) Volumetric Requirements. The target value for the air voids of the hot mix asphalt (HMA) shall be 4.0 percent at the design number of gyrations. The VMA and VFA of the HMA design shall be based on the nominal maximum size of the aggregate in the mix and shall conform to the requirements listed in Table 2.

	TAB	LE 2. VOLL	METRIC REC	QUIREMENT	S
	Voids in the Mineral Aggregate (VMA), % minimum			Voids Filled with Asphalt (VFA),	
Ndesign	IL-25.0	IL-19.0	IL-12.5	IL-9.5	<u>%</u>
50				1	65 - 78
70	12.0	13.0	14.0	15	65 - 75
90] 12.0	10.0		!	05-75
105	}			<u> </u>	

(d) Determination of Need for Anti-Stripping Additive. The mixture designer shall determine if an additive is needed in the mix to prevent stripping. The determination will be made on the basis of tests performed according to Illinois Modified T 283 using 4 in. Marshall bricks. To be considered acceptable by the Department as a mixture not susceptible to stripping, the ratio of conditioned to unconditioned split tensile strengths (TSRs) shall be equal to or greater than 0.75. Mixtures, either with or without an additive, with TSRs less than 0.75 will be considered unacceptable.

If it is determined that an additive is required, the additive may be hydrated lime, slaked quicklime, or a liquid additive, at the Contractor's option. The liquid additive shall be selected from the Department's list of approved additives and may be limited to those which have exhibited satisfactory performance in similar mixes.

Dry hydrated lime shall be added at a rate of 1.0 to 1.5 percent by weight of total dry aggregate. Slurry shall be added in such quantity as to provide the required amount of hydrated lime solids by weight of total dry aggregate. The exact rate of application for all anti-stripping additives will be determined by the Department. The method of application shall be according to Article 406.12 of the Standard Specifications.

<u>Personnel</u>. The QC Manager and Level 1 Technician shall have successfully completed the Department's "Superpave Field Control Course".

Required Plant Tests. Testing shall be conducted to control the production of the bituminous mixture. The Contractor shall use the test methods identified to perform the following mixture tests at a frequency not less than that indicated in Table 3.

		REQUIRED PLANT TESTS for SUPERPAVE Frequency of Tests	Test Method
Parameter Aggregate Gradation Hot bins for batch and continuous plants Individual cold-feeds or combined belt-feed for drier drum plants.		1 dry gradation per day of production (either morning or afternoon sample). and 1 washed ignition oven test on the mix per day of production (conduct in afternoon if dry gradation is conducted in the morning or vice versa).	Illinois Procedure (See Manual of Test Procedures for Materials).
12.5 mm 4.75 mm 2.36 mm 600 µm	ing sieves: n (1/2 in.), n (No. 4), n (No. 8), (No. 30), No. 200))	NOTE. The order in which the above tests are conducted shall alternate from the previous production day (example: a dry gradation conducted in the morning will be conducted in the afternoon on the next production day and so forth).	
		The dry gradation and washed ignition oven test results shall be plotted on the same control chart.	
Asphalt	Content by Ignition	1 per half day of production	Illinois Modified AASHTO T 308
Air Voids	Bulk Specific Gravity of Gyratory Sample	1 per half day of production for first 2 days and 1 per day thereafter (first sample of the day)	Illinois Modified AASHTO T 312
	Maximum Specific Gravity of Mixture	i per day diereation (mocoampio et ano day)	Illinois Modified AASHTO T 209

Note 1. The Engineer may waive the ignition oven requirement for AC content if the aggregates to be used are known to have ignition AC content calibration factors which exceed 1.5 percent. If the ignition oven requirement is waived, other Department approved methods shall be used to determine the AC content.

During production, the ratio of minus 75 μ m (#200) sieve material to total asphalt cement shall be not less than 0.6 nor more than 1.2 and the moisture content of the mixture at discharge from the mixer shall not exceed 0.5 percent. If at any time the ratio of minus 75 μ m (#200) material to asphalt or moisture content of the mixture falls outside the stated limits, production of the mix shall cease. The cause shall be determined and corrective action satisfactory to the Engineer shall be initiated prior to resuming production.

During production, mixtures containing an anti-stripping additive will be tested by the Department for stripping according to Illinois Modified T 283. If the mixture fails to meet the TSR

criteria for acceptance, no further mixture will be accepted until the Contractor takes such action as is necessary to furnish a mixture meeting the criteria.

Construction Requirements

Lift Thickness.

(a) Binder and Surface Courses. The minimum compacted lift thickness for constructing bituminous concrete binder and surface courses shall be according to Table 4:

TABLE 4 - MINIMUM COMPACTED LIFT THICKNESS		
Mixture	Thickness, mm (in.)	
IL-9.5	32 (1 1/4)	
L-12.5	38 (1 1/2)	
IL-19.0	57 (2 1/4)	
IL-25.0	76 (3)	

(b) Leveling Binder. Mixtures used for leveling binder shall be as follows:

TABLE 5 – LEVELING BINDER		
Nominal, Compacted, Leveling	Mixture	
Binder Thickness, mm (in.)		
≤ 32 (1 1/4)	IL-9.5	
32 (1 1/4) to 50 (2)	IL 9.5 or IL-12.5	

Density requirements shall apply for leveling binder when the nominal, compacted thickness is 32 mm (1 1/4 in.) or greater for IL-9.5 mixtures and 38 mm (1 1/2 in.) or greater for IL-12.5 mixtures.

(c) Full-Depth Pavement. The compacted thickness of the initial lift of binder course shall be 100 mm (4 in.). The compacted thickness of succeeding lifts shall meet the minimums specified in Table 4 but not exceed 100 mm (4 in.).

If a vibratory roller is used for breakdown, the compacted thickness of the binder lifts, excluding the top lift, may be increased to 150 mm (6 in.) provided the required density is obtained.

(d) Bituminous Patching. The minimum compacted lift thickness for constructing bituminous patches shall be according to Table 4.

Control Charts/Limits. Control charts/limits shall be according to QC/QA Class I requirements, except density shall be plotted on the control charts within the following control limits:

TABLE 6. DENSITY CONTROL LIMITS				
Mixture	Parameter	Individual Test		
12.5 mm / 9.5 mm	Ndesign ≥ 90	92.0 - 96.0%		
12.5 mm / 9.5 mm	Ndesign < 90	92.5 - 97.4%		
19.0 mm / 25.0 mm	Ndesign ≥ 90	93.0 - 96.0%		
19.0 mm / 25.0 mm	Ndesign < 90	93.0 - 97.4%		

<u>Basis of Payment</u>. On resurfacing projects, this work will be paid for at the contract unit price per metric ton (ton) for BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, of the friction aggregate mixture and Ndesign specified, LEVELING BINDER (HAND METHOD), SUPERPAVE, of the Ndesign specified, LEVELING BINDER (MACHINE METHOD), SUPERPAVE, of the Ndesign specified, and BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, of the mixture composition and Ndesign specified.

On resurfacing projects in which polymer modifiers are required, this work will be paid for at the contract unit price per metric ton (ton) for POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, of the friction aggregate mixture and Ndesign specified, POLYMERIZED LEVELING BINDER (HAND METHOD), SUPERPAVE, of the Ndesign specified, POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, of the Ndesign specified, and POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, of the mixture composition and Ndesign specified.

On full-depth pavement projects, this work will be paid for at the contract unit price per square meter (square yard) for BITUMINOUS CONCRETE PAVEMENT, (FULL-DEPTH), SUPERPAVE, of the thickness specified.

On projects where widening is constructed and the entire pavement is then resurfaced, the binder for the widening will be paid for at the contract unit price per square meter (square yard) for BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, of the mixture composition, Ndesign, and thickness specified. The surface and binder used to resurface the entire pavement will be paid for according to the paragraphs above for resurfacing projects.

TEMPORARY EROSION CONTROL (BDE)

Effective: November 1, 2002

Revise the fifth sentence of the third paragraph of Article 280.04(a) of the Standard Specifications to read:

"This work may be constructed of hay or straw bales, extruded UV resistant high density polyethylene panels, erosion control blanket, mulch barrier, aggregate barriers, excavation, seeding, or mulch used separately or in combination, as approved, by the Engineer."

Add the following paragraphs after the fifth paragraph of Article 280.04(a) of the Standard Specifications.

"A ditch check constructed of extruded, UV resistant, high density polyethylene panels, "M" pins and erosion control blanket shall consist of the following materials:

Extruded, UV resistant, high density polyethylene panels shall have a minimum height of 250 mm (10 in.) and minimum length of 1.0 m (39.4 in.). The panels shall have a 51 mm (2 in.) lip along the bottom of the panel. Each panel shall have a single rib thickness of 4 mm (5/32 in.) with a 12 mm (1/2 in.) distance between the ribs. The panels shall have an average apparent opening size equal to 4.75 mm (No. 4) sieve, with an average of 30 percent open area. The tensile strength of each panel shall be 26.27 kN/m (1800 lb/ft) in the machine direction and 7.3 kN/m (500 lb/ft) in the transverse direction when tested according to ASTM D 4595.

"M" pins shall be at least 76 mm (3 in.) by 686 mm (27 in.), constructed out of deformed grade C1008 D3.5 rod (0.211 in. diameter). The rod shall have a minimum tensile strength of 55 MPa (8000 psi).

Erosion control blanket shall conform to Article 251.04.

A section of erosion control blanket shall be placed transverse to the flowline direction of the ditch prior to the construction of the polyethylene ditch check. The length of the section shall extend from the top of one side of the ditch to the top of the opposite side of the ditch, while the width of the section shall be one roll width of the blanket. The upstream edge of the erosion control blanket shall be secured in a 100 mm (4 in.) trench. The blanket shall be secured in the trench with 200 mm (8 in.) staples placed at 300 mm (1 ft) intervals along the edge before the trench is backfilled. Once the upstream edge of the blanket is secured, the downstream edge shall be secured with 200 mm (8 in.) staples placed at 300 mm (1 ft) intervals along the edge. The polyethylene ditch check shall be installed in the middle of the erosion control blanket, with the lip of each panel facing outward.

The ditch check shall consist of two panels placed back to back forming a single row. Placement of the first two panels shall be at the toe of the backslope or sideslope, with the panels extending across the bottom of the ditch. Subsequent panels shall extend both across the bottom of the ditch and up the opposite sideslope, as well as up the original backslope or sideslope at the distance determined by the Engineer.

The M pins shall be driven through the panel lips to secure the panels to the ground. M pins shall be installed in the center of the panels with adjacent panels overlapping the ends a minimum of 50 mm (2 in.). The pins shall be placed through both sets of panels at each overlap. They shall be installed at an interval of three M pins per one meter (39 in.) length of ditch check. The panels shall be wedged into the M pins at the top to ensure firm contact between the entire bottom of the panels and the soil."

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)

Effective: April 1, 1992 Revised: January 1, 2005

To ensure a prompt response to incidents involving the integrity of work zone traffic control, the Contractor shall provide a telephone number where a responsible individual can be contacted 24 hours-a-day.

When the Engineer is notified, or determines a traffic control deficiency exists, he/she will notify and direct the Contractor to correct the deficiency within a specified time. The specified time, which begins upon notification to the Contractor, will be from 1/2 hour to 12 hours based upon the urgency of the situation and the nature of the deficiency. The Engineer shall be the sole judge.

A deficiency may be any lack of repair, maintenance, or non-compliance with the traffic control plan. A deficiency may also be applied to situations where corrective action is not an option such as the use of non-certified flaggers for short term operations; working with lane closures beyond the time allowed in the contract; or failure to perform required contract obligations such as traffic control surveillance.

If the Contractor fails to correct a deficiency within the specified time, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency exists. The calendar day(s) will begin with notification to the Contractor and end with the Engineer's acceptance of the correction. The daily monetary deduction will be either \$1,000 or 0.05 percent of the awarded contract value, whichever is greater. For those deficiencies where corrective action was not an option this monetary deduction will be immediate.

In addition, if the Contractor fails to respond, the Engineer may correct the deficiency and the cost thereof will be deducted from monies due or which may become due the Contractor. This corrective action will in no way relieve the Contractor of his/her contractual requirements or responsibilities.

TRAFFIC SIGNAL GROUNDING (BDE)

Effective: April 1, 2006

Add the following paragraphs to the end of Article 807.01 of the Standard Specifications:

"The grounding system shall consist of a continuous, green, insulated conductor Type XLP, No. 6 AWG, stranded copper installed in raceways and bonded to each metal enclosure (handhole, post, mast arm pole, signal cabinet, etc.). All clamps shall be bronze or copper, UL approved.

A grounding cable with connectors shall be installed between each handhole cover and frame. The grounding cable shall be looped over cable hooks installed in the handholes and 1.5 m (5 ft) of slack shall be provided between the frame and cover.

All equipment grounding conductors shall terminate at the ground bus in the controller cabinet. The neutral conductor and the ground conductor shall be connected in the service installation. At no other point in the traffic signals system shall the neutral and ground conductors be connected."

Revise Article 873.02 of the Standard Specifications to read:

"873.02 Materials. Materials shall be according to the following.

Maria	Article/Section
item	n, Communication, Service, and Grounding 1076.04
(a) Electric Cable – Signal, Leau-II	1, Communication, Co. 1100, and 1011 1088.01"
(b) Conduit	1, Communication, Control, and 1088.01"

Revise the last sentence of Article 873.05 of the Standard Specifications to read:

"The type specified will indicate the method of installation and whether the electric cable is Service, Signal, Lead-in, Communication, or Grounding."

Revise the heading of Article 1076.04 of the Standard Specifications to read:

"1076.04 Electric Cable – Signal, Lead-in, Communication, Service, and Grounding."

Add the following paragraph to the end of Article 1076.04 of the Standard Specifications:

"(e) Grounding Conductor. The cross linked polyethylene (XLP) insulated conductor shall be according to Articles 1066.02 and 1066.03. The stranded copper conductor shall be No. 6 AWG and the insulation color shall be green."

TRAINING SPECIAL PROVISIONS (BDE) This Training Special Provision supersedes Section 7b of the Special Provision entitled "Specific Equal Employment Opportunity Responsibilities," and is in implementation of 23 U.S.C. 140(a).

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The contractor shall provide on-the-job training aimed at developing full journeyman in the type of trade or job classification involved. The number of trainees to be trained under this contract will be **2**. In the event the contractor subcontracts a portion of the contract work, he shall determine how many, if any, of the trainees are to be trained by the subcontractor, provided however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training.

The number of trainees shall be distributed among the work classifications on the basis of the contractor's needs and the availability of journeymen in the various classifications within the reasonable area of recruitment. Prior to commencing construction, the contractor shall submit to the Illinois Department of Transportation for approval the number of trainees to be trained in each selected classification and training program to be used. Furthermore, the contractor shall specify the starting time for training in each of the classifications. The contractor will be credited for each trainee employed by him on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees as provided hereinafter.

Training and upgrading of minorities and women toward journeyman status is a primary objective of this Training Special Provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g. by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees) to the extent such persons are available within a reasonable area of recruitment. The contractor will be responsible for demonstrating the steps that he has taken in pursuance thereof, prior to a determination as to whether the contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which he has successfully completed a training course leading to journeyman status or in which he has been employed as a journeyman. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used the contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the contractor and approved by the Illinois Department of Transportation and the Federal Highway Administration. The Illinois Department of Transportation and the Federal Highway Administration shall approve a program, if it is reasonably calculated to meet the equal employment opportunity obligations of the contractor and to qualify the average trainee for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau and training programs approved by not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather then clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the Illinois Department of Transportation and the Federal Highway Administration. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the contractor where he does one or more of the following and the trainees are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or pays the trainee's wages during the offsite training period.

No payment shall be made to the contractor if either the failure to provide the required training, or the failure to hire the trainee as a journeyman, is caused by the contractor and evidences a lack of good faith on the part of the contractor in meeting the requirement of this Training Special Provision. It is normally expected that a trainee will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program.

It is not required that all trainees be on board for the entire length of the contract. A contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Trainees will be paid at least 60 percent of the appropriate minimum journeyman's rate specified in the contract for the first half of the training period, 75 percent for the third quarter of the training period, and 90 percent for the last quarter of the training period, unless apprentices or trainees in an approved existing program are enrolled as trainees on this project. In that case, the appropriate rates approved by the Departments of Labor or Transportation in connection with the existing program shall apply to all trainees being trained for the same classification who are covered by this Training Special Provision.

The contractor shall furnish the trainee a copy of the program he will follow in providing the training. The contractor shall provide each trainee with a certification showing the type and length of training satisfactorily complete.

The contractor will provide for the maintenance of records and furnish periodic reports documenting his performance under this Training Special Provision.

METHOD OF MEASUREMENT The unit of measurement is in hours.

<u>BASIS OF PAYMENT</u> This work will be paid for at the contract unit price of 80 cents per hour for TRAINEES. The estimated total number of hours, unit price and total price have been included in the schedule of prices.

TRANSIENT VOLTAGE SURGE SUPPRESSION (BDE)

Effective: August 1, 2003

Revise the first paragraph of Article 1074.03(a)(4) of the Standard Specifications to read:

"(4) Transient Voltage Surge Suppression. The cabinet shall be provided with transient voltage surge suppression. Transient surge suppression unit leads shall be kept as short as possible and ground shall be made directly to the cabinet wall or ground plate as near as possible to the object being grounded. All transient surge suppression units shall be tested and certified as meeting this specification by an independent testing laboratory. One copy of each of the full testing report shall be submitted to the Engineer."

Revise Article 1074.03(a)(4)a. of the Standard Specifications to read:

"a. Surge Suppressor. The suppressor protecting the solid state controller, conflict monitor, and detection equipment shall consist of two stages: stage one which shall include a controller cabinet AC power protection assembly and stage two which shall include AC circuit protection.

The design of the stage one suppressor shall be modular and it shall be installed in such a way that it may be removed and replaced with the intersection under power and in flashing operation. It shall have a permanently mounted and wired base and a removable circuit package. The stage one suppressor shall have two LED failure indicators for power 'on' and suppression 'failure' and shall meet the following properties:

Stage One Suppressor				
Properties	Criteria			
"Plug-in" suppression module	12 pin connector assembly			
Clamp voltage	250 V at 20,000 A typical			
Response time	Less than 5 nanoseconds			
Maximum continuous service current	15 A at 120 VAC 60 Hz			
High frequency noise attenuation	At least 50 dB at 100,000 Hz			
Operating temperature	-40 °C (-40 °F) to 85 °C (185 °F)			

If the controller assembly includes a system telemetry module or remote intersection monitor, the status of the stage one suppressor shall be continuously and remotely monitored by an appropriate alarm circuit.

The stage two, high speed, solid state, transient suppressor shall protect the system from transient over voltage without affecting power at the load. It shall suppress transients of either polarity and from either direction (source or load). The suppressor shall have a visual "on" indicator lamp when the unit is operating normally. It shall also have a UL plastic enclosure, a four position terminal strip for

power connection, and it shall utilize silicon avalanche diode technology. The stage two suppressor shall meet the following properties:

Stage Two S	Suppressor
Properties	Criteria
Nominal service voltage	120 V at 50/60 Hz
Maximum voltage protection level	±330 V
Minimum voltage protection level	±220 V ±5%
Minimum surge current rating	700 A
Stand by power	Less than 0.5 Watts
Hot to neutral leakage current at 120 V	
RMS	
Maximum response time	5 nanoseconds
Operating and Storage temperature	-20 °C (-4 °F) to 50 °C (122 °F)"

80107m

TRUCK BED RELEASE AGENT (BDE)

Effective: April 1, 2004

Add the following sentence after the third sentence of the first paragraph of Article 406.14 of the Standard Specifications.

"In addition to the release agent, the Contractor may use a light scatter of manufactured sand (FA 20 or FA 21) evenly distributed over the bed of the vehicle."

VARIABLY SPACED TINING (BDE)

Effective: August 1, 2005

Revise the first sentence of the third paragraph of Article 420.11(e)(1) of the Standard Specifications to read:

"The metal comb shall consist of a single line of tempered spring steel tines variably spaced as shown in the table below and securely mounted in a suitable head."

Replace the sixth sentence of the third paragraph of Article 420.11(e)(1) of the Standard Specifications to read:

"The tining device shall be operated so as to a produce a pattern of grooves, 3 to 5 mm (1/8 in. to 3/16 in.) deep and 2.5 to 3.2 mm (1/10 in. to 1/8 in.) wide across the pavement. The tining device shall be operated at a 1:6 skew across the pavement for facilities with a posted speed limit of 55 mph or greater. The tining pattern shall not overlap or leave gaps between successive passes."

Add the following table after the third paragraph of Article 420.11(e)(1) of the Standard Specifications:

	Center to Cen	ter Spacings of Mo	etal Comb Tines			
Center to Center Spacings of Metal Comb Tines mm (in.) (read spacings left to right)						
34 (1 5/16)	36 (1 7/16)	47 (1 7/8)	54 (2 1/8)	48 (1 7/8)		
43 (1 11/16)	32 (1 1/4)	31 (1 1/4)	27 (1 1/16)	36 (1 7/16)		
29 (1 1/8)	46 (1 13/16)	21 (13/16)	43 (1 11/16)	23 (7/8)		
42 (1 5/8)	52 (2 1/16)	24 (15/16)	18 (11/16)	28 (1 1/8)		
40 (1 9/16)	34 (1 5/16)	27 (1 1/16)	26 (1)	25 (1)		
27 (1 1/16)	20 (13/16)	37 (1 7/16)	38 (1 1/2)	52 (2 1/16)		
51 (2)	45 (1 3/4)	37 (1 7/16)	43 (1 11/16)	53 (2 1/16)		
27 (1 1/16)	37 (1 7/16)	42 (1 5/8)	41 (1 5/8)	29 (1 1/8)		
43 (1 11/16)	45 (1 3/4)	44 (1 3/4)	30 (1 3/16)	37 (1 7/16)		
33 (1 5/16)	40 (1 9/16)	28 (1 1/8)	31 (1 1/4)	50 (1 15/16)		
34 (1 5/16)	45 (1 3/4)	20 (13/16)	45 (1 3/4)	50 (1 15/16)		
53 (2 1/16)	51 (2)	29 (1 1/8)	25 (1)	18 (11/16)		
53 (2 1/16)	18 (11/16)	38 (1 1/2)	51 (2)	40 (1 9/16)		
17 (11/16)	49 (1 15/16)	50 (1 15/16)	39 (1 9/16)	51 (2)		
36 (1 7/16)	36 (1 7/16)	38 (1 1/2)	46 (1 13/16)	29 (1 1/8)		
38 (1 1/2)	50 (1 15/16)	24 (15/16)	33 (1 5/16)			

WEIGHT CONTROL DEFICIENCY DEDUCTION (BDE)

Effective: April 1, 2001 Revised: August 1, 2002

The Contractor shall provide accurate weights of materials delivered to the contract for incorporation into the work (whether temporary or permanent) and for which the basis of payment is by weight. These weights shall be documented on delivery tickets which shall identify the source of the material, type of material, the date and time the material was loaded, the contract number, the net weight, the tare weight when applicable and the identification of the transporting vehicle. For aggregates, the Contractor shall have the driver of the vehicle furnish or establish an acceptable alternative to provide the contract number and a copy of the material order to the source for each load. The source is defined as that facility that produces the final material product that is to be incorporated into the contract pay items.

The Department will conduct random, independent vehicle weight checks for material sources according to the procedures outlined in the Documentation Section Policy Statement of the Department's Construction Manual and hereby incorporated by reference. The results of the independent weight checks shall be applicable to all contracts containing this Special Provision. Should the vehicle weight check for a source result in the net weight of material on the vehicle exceeding the net weight of material shown on the delivery ticket by 0.50% (0.70% for aggregates) or more, the Engineer will document the independent vehicle weight check and immediately furnish a copy of the results to the Contractor. No adjustment in pay quantity will be made. Should the vehicle weight check for a source result in the net weight of material shown on the delivery ticket exceeding the net weight of material on the vehicle by 0.50% (0.70% for aggregates) or more, the Engineer will document the independent vehicle weight check and immediately furnish a copy of the results to the Contractor. The Engineer will adjust the net weight shown on the delivery ticket to the checked delivered net weight as determined by the independent vehicle weight check.

The Engineer will also adjust the method of measurement for all contracts for subsequent deliveries of all materials from the source based on the independent weight check. The net weight of all materials delivered to all contracts containing this Special Provision from this source, for which the basis of payment is by weight, will be adjusted by applying a correction factor "A" as determined by the following formula:

$$A = 1.0 - \left(\frac{B - C}{B}\right)$$
; Where $A \le 1.0$; $\left(\frac{B - C}{C}\right) > 0.50\%$ (0.70% for aggregates)

Where A = Adjustment factor

B = Net weight shown on delivery ticket

C = Net weight determined from independent weight check

The adjustment factor will be applied as follows:

Adjusted Net Weight = A x Delivery Ticket Net Weight

The adjustment factor will be imposed until the cause of the deficient weight is identified and corrected by the Contractor to the satisfaction of the Engineer. If the cause of the deficient weight is not identified and corrected within seven (7) calendar days, the source shall cease delivery of all materials to all contracts containing this Special Provision for which the basis of payment is by weight.

Should the Contractor elect to challenge the results of the independent weight check, the Engineer will continue to document the weight of material for which the adjustment factor would be applied. However, provided the Contractor furnishes the Engineer with written documentation that the source scale has been calibrated within seven (7) calendar days after the date of the independent weight check, adjustments in the weight of material paid for will not be applied unless the scale calibration demonstrates that the source scale was not within the specified Department of Agriculture tolerance.

At the Contractor's option, the vehicle may be weighed on a second independent Department of Agriculture certified scale to verify the accuracy of the scale used for the independent weight check.

WORK ZONE TRAFFIC CONTROL DEVICES (BDE)

Effective: January 1, 2003 Revised: November 1, 2004

Add the following to Article 702.01 of the Standard Specifications:

"All devices and combinations of devices shall meet the requirements of the National Cooperative Highway Research Program (NCHRP) Report 350 for their respective categories. The categories are as follows:

Category 1 includes small, lightweight, channelizing and delineating devices that have been in common use for many years and are known to be crashworthy by crash testing of similar devices or years of demonstrable safe performance. These include cones, tubular markers, flexible delineators and plastic drums with no attachments. Category 1 devices shall be crash tested and accepted or may be self-certified by the manufacturer.

Category 2 includes devices that are not expected to produce significant vehicular velocity change but may otherwise be hazardous. These include drums and vertical panels with lights, barricades and portable sign supports. Category 2 devices shall be crash tested and accepted for Test Level 3.

Category 3 includes devices that are expected to cause significant velocity changes or other potentially harmful reactions to impacting vehicles. These include crash cushions, truck mounted attenuators and other devices not meeting the definitions of Category 1 or 2. Category 3 devices shall be crash tested and accepted for either Test Level 3 or the test level specified.

Category 4 includes portable or trailer-mounted devices such as arrow boards, changeable message signs, temporary traffic signals and area lighting supports. Currently, there is no implementation date set for this category and it is exempt from the NCHRP 350 compliance requirement.

The Contractor shall provide a manufacturer's self-certification letter for each Category 1 device and an FHWA acceptance letter for each Category 2 and Category 3 device used on the contract. The letters shall state the device meets the NCHRP 350 requirements for its respective category and test level, and shall include a detail drawing of the device."

Delete the third, fourth and fifth paragraphs of Article 702.03(b) of the Standard Specifications.

Delete the third sentence of the first paragraph of Article 702.03(c) of the Standard Specifications.

Revise the first sentence of the first paragraph of Article 702.03(e) of the Standard Specifications to read:

"Drums shall be nonmetallic and have alternating reflectorized Type AA or Type AP fluorescent orange and reflectorized white horizontal, circumferential stripes."

Add the following to Article 702.03 of the Standard Specifications:

"(h) Vertical Barricades. Vertical barricades may be used in lieu of cones, drums or Type II barricades to channelize traffic."

Delete the fourth paragraph of Article 702.05(a) of the Standard Specifications.

Revise the sixth paragraph of Article 702.05(a) of the Standard Specifications to read:

"When the work operations exceed four days, all signs shall be post mounted unless the signs are located on the pavement or define a moving or intermittent operation. When approved by the Engineer, a temporary sign stand may be used to support a sign at 1.2 m (5 ft) minimum where posts are impractical. Longitudinal dimensions shown on the plans for the placement of signs may be increased up to 30 m (100 ft) to avoid obstacles, hazards or to improve sight distance, when approved by the Engineer. "ROAD CONSTRUCTION AHEAD" signs will also be required on side roads located within the limits of the mainline "ROAD CONSTRUCTION AHEAD" signs."

Delete all references to "Type 1A barricades" and "wing barricades" throughout Section 702 of the Standard Specifications.

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

		Page
l.	General	1
II.	Nondiscrimination	1
III.	Nonsegregated Facilities	3
IV.	Payment of Predetermined Minimum Wage	3
V.	Statements and Payrolls	6
VI.	Record of Materials, Supplies, and Labor	7
VIII.	Safety: Accident Prevention	7
IX.	False Statements Concerning Highway Projects	7
Χ.	Implementation of Clean Air Act and Federal	
	Water Pollution Control Act	8
XI.	Certification Regarding Debarment, Suspension,	
	Ineligibility, and Voluntary Exclusion	8
XII.	Certification Regarding Use of Contract Funds for	
	Lobbying	9

ATTACHMENTS

A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

I. GENERAL

- 1. These contract provisions shall apply to all word performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
- 2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
- A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
- 4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2; Section IV, paragraphs 1, 2, 3, 4 and 7; Section V, paragraphs 1 and 2a through 2g.

- 5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6 and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
- 6. Selection of Labor: During the performance of this contract, the contractor shall not:
 - a. Discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
- b. Employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- 1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60 (and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seg.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of FFO:
 - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
 - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job-training."

- 2. EEO Officer: The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for an must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above

Page 1

agreement will be met, the following actions will be taken as a minimum:

- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- 4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
 - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employees referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish which such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
 - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
 - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
- 5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
 - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
 - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any

paid within each classification to deter

evidence of discriminatory wage practices.

- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

6. Training and Promotion:

- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
 - a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
 - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
 - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to

the SHA and shall set forth what efforts have been made to obtain such information.

- d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.
- 8. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
 - a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
 - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
 - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
- 9. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
 - a. The records kept by the contractor shall document the following:
 - The number of minority and non-minority group members and women employed in each work classification on the project;
 - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
 - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.

b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the

contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
- (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
- (2) the additional classification is utilized in the area by the construction industry:
- (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
- (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or

disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the question, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advised the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any cost reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- 4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

- (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not

be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable $\,$ wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

- (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits

Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which cases such trainees shall receive the same fringe benefits as apprentices.

(4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV. 2. Any worker listed on a payroll at a helper wage rate, who is not a helper under a approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. Apprentices and Trainees (Programs of the U.S. DOT):

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. Withholding:

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor or any other Federallyassisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainee's and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. Overtime Requirements:

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. Violation:

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. Withholding for Unpaid Wages and Liquidated Damages:

The SHA shall; upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

- 2. Payrolls and Payroll Records:
 - a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
 - b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan

or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period).

The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V.

This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all suncontractors.

- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
- (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
- (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
- (3) that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U/S. C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for

inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

- 1. On all federal-aid contracts on the national highway system, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
 - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
 - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.
 - c. Furnish, upon the completion of the contract, to the SHA resident engineer on /Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
- 2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

VII. SUBLETTING OR ASSIGNING THE CONTRACT

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in he contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted form the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
 - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
 - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a

whole and in general are to be limited to minor components of the overall contract.

- 2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract.

Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S. C. 333).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification,

distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more).

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
- 2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
- 3. That the firm shall promptly notify the SHA of the receipt of

any communication from the Director, Office of Federal Activities, EPA indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.

4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. Instructions for Certification - Primary Covered Transactions:

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible,""lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled

"Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded from Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Primary Covered Transactions

- 1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
 - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
 - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- 2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Covered Transactions:

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tie participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealing.
- Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily

excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

Certification Regarding Debarment, Suspension, Ineligibility And Voluntary Exclusion-Lower Tier Covered Transactions:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief. that:
 - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
 - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision

NOTICE

The most current **General Wage Determination Decisions** (wage rates) are available on the IDOT web site. They are located on the Letting and Bidding page at http://www.dot.il.gov/desenv/delett.html.

In addition, ten (10) days prior to the letting, the applicable Federal wage rates will be e-mailed to subscribers. It is recommended that all contractors subscribe to the Federal Wage Rates List or the Contractor's Packet through IDOT's subscription service.

PLEASE NOTE: if you have already subscribed to the Contractor's Packet you will automatically receive the Federal Wage Rates.

The instructions for subscribing are at http://www.dot.il.gov/desenv/subsc.html.

If you have any questions concerning the wage rates, please contact IDOT's Chief Contract Official at 217-782-7806.