

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303 03-00520-00-WR	WINNEBAGO	254	7
STA. TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% CITY		Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y080 TRAINING
				I000 BIT. CONCRETE	J000 P. C. CONCRETE			
60500060	REMOVING INLETS	EACH	46		46			
60600095	CLASS SI CONCRETE (OUTLET)	C. Y.	14.14		14.14			
60603500	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.06	FT.	2,398.6		2,398.6			
60604400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	FT.	3,420.0		3,420.0			
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FT.	20,569.4		20,569.4			
60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06	FT.	358.2		358.2			
60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24	FT.	525.8		525.8			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S. F.	42,448.3		42,448.3			
60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	S. F.	36,579.4		36,579.4			
67000400	ENGINEER'S FIELD OFFICE	CH. MO	18		18			
67100100	MOBILIZATION	L. SUM	1		1			
70103700	TRAFFIC CONTROL COMPLETE	L. SUM	1		1			
72300100	INSTALL EXISTING SIGN PANEL	S. F.	27				27	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	S. F.	584.0		584.0			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FT.	3,402		3,402			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FT.	459		459			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FT.	2,400		2,400			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FT.	50		50			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FT.	285		285			
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	S. F.	2,371.2		2,371.2			
* 78001110	PAINT PAVEMENT MARKING, LINE 4"	FT.	4,988.7		4,988.7			
* 78001140	PAINT PAVEMENT MARKING, LINE 8"	FT.	17,732.3		17,732.3			

* SPECIALTY ITEMS