

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303 03-00520-00-WR	WINNEBAGO	254	10
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% CITY				
				I000 BIT. CONCRETE	J000 P. C. CONCRETE	Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y080 TRAINING
*88800100	PEDESTRIAN PUSH-BUTTON	EACH	29				29	
*89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L. SUM	1				1	
*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FT.	830				830	
*89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5				5	
XX000968	INLETS, TYPE 700	EACH	27		27			
* XX002191	BARE COPPER WIRE, 1/C NO. 8	FT.	8,410				8,410	
* X0325151	REMOVE EXISTING LIGHT POLE	EACH	1				1	
* XX004270	ELECTRIC CABLE IN CONDUIT, 600V 1/C NO. 6 THHN/THWN	FT.	28,000			28,000		
* X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	3				3	
* X0320873	VIDEO VEHICLE DETECTOR	EACH	3				3	
X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15"	FT.	12		12			
X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24"	FT.	200		200			
X0322127	STORM SEWER (WATER MAIN REQUIREMENTS) 30"	FT.	77		77			
* X0322283	VIDEO SURVEILLANCE SYSTEM, COMPLETE	EACH	2				2	
* X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM, LINE SENSOR CABLE, NO. 20 3/C	FT.	3,353				3,353	
X0930400	STORM SEWER WATER MAIN 12"	FT.	1,354		1,354			
X0930500	STORM SEWER WATER MAIN 18"	FT.	597		597			
X4066436	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N70	TON	2,455	2,455				
X4066412	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N30	TON	1,131		1,131			
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	2,455	2,455				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,241				2,241	
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	30				30	

*SPECIALTY ITEMS