

F.A. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	03-00520-00-WR	WINNEBAGO	254	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# GENERAL NOTES

37. Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The Contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.
38. Only those trees designated by the Engineer or listed in the tree removal schedule shall be removed. The Contractor shall protect all remaining trees from damage due to his operations.
39. All elevations are referring to the U.S.G.S. mean sea level datum.
40. Abandoned underground utilities that conflict with construction shall be disposed of outside the limits of the right-of-way according to Article 202.03 of the Standard Specifications and as directed by the Engineer. This work will not be paid for separately but shall be included in the cost of EARTH EXCAVATION.
41. Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the sub number listed on the Index of sheets or the copy of the standard included in these plans.
42. All roadway radii shown on the plans are to the edge of pavement, unless otherwise indicated on the plans.
43. Existing road signs that interfere with construction will be relocated as directed by the Engineer. After the construction is complete, the Contractor will replace the signs as directed by the Engineer. This work will not be paid separately but shall be considered incidental to the contract and no compensation will be allowed.
44. Access to all commercial entrances shall be maintained at all times.
45. Before ordering storm sewers, catch basins, pipe culverts, pipe drains, and manholes, the contractor shall contact the engineer as to the exact length and quantity required.
46. Ten (10) ft. transitions shall be used to match proposed items of work to existing items in the field, unless otherwise shown. The transitions shall be paid for at the contract unit price for the proposed item of work specified.
47. Multi-use path signing shall be installed by the City of Rockford prior to completion of the path.

COMMITMENTS

None.