

DATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	D3-00520-00-WR	WINNEBAGO	254	33
STA. TO STA.				
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

550A0340 STORM SEWERS, CLASS A, TYPE 2, 12" FT.	55100900 STORM SEWER REMOVAL 18" FT.	60218400 MANHOLES, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID EACH
HARRISON AVE.	RT. STA. 203+98	MULFORD
44.28' RT. STA. 217+45.00-73.77' RT. STA. 217+45.00	LT. STA. 221+26-221+32	4.61' RT. STA. 16+93.82
76.41' RT. STA. 220+00.00-57.6' RT. STA. 219+99		55.72' LT. STA. 17+26.83
60.8' LT. STA. 221+25.2-57.85' LT. STA. 221+30.60		HARRISON AVE.
50.92' RT. STA. 225+43.86-86.56' RT. STA. 226+05.33		36.22' LT. STA. 211+30
36.83' RT. STA. 246+50.00-36.83' RT. STA. 248+60.00	55101200 STORM SEWER REMOVAL 24" FT.	39.4' LT. STA. 213+00.00
52.40' RT. STA. 269+21.30-39.88' RT. STA. 271+00.00	LT. STA. 206+41-206+92	76.16' LT. STA. 252+50.49
11.58' RT. STA. 282+11.00-4.57' RT. STA. 283+45.57		62.5' RT. STA. 262+94.00
4.57' RT. STA. 283+43.57-36' RT. STA. 286+56.2		64' LT. STA. 266+59.50
42.72' RT. STA. 284+00.00-38.72' RT. STA. 286+00.00		71.92' LT. STA. 280+52.16
38.72' RT. STA. 286+00.00-45.00' RT. STA. 286+56.20	55101400 STORM SEWER REMOVAL 30" FT.	45' RT. STA. 286+56.20
	LT. STA. 257+15	55.65' RT. STA. 286+81.00
TOAL 1,176		56.43' RT. STA. 288+08.76
		TOTAL 11
550A0360 STORM SEWERS, CLASS A, TYPE 2, 15" FT.	56101000 WATER MAIN 16" FT.	60221100 MANHOLES, TYPE A, 5' DIA., TYPE 1 FRAME, CLOSED LID EACH
HARRISON AVE.	LT. STA. 256+89.68-257+41.28	HARRISON AVE.
43.20' RT. STA. 221+94.00-60' RT. STA. 221+94.00		33.11' RT. STA. 206+51.74
36.83' LT. STA. 248+60.00-37.58' RT. STA. 250+60.00		38.80' RT. STA. 226+10.13
39.88' RT. STA. 271+00.00-42.83' RT. STA. 273+00.00		37.34' LT. STA. 226+97.40
42.83' RT. STA. 273+00.00-46.70' RT. STA. 275+00.00		37.66' LT. STA. 230+22.48
46.70' RT. STA. 275+00.00-54.83' RT. STA. 276+75.00		37.66' LT. STA. 232+27.95
54.83' RT. STA. 276+75.00-54.83' RT. STA. 278+63.00		60.45' LT. STA. 244+19.00
TOTAL 949	56400300 FIRE HYDRANTS TO BE ADJUSTED EACH	75.20' LT. STA. 250+76.25
	HARRISON AVENUE	6.50' LT. STA. 278+63.04
	54.0' LT. STA. 210+60	FOREST VIEW
	52.0' LT. STA. 202+27.50	23.08' RT. STA. 507+85.43
	65.0' LT. STA. 226+22	22.78' LT. STA. 507+85.55
	59.9' LT. STA. 238+54	
	MULFORD 65.0' LT. STA. 14+85	TOTAL 10
	56400400 FIRE HYDRANTS TO BE RELOCATED EACH	60221200 MANHOLES, TYPE A, 5' DIA., TYPE 3 FRAME & GRATE EACH
	HARRISON AVENUE	FOREST VIEW
	72' LT. STA. 286+31	18.40' LT. STA. 507+93.40
		TOTAL 1
	60107600 PIPE UNDERDRAINS 4" FT.	60223800 MANHOLES, TYPE A, 6' DIA., TYPE 1 FRAME, CLOSED LID EACH
	HARRISON AVE.	HARRISON AVE.
	RT. STA. 206+25	40.45' RT. STA. 206+24.53
	LT. STA. 206+41	TOTAL 1
	RT. STA. 211+31	
	LT. STA. 211+31	
	LT. STA. 215+32	60236200 INLETS, TYPE A, TYPE 8 GRATE EACH
	RT. STA. 215+55	HARRISON AVE.
	LT. STA. 220+00	73.77' RT. STA. 217+45.00
	RT. STA. 220+00	76.41' RT. STA. 220+00.00
	LT. STA. 225+40	59.80' LT. STA. 226+96.60
	RT. STA. 225+40	66.60' LT. STA. 271+00.00
	LT. STA. 238+48	49.97' RT. STA. 288+08.80
	RT. STA. 239+50	TOTAL 5
	RT. STA. 243+50	
	LT. STA. 244+24	60236800 INLETS, TYPE A, TYPE 11 FRAME AND GRATE EACH
	LT. STA. 250+60	MULFORD
	RT. STA. 250+60	5.58' RT. STA. 17+27.00
	LT. STA. 257+08	5.58' RT. STA. 18+31.00
	RT. STA. 257+08	3.57' RT. STA. 19+75.00
	LT. STA. 260+00	HARRISON AVE.
	RT. STA. 260+00	11.58' LT. STA. 277+50.00
	LT. STA. 271+00	11.58' RT. STA. 282+11.00
	RT. STA. 271+00	4.57' RT. STA. 283+43.57
	LT. STA. 276+75	TOTAL 6
	LT. STA. 277+00	
	RT. STA. 284+00	
	LT. STA. 284+00	
	LT. STA. 288+00	
	TOTAL 1,025	
550A0380 STORM SEWERS, CLASS A, TYPE 2, 18" FT.		
HARRISON AVE.		
41.96' LT. STA. 266+72.00-37.58' LT. STA. 269+00.00		
37.58' LT. STA. 269+00.00-37.58' LT. STA. 271+00.00		
37.58' LT. STA. 271+00.00-37.58' LT. STA. 273+00.00		
37.58' LT. STA. 271+00.00-60.60' LT. STA. 271+00.00		
TOTAL 626		
550A0410 STORM SEWERS, CLASS A, TYPE 2, 24" FT.		
HARRISON AVE.		
37.58' RT. STA. 250+60.00-47.52' RT. STA. 252+75.00		
TOTAL 210		
550A0430 STORM SEWERS, CLASS A, TYPE 2, 30" FT.		
HARRISON AVE.		
48.58' RT. STA. 253+58.00-49.58' RT. STA. 255+30.00		
49.58' RT. STA. 255+30.00-75.29' RT. STA. 255+81.04		
75.29' RT. STA. 255+81.04-75.67' RT. STA. 256+54.09		
TOTAL 287		
55100500 STORM SEWER REMOVAL 12" FT.		
LT. STA. 215+10		
RT. STA. 215+10		
RT. STA. 221+94		
LT. STA. 223+28		
RT. STA. 225+44-226+13		
RT. STA. 226+13-226+86		
TOTAL 237		
55100700 STORM SEWER REMOVAL 15" FT.		
LT. STA. 221+93		
RT. STA. 221+94		
LT. STA. 221+32-221+61		
RT. STA. 237+46-238+90		
LT. STA. 252+50-252+64		
RT. STA. 255+30-255+81		
FOREST VIEW STA. 507+85-507+93		
TOTAL 321		