# TRAFFIC SIGNAL SCHEDULE OF QUANTITIES

| CODE NO. | DESCRIPTION | UNIT | TOTAL | HOLMES ST. | FOREST VIEW RD. | EAST ROCK DR. | STOWMARKET AVE. | MULFORD RD. |
|---|---|---|---|---|---|---|---|---|
| 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 42 | | 9 | 3 | 12 | 18 |
| 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 10.5 | | 3.5 | 3.5 | | 3.5 |
| 87800415 | CONCRETE FOUNDATION, TYPE E, 36 INCH DIA. | FOOT | 211 | 13 | 56 | 52 | 30 | 60 |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 4 | | | | 4 | |
| 88200310 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC | EACH | 72 | 3 | 16 | 15 | 14 | 24 |
| 88700200 | LIGHT DETECTOR | EACH | 15 | 1 | 4 | 4 | 2 | 4 |
| 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 3 | | 1 | 1 | | 1 |
| 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 29 | 4 | 6 | 2 | 8 | 9 |
| 89000200 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | | | | |
| 89502300 | REMOVE ELECTRIC CABLE FROM CONDUIT | FOOT | 830 | 830 | | | | |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 5 | 1 | 1 | 1 | 1 | 1 |
| X0320872 | VIDEO VEHICLE DETECTION SYSTEM | EACH | 3 | | 1 | 1 | | 1 |
| X0320873 | VIDEO VEHICLE DETECTOR | EACH | 3 | 1 | | | 2 | |
| X0324085 | EMERGENCY VEHICLE PRIORITY SYSTEM, LINE SENSOR CABLE, NO. 20 3/C | FOOT | 3,353 | 188 | 790 | 754 | 601 | 1,020 |
| X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 2,241 | 300 | 425 | 414 | 440 | 662 |
| X8801310 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 30 | 2 | 7 | 10 | 3 | 8 |
| X8801395 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 27 | 1 | 4 | 2 | 8 | 12 |
| X8801400 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED | EACH | 14 | | 5 | 3 | 2 | 4 |
| X8801447 | SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 4 | | | | | 4 |
| X8810395 | PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED | EACH | 12 | 2 | 3 | 2 | 2 | 3 |
| X8810495 | PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED | EACH | 7 | 1 | 1 | | 3 | 2 |
| X8810630 | PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED | EACH | 2 | | 1 | | | 1 |
| XX002191 | BARE COPPER WIRE, 1/C NO. 8 | FOOT | 8,410 | 1,827 | 1,922 | 1,905 | 1,827 | 929 |
| | FIBER OPTIC CABLE IN CONDUIT, 48 FIBER SINGLE MODE AND 24 FIBER MULTIMODE | FOOT | 8,410 | 1,827 | 1,922 | 1,905 | 1,827 | 929 |
| X0322283 | VIDEO SURVEILLANCE SYSTEM, COMPLETE | EACH | 2 | 1 | | | 1 | |

**TRAFFIC SIGNAL SCHEDULE OF QUANTITIES**