

SUMMARY OF QUANTITIES

| | | | | |
|---------------------|--------------|------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 669 | 11W-3,RS-8,* | TAZEWELL | 442 | 11 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| * 11BR-1, 11BR-2 | | | | |

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | ACF | | HSIP | ACF | | | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|--|-------|------------------------------|--|--|--|--|--|------------------------------------|------------------------|--|--|--|--|--|
| CODE NO | ITEM | UNIT | | ROADWAY 20% STATE 80% FED 1000-2A | ROADWAY SAFETY 10% STATE 90% FED 1000-1A | STRUCTURE 090-0172 20% STATE 80% FED X071-2A | STRUCTURE 090-0174 20% STATE 80% FED X020-2A | IMPACT ATTENUATORS 20% STATE 80% FED SFTY-3N | WATER MAIN 100% VILLAGE Y060 | | | | | | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 2347 | 1336 | | 1011 | | | | | | | | | |
| 28100125 | STONE RIPRAP, CLASS B3 | SQ YD | 852 | 814 | 38 | | | | | | | | | | |
| 28200200 | FILTER FABRIC | SQ YD | 2347 | 1336 | | 1011 | | | | | | | | | |
| 28500100 | FABRIC FORMED CONCRETE REVETMENT MATS | SQ YD | 1331 | 28 | 211 | | 1092 | | | | | | | | |
| 31101900 | SUB-BASE GRANULAR MATERIAL, TYPE C | TON | 4795 | 3354 | 1441 | | | | | | | | | | |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 197 | 84 | 113 | | | | | | | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 43.3 | 27.6 | 15.7 | | | | | | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 270 | 172 | 98 | | | | | | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | | | | | | | | | | |
| 40600980 | BITUMINOUS SURFACE REMOVAL - BUTT JOINT | SQ YD | 552 | 187 | 365 | | | | | | | | | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 528 | 288 | 240 | | | | | | | | | | |
| 40800040 | INCIDENTAL BITUMINOUS SURFACING | TON | 56 | | 50 | | | | 6 | | | | | | |
| 42001165 | BRIDGE APPROACH PAVEMENT | SQ YD | 1086 | 570 | 516 | | | | | | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 1194 | 626 | 568 | | | | | | | | | | |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 192 | | 192 | | | | | | | | | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 188 | 188 | | | | | | | | | | | |
| 44000006 | BITUMINOUS SURFACE REMOVAL 1 1/2" | SQ YD | 48393 | 35520 | 12873 | | | | | | | | | | |
| 44000007 | BITUMINOUS SURFACE REMOVAL 2" | SQ YD | 5442 | 1175 | 4267 | | | | | | | | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 9650 | 1535 | 8115 | | | | | | | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 676 | 393 | 235 | | | | 48 | | | | | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 3081 | 3081 | | | | | | | | | | | |
| 44001430 | BITUMINOUS SHOULDER REMOVAL | SQ YD | 1028 | 1028 | | | | | | | | | | | |
| 44003100 | MEDIAN REMOVAL | SQ FT | 6314 | 3785 | 2529 | | | | | | | | | | |
| 44003510 | MEDIAN REMOVAL PARTIAL DEPTH | SQ FT | 12298 | 7980 | 4318 | | | | | | | | | | |
| 44004400 | PAVEMENT REMOVAL (SPECIAL) | SQ YD | 603 | 386.5 | 216.5 | | | | | | | | | | |
| 44201389 | CLASS C PATCHES, TYPE II, 13 INCH | SQ YD | 1132 | 644 | 488 | | | | | | | | | | |
| 44201394 | CLASS C PATCHES, TYPE III, 13 INCH | SQ YD | 46 | | 46 | | | | | | | | | | |
| 44201396 | CLASS C PATCHES, TYPE IV, 13 INCH | SQ YD | 215 | 138 | 77 | | | | | | | | | | |
| 44201737 | CLASS D PATCHES, TYPE I, 8 INCH | SQ YD | 8 | | 8 | | | | | | | | | | |

(X) SPECIALTY ITEM