

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 11BR-1, 11BR-2				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	ACF		HSIP	← ACF →			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 20% STATE 80% FED 1000-2A	ROADWAY SAFETY 10% STATE 90% FED 1000-1A	STRUCTURE 090-0172 20% STATE 80% FED X071-2A	STRUCTURE 090-0174 20% STATE 80% FED X020-2A	IMPACT ATTENUATORS 20% STATE 80% FED SFTY-3N	WATER MAIN 100% VILLAGE Y060					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	120		120									
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	25866	17158	8708									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	635	443	192									
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	15329	11105	4224									
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2			1	1							
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1										
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1									
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1									
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1										
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1										
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1									
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1		1									
50102400	CONCRETE REMOVAL	CU YD	3.0	3.0										
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	2	2									
50105220	PIPE CULVERT REMOVAL	FOOT	944	321	623									
50200100	STRUCTURE EXCAVATION	CU YD	467			136	331							
50300100	FLOOR DRAINS	EACH	26			18	8							
50300225	CONCRETE STRUCTURES	CU YD	482.4			256.6	225.8							
50300255	CONCRETE SUPER STRUCTURES	CU YD	680.3			364	316.3							
50300260	BRIDGE DECK GROOVING	SQ YD	1951			1253	698							
50300300	PROTECTIVE COAT	SQ YD	2187			1399	788							
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1								
50500505	STUD SHEAR CONNECTORS	EACH	3690			3690								
50800105	REINFORCEMENT BARS	POUND	168		168									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	214,710			106,790	107,920							
51201100	FURNISHING METAL PILE SHELLS 14"	FOOT	8692			5339	3353							
51202600	DRIVING AND FILLING SHELLS	FOOT	8692			5339	3353							
51203200	TEST PILE METAL SHELLS	EACH	5			3	2							
51205200	TEMPORARY SHEET PILING	SQ FT	2409			1352	1057							

(X) SPECIALTY ITEM

PLOT DATE = 4/19/2006
 FILE NAME = c:\projects\24\pilot\phase_11\masc.dgn
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = SHEET