

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8	TAZEWELL	442	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• 11BR-1, 11BR-2

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	ACF		HSIP		ACF			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 20% STATE 80% FED 1000-2A	ROADWAY SAFETY 10% STATE 90% FED 1000-1A	STRUCTURE 090-0172 20% STATE 80% FED X071-2A	STRUCTURE 090-0174 20% STATE 80% FED X020-2A	IMPACT ATTENUATORS 20% STATE 80% FED SFTY-3N	WATER MAIN 100% VILLAGE Y060						
51500100	NAME PLATES	EACH	2			1	1								
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	240	176	64										
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	24		24										
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	192	192											
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	1	2										
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5	3	2										
54213873	STEEL END SECTIONS 18"	EACH	7	7											
54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1		1										
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2		2										
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	1		1										
54248510	CONCRETE COLLAR	CU YD	3.1		3.1										
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	94		94										
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	72	72											
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1318		1318										
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	672		672										
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	883		883										
55100900	STORM SEWER REMOVAL 18"	FOOT	11		11										
55101600	STORM SEWER REMOVAL 36"	FOOT	40	40											
X 56100800	WATER MAIN 10"	FOOT	531							531					
X 56200300	WATER SERVICE LINE 1"	FOOT	100							100					
X 56201400	CORPORATION STOPS 1"	EACH	2							2					
X 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2							2					
X 56400600	FIRE HYDRANTS	EACH	6							6					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	208.8			142	66.8								
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	502			250	252								
60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	1	1										

(X) SPECIALTY ITEM