

| F.A.P. RTE. | SECTION      | COUNTY   | TOTAL SHEETS | SHEET NO. |
|-------------|--------------|----------|--------------|-----------|
| 669         | 11W-3,RS-8,* | TAZEWELL | 442          | 41        |

|                     |                           |
|---------------------|---------------------------|
| STA.                | TO STA.                   |
| FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT |
| • 11BR-1, 11BR-2    |                           |

FOR INFORMATION ONLY

| LOCATION                  | EARTH EXCAVATION (CUT) | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE | EMBANKMENT (FILL) | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) | FILL REQUIRED PER LOCATION |
|---------------------------|------------------------|---|-------------------|---|----------------------------|
|                           | CU YD                  | CU YD                                   | CU YD             | CU YD                                       | CU YD                      |
| IL 29                     |                        |   |                   |   |                            |
| STA. 245+00 TO 250+30     | 251                    | 188.25                                  | 131               | 57.25                                       |                            |
| STA. 250+65 TO 251+80     | 40                     | 30                                      | 46                | -16   | 16                         |
| STA. 251+80 TO 262+24     | 1480                   | 1110                                    | 786               | 324   |                            |
| STA. 262+24 TO 266+45     | 509                    | 381.75                                  | 404               | -22.25                                      | 22.25                      |
| STA. 266+45 TO 271+15     | 799                    | 599.25                                  | 375               | 224.25                                      |                            |
| STA. 271+15 TO 275+22     | 549                    | 411.75                                  | 341               | 70.75                                       |                            |
| STA. 276+45 TO 280+00     | 593                    | 444.75                                  | 60                | 384.75                                      |                            |
| STA. 280+00 TO 282+00     | 577                    | 432.75                                  | 620               | -187.25                                     | 210.5                      |
| STA. 282+00 TO 301+00     | 2911                   | 2183.25                                 | 6997              | -4813.75                                    | 4868                       |
| STA. 303+00 TO 313+00     | 3786                   | 2839.5                                  | 1374              | 1465.5                                      |                            |
| STA. 313+00 TO 327+00     | 4039                   | 3029.25                                 | 3733              | -703.75                                     | 852.25                     |
| STA. 327+00 TO 335+84     | 1044                   | 783                                     | 1028              | -245  |                            |
| LICK CREEK CHANNEL        |                        |   |                   |   |                            |
| STA. 10+63.55 TO 12+00.44 | 0                      | 0                                       | 316               | -316  | 316                        |
| LICK CREEK                |                        |   |                   | 0   |                            |
| STA. 10+00 TO 10+83.55    | 38                     | 28.5                                    | 28                | 0.5   |                            |
| IDNR                      |                        |   |                   | 0   |                            |
| STA. 10+00 TO 10+80       | 5                      | 3.75                                    | 566               | -562.25                                     | 562.25                     |
| VILLAGE RT.               |                        |   |                   | 0   |                            |
| STA. 30+00 TO 30+90       | 158                    | 118.5                                   | 0                 | 118.5                                       |                            |
| VILLAGE LT.               |                        |   |                   | 0   |                            |
| STA. 20+00 TO 20+70       | 183                    | 137.25                                  | 0                 | 137.25                                      |                            |
| ELM ST.                   |                        |   |                   | 0   |                            |
| STA. 70+39 TO 71+35       | 36                     | 27                                      | 103               | -76   | 76                         |
| TOTAL                     | 16998                  | 12749                                   | 16908             | -4160                                       |                            |

| SPECIAL EXCAVATION   |       |
|----------------------|-------|
| LOCATION             | CU YD |
| STA. 279+95 - 282+05 | 200.5 |
| STA. 302+94 - 308+05 | 649.7 |
| STA. 312+95 - 317+05 | 394.8 |
| TOTAL                | 1245  |

| CHANNEL EXCAVATION    |       |
|-----------------------|-------|
| LOCATION              | CU YD |
| LICK CREEK            |       |
| STA. 10+00 - 13+13.55 | 1667  |
| LITTLE LICK CREEK     | 862   |
| TOTAL                 | 2529  |

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES