

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	60
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 11BR-1, 11BR-2				

DUCTILE IRON SCHEDULE

LOCATION	DUCTILE IRON WATER MAIN FITTINGS 8 X 6 TEE	DUCTILE IRON WATER MAIN FITTINGS 8" TEE	DUCTILE IRON WATER MAIN FITTINGS 8" 45° BEND	DUCTILE IRON WATER MAIN FITTINGS 6" 90° BEND	DUCTILE IRON WATER MAIN PIPE PRESSURE CL., 350, 8"	DUCTILE IRON WATER MAIN FITTINGS 8" 22.5° BEND
WATER MAIN	EACH	EACH	EACH	EACH	FOOT	EACH
STA. 283+00 LT						1
STA. 283+35 LT						1
STA. 301+30 LT			1			
STA. 301+36 LT			1			
STA. 301+61 LT						1
STA. 301+00 - 302+50					160	
STA. 302+15 LT			1			
STA. 302+31 LT						1
STA. 303+47 LT						1
STA. 303+75 LT						1
STA. 305+00 LT	1					
STA. 307+00 LT						1
STA. 307+56 LT						1
STA. 312+00 LT						1
STA. 312+25 LT						1
STA. 317+70 LT		1				
STA. 318+00 LT						1
STA. 318+50 LT						1
STA 323+00 LT	1					
STA. 327+00 LT						1
STA. 327+15 LT						1
STA 327+50 LT	1					
STA 332+00 LT	1					
STA. 302+20 LT						1
IL 29 / IL 98	2		2	1		
WEST LANE	1					
TOTAL	7	1	5	1	160	15

VALVE SCHEDULE

LOCATION	VALVE VAULTS, TY. A, 4'-DIA. & CL. LID	VALVE BOXES, 6"	GATE VALVES, 6"	GATE VALVES, 8"	WATER VALVE BOXES TO BE ABANDONED
	EACH	EACH	EACH	EACH	EACH
WATER MAIN					
STA. 292+50 LT		1		1	
STA. 301+00 LT	1	1		1	
STA. 302+50 LT		1		1	
STA. 305+00 LT		1	1		
STA. 306+75 LT		1		1	
STA. 317+00 LT		1		1	
STA. 317+65 LT					1
WEST LANE		2	1	1	
STA. 323+00 LT		1	1		
STA. 325+50 LT		1		1	
STA. 327+50 LT		1	1		
STA. 332+00 LT		1	1		
IL 29 / IL 98		3	2	1	
TOTAL	1	15	7	8	1

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES