


April 12, 2006

C:\234\2006_Job\234\001\234_Canton Ash St. & 110 Ave (Phase I) Pwr. Eng. Sec. 06-00093-01-RS-Construction Plans\10-Summary of Quantities.dwg

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
* 04-00093-00-RS		FULTON	11	4
* FAU 6883 & 6904			CONTRACT NO. 89378	

SUMMARY OF QUANTITIES					TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
SPECIALTY ITEMS	CODE NO.	ITEM	UNIT	1000		
	28000500	INLET AND PIPE PROTECTION	EACH	16	16	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	613	613	
	40600300	AGGREGATE (PRIME COAT)	TON	21	21	
	40600400	MIXTURE FOR CRACKS, JOINTS, & FLANGEWAYS	TON	13	13	
	40600990	TEMPORARY RAMP	SQ. YD.	405	405	
	40800040	INCIDENTAL BITUMINOUS SURFACING	TON	10	10	
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	1740	1740	
	42400800	DETECTABLE WARNINGS	SQ. FT.	72	72	
	44000075	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	SQ. YD.	13279	13279	
	44000100	PAVEMENT REMOVAL	SQ. YD.	26	26	
	44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	4229	4229	
	44000600	SIDEWALK REMOVAL	SQ. FT.	1812	1812	
	44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ. YD.	19933	19933	
	60255500	MANHOLES TO BE ADJUSTED	EACH	37	37	
	60260100	INLETS TO BE ADJUSTED	EACH	10	10	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	9	
	60604400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	FOOT	4229	4229	
	67100100	MOBILIZATION	L SUM	1.0	1.0	
	70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501	L SUM	1.0	1.0	
	70102640	TRAFFIC CONTROL & PROTECTION, STANDARD 701801	L SUM	1.0	1.0	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1372	1372	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	175	175	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE, 4"	FOOT	1440	1440	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE, 6"	FOOT	356	356	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE, 24"	FOOT	133	133	
	X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ. YD.	198	198	
	X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE "D", N50	TON	1698	1698	
	XX003643	BASE REPAIR, SPECIAL	SQ. YD.	194	194	

		1670 EAST ASH STREET CANTON, ILLINOIS 61520 PH. (309) 647-7851 FAX (309) 647-6155
SUMMARY OF QUANTITIES		
FOR: CITY OF CANTON, ILLINOIS		
REVISIONS DESIGNED CHECKED DRAWN CHECKED	DATE 04/14/06 -- -- JAM GEM	PROJECT NO. 234-08013A DRAWING NO. 1 SHEET 1 OF 1