

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|---------|--------|--------------|-----------|
| 709 | * | ** | 72 | 17 |

SCHEDULE OF QUANTITIES

* 113(RS-5,BR) & 114RS-2
 ** CHAMPAIGN AND VERMILION
 CONTRACT NO. 90864

*28100107 STONE RIPRAP, CLASS A4

CHAMPAIGN COUNTY

| STATION | TO | STATION | SQ YD |
|--------------|----|-----------|--------------|
| RT 484+10 | | RT 485+30 | 156.0 |
| LT 484+55 | | LT 485+50 | 124.0 |
| <u>TOTAL</u> | | | <u>280.0</u> |

* THE ENGINEER MAY MODIFY LOCATIONS OF STONE RIPRAP, CLASS A4 BASED ON FIELD CONDITIONS

31101200 SUB-BASE GRANULAR MATERIAL, TYPE B, 4"

CHAMPAIGN COUNTY

| | STATION | TO | STATION | SQ YD |
|--------------|--------------|----|--------------|-------------|
| PARK AVE | LT 9+59.43 | | LT 9+86.7 | 11.0 |
| PARK AVE | RT 9+59.55 | | RT 9+86.7 | 17.0 |
| PENNFIELD RD | LT 803+35.89 | | LT 3+24.20 | 26.0 |
| PENNFIELD RD | RT 2+07.77 | | RT 804+54.16 | 23.0 |
| <u>TOTAL</u> | | | | <u>77.0</u> |

40600980 BITUMINOUS SURFACE REMOVAL-BUTT JOINT

CHAMPAIGN COUNTY

| | STATION | TO | STATION | LENGTH FT. | WIDTH FT. | AREA SQ. YDS. |
|--------------|---------|----|---------|------------|-----------|---------------|
| | 423+35 | | 423+90 | 55.0 | 24.0 | 146.7 |
| PARK AVE | 9+37 | | 9+52 | 15.0 | 22.0 | 36.7 |
| PENNFIELD RD | 802+68 | | 802+98 | 30.0 | VAR | 125.0 |
| PENNFIELD RD | 804+66 | | 804+96 | 30.0 | VAR | 83.3 |

SUBTOTAL 391.6

USE 392.0

VERMILION COUNTY

| | | | | | | |
|--|----------|--|----------|------|-------|-------|
| | 67+89 | | 67+84 | 45.0 | 26.0 | 130.0 |
| | 70+76 | | 71+21 | 45.0 | 26.0 | 130.0 |
| | 120+55 | | 121+00 | 45.0 | 24.0 | 120.0 |
| | 126+00 | | 126+45 | 45.0 | 24.0 | 120.0 |
| | 162+37.6 | | 162+48.6 | 11.0 | 166.0 | 203.0 |

SUBTOTAL 703.0

USE 703.0

TOTAL 1095.0

* 40600990 TEMPORARY RAMPS

CHAMPAIGN COUNTY

| | STATION | LENGTH FOOT | WIDTH FOOT | AREA SQ YD |
|--------------|---------|-------------|------------|------------|
| | 423+00 | 24 | 5 | 13.3 |
| PARK AVE. | 9+37 | 22 | 5 | 12.2 |
| PENNFIELD RD | 802+68 | 22 | 5 | 12.2 |
| PENNFIELD RD | 804+96 | 22 | 5 | 12.2 |

SUB-TOTAL 50

VERMILION COUNTY

| | | | | |
|--|----------|-----|---|------|
| | 67+84 | 26 | 5 | 14.4 |
| | 70+76 | 26 | 5 | 14.4 |
| | 121+00 | 24 | 5 | 13.3 |
| | 126+00 | 24 | 5 | 13.3 |
| | 162+48.6 | 150 | 5 | 83.3 |

SUB-TOTAL 139

TOTAL 189

* TEMPORARY RAMPS SHALL BE USED AT LOCATIONS SHOWN IN PLANS. IT IS THE INTENTION TO USE TEMPORARY RAMPS FOR MAJOR SIDE ROADS AND LOCATIONS WHERE BITUMINOUS SURFACE REMOVAL-BUTT JOINTS ARE CONSTRUCTED. TEMPORARY RAMPS SHALL NOT BE USED AT MINOR TOWNSHIP ROADS, PRIVATE ENTRANCES, AND COMMERCIAL ENTRANCES.