

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	*	**	72	19

SCHEDULE OF QUANTITIES

* 113(RS-5,BR) & 114RS-2
 ** CHAMPAIGN AND VERMILION
 CONTRACT NO. 90864

40800040 INCIDENTAL BITUMINOUS SURFACING (CONTD.)

STATION	AREA SQ YD	AVERAGE THICKNESS INCHES	MAILBOX TONS	FIELD ENTR. TONS	PRIV ENT. W/ MBTO TONS	PRIVATE ENTR. TONS	COMMER. ENTR. TONS	SIDEROAD TONS	40800010	40800030
									BIT MATLS PR CT GALLONS	AGG PR CT TONS
<u>CHAMPAIGN COUNTY (CONTINUED)</u>										
RT 2+67.31 (PENNFIELD RD)	600	1.875		63.0				63.0	60.0	1.2
LT 2+67.31 (PENNFIELD RD)	686	1.875		72.0				72.0	68.6	1.4
RT 4+21.37	98	1.875							9.8	0.2
RT 5+26.95	97	1.875							9.7	0.2
RT 6+43.35	72	1.875							7.2	0.1
RT 15+10	17	1.875		1.8					1.7	0.03
LT 23+00	43	1.875				4.5			4.3	0.1
RT 23+70	17	1.875		1.8					1.7	0.03
LT 24+50	43	1.875				4.5			4.3	0.1
RT 29+20	17	1.875		1.8					1.7	0.03
LT 39+00	17	1.875		1.8					1.7	0.03
RT 54+00	17	1.875		1.8					1.7	0.03
<u>CHAMPAIGN COUNTY SUBTOTAL</u>			10.8	198.1	20.7	29.6	56.6	192.6	345.2	7.2
<u>USE</u>			11.0	198.0	21.0	30.0	41.0	193.0	345.0	7.0
<u>VERMILION COUNTY</u>										
LT 57+00	17	1.875		1.8					1.7	0.03
RT 57+12	43	1.875				4.5			4.3	0.1
RT 73+00	17	1.875				1.8			1.7	0.03
RT 78+83	43	1.875				4.5			4.3	0.1
RT 80+24	32	1.875	3.4						3.2	0.1
LT 80+50	43	1.875				4.5			4.3	0.1
RT 81+00	17	1.875		1.8		1.8			1.7	0.03
RT 82+50	63	1.875			6.6	6.6			6.3	0.1
RT 93+25	17	1.875		1.8		1.8			1.7	0.03
LT 94+10	17	1.875		1.8		1.8			1.7	0.03
LT 94+57	44	1.875				4.6			4.4	0.1
LT 109+42 (TR 1700 E)	114	1.875				12.0		12.0	11.4	0.2
RT 109+45	17	1.875		1.8		1.8			1.7	0.03
RT 112+72	63	1.875			6.6				6.3	0.1
LT 154+85	17	1.875		1.8					1.7	0.03
<u>VERMILION COUNTY SUBTOTAL</u>			3.4	10.7	13.2	45.7	0.0	12.0	56.4	1.1
<u>USE</u>			4.0	11.0	7.0	46.0	0.0	12.0	56.0	1.0
<u>TOTAL QUANTITY</u>			15.0	209.0	28.0	76.0	41.0	205.0	401.0	8.0