

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	.	**	72	23

# SCHEDULE OF QUANTITIES

\* 113(RS-5,BR) & 114RS-2  
 \*\* CHAMPAIGN AND VERMILION  
 CONTRACT NO. 90864

78000200 THERMOPLASTIC PAVEMENT  
MARKING-LINE 4" (WHITE)

VERMILION COUNTY

STATION	TO	STATION	LIN FT
156+50 RT		161+47.62 RT	498.0
156+50 LT		161+47.62 LT	498.0
TURN LANE 160+10.30		162+34.30	124.0
<u>TOTAL</u>			<u>1120.0</u>

78000200 THERMOPLASTIC PAVEMENT  
MARKING-LINE 4" (YELLOW)

VERMILION COUNTY

STATION	TO	STATION	LIN FT
156+00 RT		157+70 RT	170.0
156+50 LT		157+70 LT	120.0
(DOUBLE) 157+70 RT		160+13.40 RT	487.0
(DOUBLE) 160+13.40 RT		161+10.30 RT	194.0
(DOUBLE) 157+70 LT		161+10.30 LT	681.0
(DOUBLE) 161+10.30 LT		162+34.30 LT	248.0
<u>TOTAL</u>			<u>1900.0</u>

78201000 TERMINAL MARKER DIRECT APPLIED

CHAMPAIGN COUNTY

STATION	EACH	
RT 482+68.19	1.0	
LT 483+82.66	1.0	
RT 486+05.60	1.0	
LT 487+20.16	1.0	
RT 535+29	1.0	
RT 538+66	1.0	
LT 539+83	1.0	
RT 543+72	1.0	
LT 544+03	1.0	
RT 546+84	1.0	
LT 547+53	1.0	
<u>TOTAL</u>		<u>11.0</u>

X0301232 SURVEY MARKER VAULT

STATION EACH

CHAMPAIGN COUNTY

CL 515+96 1.0 (PK NAIL & WASHER)

VERMILION COUNTY

3.5" RT 56+16 1.0 (PK NAIL & WASHER)

CHAMPAIGN TOTAL 1.0

VERMILION TOTAL 1.0

TOTAL 2.0

\*X0301741 AERIAL SPEED CHECK MARKING

VERMILION COUNTY

STATION LIN FT

558+64 4.0  
 552+04 4.0

TOTAL 8.0

\*PRIOR TO AERIAL SPEED CHECK MARKING PLACEMENT  
 THE ENGINEER SHALL CONTACT:  
 H. JAY HANNER OF DISTRICT 5 OPERATIONS  
 AT (217)466-7238 FOR COORDINATION WITH  
 ILLINOIS STATE POLICE IN REGARDS TO THE  
 CORRECT PLACEMENT OF THE MARKINGS

X0323115 REFLECTOR MARKER, TYPE A

CHAMPAIGN COUNTY

STATION TO STATION EACH

RT 483+33.195 RT 485+33.195 3.0  
 LT 484+55.16 LT 486+55.16 3.0

TOTAL 6.0

X0324058 OUTLET (SPECIAL)

CHAMPAIGN COUNTY

STATION EACH

LT 3+00.72 1.0  
 RT 804+40.99 1.0

TOTAL 2.0

X3560120 BITUMINOUS CONCRETE BASE COURSE  
WIDENING, SUPERPAVE, 8"

CHAMPAIGN COUNTY

STATION TO STATION SQ. YD.

PARK AVE LT 9+59.43 LT 9+86.7 9.0  
 PARK AVE RT 9+59.55 RT 9+86.7 14.0

TOTAL 23.0

Z0014700 CULVERTS TO BE CLEANED

CHAMPAIGN COUNTY

STATION EACH

RT 4+20 1.0  
 RT 5+28 1.0  
 RT 6+44 1.0

TOTAL 3.0