

CONTRACT NO. 93410

GENERAL NOTES


1. THE LOCATION OF UNDERGROUND UTILITIES SHOWN ON THE PLANS REPRESENTS THE BEST KNOWLEDGE OF THE COUNTY AND THE INDICATED ADJUSTMENTS OR RECONSTRUCTION ARE CONSIDERED TO BE REASONABLY ACCURATE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY, AS DETAILED IN SECTION 563 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, TO VERIFY LOCATIONS OF UNDERGROUND INSTALLATIONS BEFORE STARTING CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL INDEMNIFY THE COUNTY, ITS OFFICERS, AND EMPLOYEES AGAINST ALL CLAIMS DUE TO DAMAGE TO CORPORATE OR PRIVATE PROPERTY RESULTING FROM HIS CONSTRUCTION OPERATIONS AS DESCRIBED IN ARTICLE 107.20 AND 107.26 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
2. THE CONTRACTOR SHALL NOTIFY THE AGENCIES AND UTILITIES AT LEAST 10 (TEN) DAYS PRIOR TO ANY CONSTRUCTION IN THE AREA AND SHALL COMPLY WITH ALL RESTRICTIONS FOR EQUIPMENT MOVEMENTS AND CLEARANCES AS REGARDS TO THEIR FACILITIES.
3. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR MUST CALL J.U.L.I.E. AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, GAS FACILITIES, AND ALL PUBLIC UTILITIES. A 48 HOUR NOTIFICATION IS REQUIRED.
4. WHEN DURING CONSTRUCTION OPERATIONS ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTER OR DRAINAGE STRUCTURES SO THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE BITUMINOUS PAVING.
5. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS IMPROVEMENT.
6. TRAFFIC CONTROL SIGNS REMOVED MUST BE RESET AT THEIR PERMANENT LOCATIONS IN A WORKMANLIKE MANNER AND VISIBLE TO TRAFFIC ON THE ROADWAY. THESE SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH THE 'MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREET AND HIGHWAYS', LATEST EDITION. THE COST OF SUCH WORK SHALL BE INCLUDED IN THE COST OF THE EARTHWORK.
7. WHENEVER IT IS NECESSARY TO REMOVE EXISTING GRAVEL, CRUSHED STONE BASE OR EARTH, IN ORDER TO CONSTRUCT THE BITUMINOUS SHOULDERS, IT SHALL BE INCLUDED IN THE COST OF THE BITUMINOUS SHOULDERS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ADDITIONAL LABOR OR EQUIPMENT REQUIRED.
8. THE NOMINAL THICKNESS FOR THE SURFACE COURSE IS SHOWN ON THE TYPICAL SECTION OR SPECIAL DETAILS. THE CONSTRUCTED THICKNESS OF THE ABOVE ITEMS SHALL NOT BE LESS THAN 90 PER CENT OF THE NOMINAL THICKNESS AT ANY LOCATION.
9. WHERE SECTION OR SUBSECTION STONES OR MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH STONES ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
10. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS SHOWN ON THE TABULATION OF REQUIRED STATE STANDARDS SHOWN IN THE PLANS.
11. ALL PROPOSED PAVEMENT WIDTHS ARE MEASURED EDGE TO EDGE OF PAVEMENT UNLESS OTHERWISE SHOWN ON THE PLANS. INTERSECTION RETURN RADII ARE MEASURED TO THE EDGE OF PAVEMENT.
12. KNOWN UTILITIES LOCATED WITHIN THE LIMITS OF THIS IMPROVEMENT ARE:


FRONTIER COMMUNICATIONS OF SCHUYLER INC. 127 SOUTH CONGRESS STREET P.O. BOX 347 RUSHVILLE, IL 62681	CASS COMMUNICATIONS 100 REDBUD ROAD P.O. BOX 200 VIRGINIA, IL 62691
CITY OF RUSHVILLE WATER RUSHVILLE WATER WORKS 128 LOGAN RUSHVILLE, IL 62681	ADAMS ELECTRIC COOPERATIVE 700 EAST WOOD STREET P.O. BOX 247 CAMP POINT, IL 62320-0247
AMEREN CIPS 700 JERSEY STREET P.O. BOX 1089 QUINCY, IL 62306-1089	HICKORY-KERTON WATER COOPERATIVE 111 WEST WASHINGTON RUSHVILLE, IL 62681

SUMMARY OF QUANTITIES - CONSTRUCTION TYPE CODE 1000			
CODE NO.	PAY ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	137
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2
28000400	PERIMETER EROSION BARRIER	FOOT	160
28000500	INLET AND PIPE PROTECTION	EACH	2
35101400	AGGREGATE BASE COURSE, TYPE B	TON	35
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	47
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,108
40600300	AGGREGATE (PRIME COAT)	TON	118
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTTJOINT	SQ YD	491
40600990	TEMPORARY RAMP	SQ YD	57
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,028
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	183
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,978
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	98,474
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	264
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	539
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	68
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,326
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	98,474
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	264
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	539
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	68
78300100	PAVEMENT MARKING REMOVAL	SQ FT	649
X3550500	BITUMINOUS CONCRETE BASE COURSE, SUPERPAVE 8"	SQ YD	148
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	10,198
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

• SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

LEGEND

 BITUMINOUS SURFACE REMOVAL - BUTT JOINT

 PAVEMENT WIDENING

MIXTURE USES	BIT CONC SURF CSE	BITUMINOUS SHOULDERS
AC/PG	PG 64-22	PG 58-22
DESIGN AIR VOIDS	15%	2%
RAP % (MAX)	4%	15%
MIX COMPOSITION (GRADATION MIXTURE)	SUPERPAVE IL-9.5 OR 12.5	BAM
FRICTION AGGREGATE	MIX "C"	N/A

14. WHENEVER IT IS NECESSARY TO PARTIALLY REMOVE, TRIM, OR GRADE EXISTING DRIVEWAY PAVEMENTS IN ORDER TO CONSTRUCT THE PROPOSED DRIVEWAY PAVEMENTS, IT SHALL BE INCLUDED IN THE COST OF THE BITUMINOUS CONCRETE SURFACE COURSE. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**COUNTY HIGHWAY 1
 GENERAL NOTES, LEGEND,
 SUMMARY OF QUANTITIES,
 SCHEDULE OF QUANTITIES**

DRAWN BY: JCG
 CHECKED BY: JRB
 DATE JULY 27, 2005