

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Y060

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	PARTICIPATING		NON-PART. 100% CITY OF QUINCY WATER & SANITARY
					1000-2A	Y031-1F	
△ 81400400	CONCRETE HANDHOLE		EACH	4		4	
△ 81400600	CONCRETE DOUBLE HANDHOLE		EACH	1		1	
△ 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	335		335	
△ 81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10		FOOT	503		503	
△ 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE		EACH	1		1	
△ 84200700	LIGHTING FOUNDATION REMOVAL	*	EACH	1		1	
△ 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C		FOOT	1539		1539	
△ 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C		FOOT	500		500	
△ 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C		FOOT	1462		1462	
△ 87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C		FOOT	696		696	
△ 87301705	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3 PAIR		FOOT	495		495	
△ 87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR		FOOT	940		940	
△ 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C		FOOT	31		31	
△ 87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.		EACH	4		4	
△ 87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II		EACH	3		3	
△ 87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.		EACH	1		1	
△ 87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.		EACH	2		2	
△ 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.		EACH	1		1	
△ 87800100	CONCRETE FOUNDATION, TYPE A		FOOT	12		12	
△ 87800200	CONCRETE FOUNDATION, TYPE D		FOOT	3		3	
△ 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER		FOOT	54		54	
△ 87900200	DRILL EXISTING HANDHOLE	*	EACH	1		1	
△ 88200100	TRAFFIC SIGNAL BACKPLATE		EACH	18		18	
△ 88800100	PEDESTRIAN PUSH-BUTTON		EACH	8		8	
△ 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION		EACH	1		1	
△ 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT		FOOT	534		534	
△ 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	*	EACH	1		1	
△ 89502380	REMOVE EXISTING HANDHOLE	*	EACH	3		3	
△ 89502385	REMOVE EXISTING CONCRETE FOUNDATION	*	EACH	6		6	
△ X0320872	VIDEO VEHICLE DETECTION SYSTEM	*	EACH	1		1	
X0323889	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 18"	*	FOOT	46	46		
X4066514	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	*	TON	966	966		
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	*	TON	168	168		
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	*	TON	2941	2941		
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	*	TON	77	77		
△ X8440102	RELOCATE EXISTING LUMINAIRE	*	EACH	2		2	
△ X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	*	EACH	3		3	
△ X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	*	EACH	2		2	
△ X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	*	EACH	1		1	
△ X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	*	EACH	4		4	
△ X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	*	EACH	3		3	
△ X8801447	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	*	EACH	1		1	
△ X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	*	EACH	6		6	
△ X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	*	EACH	1		1	
△ XX003162	EMERGENCY VEHICLE PRIORITY SYSTEM DETECTOR UNIT	*	EACH	2		2	
△ XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	*	EACH	1		1	
△ XX004683	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER AND CABINET COMPLETE	*	EACH	1		1	
XX004900	TURF REINFORCEMENT MAT	*	SQ YD	357	357		
XX004934	STORM SEWERS, DUCTILE IRON (WATER MAIN REQUIREMENTS) 12"	*	FOOT	46	46		
XX005396	BIAXIAL GEOGRID	*	SQ YD	10746	10746		
△ XX006035	CASING PIPE 16"	*	FOOT	20		20	
Z0013798	CONSTRUCTION LAYOUT	*	L SUM	1	1		
△ Z0060900	SANITARY SEWER, TYPE 3 8"	*	FOOT	80		80	

△ SPECIALTY ITEMS

REVISIONS	
NAME	DATE
TITLE BLOCK - SEB	9/26/05
PAY ITEM - SEB	9/26/05
PAY ITEM - SEB	1/10/06
ROW COM - SEB	3/6/06

SUMMARY OF QUANTITIES
 SHEET 3 OF 4
 FAU 7814 (HARRISON STREET)
 SECTION 05-00186-01-PV
 ADAMS COUNTY

SCALE: NONE DRAWN BY SEB
 DATE 9/12/05 CHECKED BY SRW

3/6/2006 P:\B\F\user\0324\Construction\1\03_2429_044_Signage.dwg