

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

NE 1/4 SEC 7, T25, R8W, 4TH PM

NW 1/4 SEC 8, T25, R8W, 4TH PM

NORMA J. JOHNSON

HAROLD R. & ALICE ROMAINE STROOT

SEE SHEET 31 FOR INTERSECTION STATION, OFFSETS AND ELEVATIONS

MATCH LINE STA 2265+50 (SHEET 24)

MATCH LINE STA 2262+00 (SHEET 23)

MATCH LINE STA 202+00 (SHEET 18)

BITUMINOUS SURFACE REMOVAL, 1/2"

END B-6.24 CURB & GUTTER STA 2265+15.00

PAVEMENT REMOVAL STA 2264+72.00 TO 2265+15.00

CURB & GUTTER REMOVAL SW RAMP TY B

PCC SW 4"

SW RAMP TY B

B-6.24

2264+35.00 55.00' RT

CONSTRUCTION LIMITS

200+10.00 40.00' LT

201+78.16 40.00' LT

PR ROW

POT STA 2263+73.98 (FAU 7830) = PI STA 100+00.00 (FAU 7814) BK = PI STA 200+00.00 (FAU 7814) AH

PCC SW 4"

10' TRANSITION

B-6.18

FAU 7814 (HARRISON ST)

FAU 7814 (HARRISON ST)

10' TRANSITION

B-6.18

BEGIN IMPROVEMENT STA 96+90.52 PCC SIDEWALK, 4"

CURB & GUTTER REMOVAL

SW RAMP TY B

B-6.24

201+10.00 40.00' RT

201+78.16 40.00' RT

CONSTRUCTION LIMITS

SIDWALK REMOVAL, TRANSITION PCC SW TO 6' WIDTH

BEGIN RETAINING WALL STA 96+98.0

RETAINING WALL WITH PEDESTRIAN RAILING SEE SHEET 41

END RETAINING WALL STA 97+84.1

SW RAMP TY A

B-6.24

BEGIN B-6.24 CURB & GUTTER STA 2262+97.48

PAVEMENT REMOVAL STA 2262+73.48 TO 2263+10.00

OUTLET FOR C&G TY B-6.24 (STD 606006)

3' AGG SHOULDER, TY B

HARRISON CURVE #1 DATA

PI STA = 205+34.20

Δ = 53°55'06" RT

D = 8°11'06"

R = 700.00'

T = 356.04'

L = 658.74'

E = 85.34'

SE = RC (2.0%)

PC STA = 201+78.16

PRC STA = 208+36.89

SE ATTAINED STA 201+42 TO STA 201+96

SE REMOVED STA 207+83 TO STA 208+37

HAROLD R. & ALICE ROMAINE STROOT

GRAPHIC SCALE (IN FEET)

REVISIONS		
NAME	DATE	
TITLE BLOCK - SEB	9/26/05	
ADDED INLET - SEB	1/10/06	
ROW COMM. - SEB	3/6/06	

HARRISON - PLAN

STA 96+00 TO STA 202+00

FAU 7814 (HARRISON STREET)

SECTION 05-00186-01-PV

ADAMS COUNTY

SCALE: 1"=20'

DATE: 9/12/05

DRAWN BY: SEB

CHECKED BY: SRW

BM #11

CHISELED "□" IN WEST END OF SOUTH HEADWALL

ELEV = 648.46

█ = PVMT, SW, AND C&G REMOVAL

MILDRED R. & WILLIAM ANDERS GARY ANDERS

3/6/2006

P:\Bentley\Drawings\042314\05-00186-01-PV\03413.dwg