



COUNTY	ROUTE	SECTION	TOTAL SHEETS	SHEET NO.
ADAMS	FAS 589	06-00195-00-RS	16	9

STATION 200+00 TO STATION 240+00
PROJECT NO. RS-589(103)

CURVE DATA
 PI STA. 206+36.5
 $\Delta=29^{\circ}22'$
 D=4'00"
 T=375.4'
 R=1,432.7'
 L=734.2'
 E=48.37'
 PC STA. 202+61.1
 PT STA. 209+95.3
 SE=0.060 FT./FT.
 ATTN: STA. 201+85.7 TO STA. 203+36.5
 REMD: STA. 209+19.9 TO STA. 210+70.7 (208+54.2)

252 TON LEVELING BINDER
 (MACHINE METHOD), SUPERPAVE N50
 TO FIX SUPERELEVATION DEFICIENCIES

