

SUMMARY OF QUANTITIES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 7989	*	SANGAMON	7	2
STA.	TO	STA.		
	ILLINOIS		93419	

* 04-00441-00-TL

CODE NO.	ITEM	UNITS	TOTAL QUANTITY
* 42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ. FT.	446
△ 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	86
* 44000600	SIDEWALK REMOVAL	SQ. FT.	462
* 44000900	BITUMINOUS CONCRETE REMOVAL	SQ. YD.	66
△ 60604400	COMBINATION, CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	128
67100100	MOBILIZATION	L. SUM.	1
* 70103700	TRAFFIC CONTROL COMPLETE	L. SUM.	1
72000100	SIGN PANEL - TYPE I	SQ. FT.	36
* 80501000	SERVICE INSTALLATION, SPECIAL	EACH	1
* 81012500	CONDUIT IN TRENCH, 1-1/2" DIA., PVC	FOOT	449
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	6
* 81012700	CONDUIT IN TRENCH, 2-1/2" DIA., PVC	FOOT	4
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	37
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	16
* 81021540	CONDUIT AUGERED, 1-1/2" DIA., PVC	FOOT	345
* 81021550	CONDUIT AUGERED, 2" DIA., PVC	FOOT	36
* 81021560	CONDUIT AUGERED, 2-1/2" DIA., PVC	FOOT	25
* 81021570	CONDUIT AUGERED, 3" DIA., PVC	FOOT	114
* 81021590	CONDUIT AUGERED, 4" DIA., PVC	FOOT	76
* 81306100	JUNCTION BOX, (SPECIAL)	EACH	3
81400400	CONCRETE HANDHOLE	EACH	4
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	512
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250WATT	EACH	2
* 85700200	FULL-ACTUATED CONTROLLER, AND TYPE IV CABINET	EACH	1
* 86400100	TRANSCEIVER-FIBER OPTIC	EACH	1
* 87100110	FIBER OPTIC CABLE IN CONDUIT, 62.5/125 6F	FOOT	914
* 87301125	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12, 3C	FOOT	398
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 3C	FOOT	529
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 5C	FOOT	335
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 7C	FOOT	714
* 87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 9C	FOOT	324
* 87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 12C	FOOT	405
* 87301525	ELECTRIC CABLE IN CONDUIT, LEAD IN, NO. 18, 6 PAIR	FOOT	689
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6. 2C	FOOT	64
87502680	TRAFFIC SIGNAL POST, ALUMINUM, 14 FT.	EACH	2
87502700	TRAFFIC SIGNAL POST, ALUMINUM, 16 FT.	EACH	2
87700170	STEEL, MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1
87700200	STEEL, MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1
* 87702860	STEEL COMBINATION, MAST ARM ASSEMBLY AND POLE, 26 FT	EACH	1
* 87702890	STEEL COMBINATION, MAST ARM ASSEMBLY AND POLE, 32 FT	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E, 30 INCH DIAMETER	FOOT	47
87900200	DRILL EXISTING HANDHOLE	EACH	1
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	15
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8
* X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	1
* X0322929	CAMERA MOUNTING ASSEMBLY	EACH	4
* X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	3402
* X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE 3-SECTION, BRACKET MOUNTED	EACH	4
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE 3-SECTION, MAST ARM MOUNTED	EACH	6
* X8801415	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE 3-SECTION, BRACKET MOUNTED	EACH	4
* XX006533	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED, COUNTDOWN TIMER	EACH	6
* XX006558	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED, COUNTDOWN TIMER	EACH	1

* - SEE SPECIAL PROVISIONS
 △ - SPECIALTY ITEMS

CONSTRUCTION TYPE CODE: Y031 - 1F

SECTION 04-00441-00-TL
 SOUTH GRAND AVE. AND WHEELER AVE.
 TRAFFIC SIGNALS INSTALLATION
SUMMARY OF QUANTITIES

CITY OF SPRINGFIELD, ILLINOIS
 OFFICE OF PUBLIC WORKS
 TRAFFIC ENGINEERING