


district
 3/3/2006
 c:\projects\94867\d\05503pa.dgn


FAP SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	121RS-3 122RS-4	JASPER	31	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94867

SUMMARY OF QUANTITIES			90% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	253	253	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18098	18098	
40600300	AGGREGATE (PRIME COAT)	TON	291	291	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	427	427	
40600990	TEMPORARY RAMP	SQ YD	64	64	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	180600	180600	
44004250	PAVED SHOULDER REMOVAL	SQ YD	200	200	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	3300	3300	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	394	394	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	313	313	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7251	7251	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	200	200	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21838	21838	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	121968	121968	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	400	400	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1820	1820	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	121968	121968	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	400	400	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	688	688	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	16716	16716	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	6088	6088	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	252	252	

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY
OF
QUANTITIES**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY