

district
 teasleyck+*_DATE_
 c:\projects\94867d\05503pa.dgn
 SCH

RESURFACING SCHEDULE

STATION TO STATION	LENGTH LIN FT	EXISTING PAVEMENT WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	BITUMINOUS SURFACE COURSE, SUPERPAVE, MIX "C", N70, 1/2" TON	LEVEL BINDER, MACHINE METHOD SUPERPAVE, N70, 3/4" TON	BITUMINOUS SURFACE REMOVAL - BUTT JOINT SQ YD	BITUMINOUS SURFACE REMOVAL, 2 1/4 SQ YD	AGGREGATE SHOULDERS, TYPE B TON	TEMPORARY RAMP SQ YD
40+00.00 TO 40+30.00	30.00	50	167	17	0	15	6	167		4	24
40+30.00 TO 41+90.90	160.90	30	536	54	1	50	18		536	22	
41+90.90 TO 50+35.90	845.00	30	2817	282	5	260	95		2817	114	
50+35.90 = 50+89.10											
50+89.10 TO 99+29.77	4840.67	30	16136	1614	26	1493	542		16136	651	
99+29.77 TO 99+59.77	30.00	30	100	10	0	7	3	80	100	4	13
99+59.77 TO 99+79.77	20.00	30	67	7	0	6	2		13	3	
99+79.77 TO 101+03.23	123.46	30	BRIDGE OMISSION		1						
101+03.23 TO 101+23.23	20.00	30	67	7	0	6	2		13	3	
101+23.23 TO 101+53.23	30.00	30	100	10	0	7	3	80	100	4	13
101+53.23 TO 132+03.20	3049.97	30	10167	1017	16	941	342		10167	410	
132+03.20 = 132+08.40											
132+08.40 TO 135+61.10	352.70	30	1176	118	2	109	40		1176	47	
135+61.10 = 135+79.50											
135+79.50 TO 245+33.80	10954.30	30	36514	3651	58	3374	1227		36514	1473	
245+33.80 = 245+33.60											
245+33.60 TO 251+20.00	586.40	30	1955	196	3	181	66		1955	79	
251+20.00 TO 256+20.00	500.00	42	2333	233	4	210	84		2333	47	
256+20.00 TO 293+63.80	3743.80	30	12479	1248	20	1153	419		12479	503	
293+63.80 = 293+72.40											
293+72.40 TO 371+16.20	7743.80	30	25813	2581	41	2385	867		25813	1041	
371+16.20 TO 379+44.50	828.30	30	2761	276	4	255	93		2761	111	
379+44.50 = 379+57.80											
379+57.80 TO 582+64.00	20306.20	30	67687	6769	108	6254	2274		67687	2730	
582+64.00 TO 582+94.00	30.00	30	100	10	0	9	3	100		4	13
PROJECT TOTALS	54195.50		180973	18098	291	16716	6088	427	180600	7251	64

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	121RS-3 122RS-4	JASPER	31	7
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT NO.	CONTRACT NO. 94867	

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH FEET	SHORT TERM PAVEMENT MARKING FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	PAINT PAVEMENT MARKING - LINE 4" FT	RAISED REFLECTIVE PAVEMENT MARKER EACH	TEMPORARY PAINT PAVEMENT MARKING LINE 4" FT	PAINT PAVEMENT MARKING - LINE 6" FT	TEMPORARY PAINT PAVEMENT MARKING LINE 6" FT	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS SQ FT	PAINT PAVEMENT MARKING - LETTERS & SYMBOLS SQ FT
40+00.00 TO 40+30.00	30.0	12	1	68	0	68				
40+30.00 TO 41+90.90	160.9	64	5	362	2	362				
41+90.90 TO 50+35.90	845.0	338	28	1551	11	1551				
50+35.90 = 50+89.10										
50+89.10 TO 99+24.77	4835.7	1934	161	10215	60	10215				
99+24.77 TO 99+59.77	35.0	14	1	79	0	79				
99+59.77 TO 99+79.77	20.0	8	1	45	0	45				
99+79.77 TO 101+03.23	123.5	49	4	278	2	278				
101+03.23 TO 101+23.23	20.0	8	1	45	0	45				
101+23.23 TO 101+58.23	35.0	14	1	79	0	79				
101+58.23 TO 132+03.20	3045.0	1218	102	7863	38	7863				
132+03.20 = 132+08.40										
132+08.40 TO 135+61.10	352.7	141	12	794	4	794				
135+61.10 = 135+79.50										
135+79.50 TO 245+33.80	10954.3	4382	365	25451	137	25451				
245+33.80 = 245+33.60										
245+33.60 TO 251+20.00	586.4	288	24	1132	11	1132	134	134		
251+20.00 TO 256+20.00	500.0	306	26	1480	13	1480	266	266	78	78
256+20.00 TO 293+63.80	3743.8	1498	125	8383	47	8383				
293+63.80 = 293+72.40										
293+72.40 TO 371+16.20	7743.8	3098	258	17114	97	17114				
371+16.20 TO 379+44.50	828.3	331	28	1864	10	1864				
379+44.50 = 379+57.80										
379+57.80 TO 582+64.00	20306.2	8123	677	45099	254	45099				
582+64.00 TO 582+94.00	30.0	12	1	68	0	68				
PROJECT TOTALS	54195.5	21838	1820	121968	688	121968	400	400	78	78

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**RESURFACING &
 PAVEMENT MARKING
 SCHEDULES**
 SCALE: VERT.
 DATE: _____ HORIZ.
 DRAWN BY _____
 CHECKED BY _____